Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no. 15		Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specification and directions of the Engineer in charge.										
		Defence Colony										
		6th Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.95	5.20	5.08		76.13		
15.00	30.00		Sqm	1	15.00	5.20	5.20	5.20		78.00		
30.00	40.10		Sqm	1	10.10	5.20	5.50	5.35		54.04		
40.10	43.70		Sqm	1	3.60	4.32	4.75	4.54		16.33		
43.70	45.00		Sqm	1	1.30	5.28	5.20	5.24		6.81		
45.00	60.00		Sqm	1	15.00	5.20	4.90	5.05		75.75		
60.00	75.00		Sqm	1	15.00	4.90	5.50	5.20		78.00		
75.00	90.00		Sqm	1	15.00	5.50	5.10	5.30		79.50		
90.00	105.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
105.00	110.80		Sqm	1	5.80	5.00	5.10	5.05		29.29		
		8th Main Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.40	4.45	4.43		66.38		
15.00	30.00		Sqm	1	15.00	4.45	4.90	4.68		70.13		
30.00	45.00		Sqm	1	15.00	4.95	5.10	5.03		75.38		
45.00	60.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
60.00	75.00		Sqm	1	15.00	4.95	5.10	5.03		75.38		
75.00	90.00		Sqm	1	15.00	5.10	5.05	5.08		76.13		
90.00	105.00		Sqm	1	15.00	4.95	5.20	5.08		76.13		
105.00	120.00		Sqm	1	15.00	5.20	5.05	5.13		76.88		
120.00	131.00		Sqm	1	11.00	4.95	4.95	4.95		54.45		
		Cross Road 2										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.25	4.10	4.18		62.63		
15.00	30.00		Sqm	1	15.00	4.10	4.00	4.05		60.75		
30.00	31.50		Sqm	1	1.50	4.00	4.00	4.00		6.00		
		Cross Road 1										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.40	4.48	4.44		66.60		
15.00	29.50		Sqm	1	14.50	4.48	4.65	4.57		66.19		
		Nithish Central Park Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.80	5.40	5.60		84.00		
15.00	21.40		Sqm	1	6.40	5.40	5.70	5.55		35.52		
21.40	29.60		Sqm	1	8.20	5.05	4.80	4.93		40.39		
29.60	30.00		Sqm	1	0.40	5.52	5.50	5.51		2.20		
30.00	45.00		Sqm	1	15.00	5.50	5.15	5.33		79.88		
45.00	60.00		Sqm	1	15.00	5.15	5.15	5.15		77.25		
60.00	75.00		Sqm	1	15.00	5.15	5.04	5.10		76.43		
75.00	80.00		Sqm	1	5.00	5.04	6.00	5.52		27.60		
80.00	83.70		Sqm	1	3.70	6.00	5.95	5.98		22.11		
83.70	87.60		Sqm	1	3.90	5.30	5.30	5.30		20.67		
87.60	93.20		Sqm	1	5.60	6.30	6.20	6.25		35.00		
93.20	96.20		Sqm	1	3.00	5.40	5.00	5.20		15.60		
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.80	5.30	5.05		75.75		
15.00	22.80		Sqm	1	7.80	5.30	5.40	5.35		41.73		
22.80	32.00		Sqm	1	9.20	4.95	4.80	4.88		44.85		
32.00	45.00		Sqm	1	13.00	4.75	5.03	4.89		63.57		
45.00	60.00		Sqm	1	15.00	5.03	4.95	4.99		74.85		
60.00	75.00		Sqm	1	15.00	4.95	5.30	5.13		76.88		
75.00	90.00		Sqm	1	15.00	4.95	5.45	5.20		78.00		
90.00	95.10		Sqm	1	5.10	5.45	5.65	5.55		28.31		
		Deducation										
		Chamber	Sqm	-1	1.90			1.40		-2.66		
		Tree Pot	Sqm	-9	0.20			0.10		-0.18		
		Electric Pole	Sqm	-1	0.90			0.50		-0.45		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Man Hole (1m Dia)	Sqm	-1	Area = 0.25*3.142*1^2=0.785					-0.79		
		7th Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.35	4.06	4.21		63.08		
15.00	17.40		Sqm	1	2.40	4.06	4.25	4.16		9.97		
17.40	26.70		Sqm	1	9.30	5.05	5.20	5.13		47.66		
26.70	41.70		Sqm	1	15.00	4.10	4.10	4.10		61.50		
41.70	45.10		Sqm	1	3.40	4.10	3.75	3.93		13.35		
45.10	60.00		Sqm	1	14.90	5.10	5.10	5.10		75.99		
60.00	75.00		Sqm	1	15.00	5.10	5.17	5.14		77.03		
75.00	83.70		Sqm	1	8.70	5.17	5.00	5.09		44.24		
83.70	98.70		Sqm	1	15.00	4.35	4.00	4.18		62.63		
98.70	100.40		Sqm	1	1.70	4.00	4.00	4.00		6.80		
100.40	104.10		Sqm	1	3.70	5.10	5.10	5.10		18.87		
		2nd Cross										
		(From North to South)										
4.00	11.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
17.00	27.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
34.00	41.00		Sqm	1	7.00	1.60	1.60	1.60		11.20		
48.00	56.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
61.00	67.00		Sqm	1	6.00	1.20	1.20	1.20		7.20		
71.00	78.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
82.00	88.00		Sqm	1	6.00	2.10	2.10	2.10		12.60		
92.00	96.40		Sqm	1	4.40	1.10	1.10	1.10		4.84		
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	6.50	5.40	5.95		89.25		
15.00	25.40		Sqm	1	10.40	5.40	6.00	5.70		59.28		
		8th Main Road										
		North to South										
6.00	8.00		Sqm	1	2.00	1.10	1.10	1.10		2.20		
12.00	16.00		Sqm	1	4.00	1.30	1.30	1.30		5.20		
26.00	29.00		Sqm	1	3.00	1.00	1.00	1.00		3.00		
42.00	47.00		Sqm	1	5.00	1.20	1.20	1.20		6.00		
88.00	93.00		Sqm	1	5.00	0.90	0.90	0.90		4.50		
		Vinayak Nagar										
		6th B Main Road										
		North to South										
8.00	11.00		Sqm	1	3.00	1.30	1.30	1.30		3.90		
55.00	59.00		Sqm	1	4.00	1.40	1.40	1.40		5.60		
63.00	67.00		Sqm	1	4.00	1.20	1.20	1.20		4.80		
76.00	79.00		Sqm	1	3.00	0.85	0.85	0.85		2.55		
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.80	5.80	5.30		79.50		
15.00	30.00		Sqm	1	15.00	5.80	5.30	5.55		83.25		
30.00	45.00		Sqm	1	15.00	5.30	6.15	5.73		85.88		
45.00	60.00		Sqm	1	15.00	6.15	6.48	6.32		94.73		
60.00	65.80		Sqm	1	5.80	6.48	6.49	6.49		37.61		
		11th Cross Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.20	4.10	4.15		62.25		
15.00	30.00		Sqm	1	15.00	4.10	3.80	3.95		59.25		
30.00	45.00		Sqm	1	15.00	3.80	3.65	3.73		55.88		
45.00	60.00		Sqm	1	15.00	3.65	4.00	3.83		57.38		
60.00	70.00		Sqm	1	10.00	4.00	4.10	4.05		40.50		
70.00	75.00		Sqm	1	5.00	4.10	4.00	4.05		20.25		
75.00	90.00		Sqm	1	15.00	4.00	4.64	4.32		64.80		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
90.00	105.00		Sqm	1	15.00	4.64	4.90	4.77		71.55		
105.00	120.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
120.00	135.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
135.00	150.00		Sqm	1	15.00	4.90	5.00	4.95		74.25		
150.00	165.00		Sqm	1	15.00	5.00	4.90	4.95		74.25		
165.00	168.00		Sqm	1	3.00	4.90	4.75	4.83		14.48		
		10th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.35	5.30	5.33		79.88		
15.00	30.00		Sqm	1	15.00	5.30	5.10	5.20		78.00		
30.00	45.00		Sqm	1	15.00	5.10	4.40	4.75		71.25		
45.00	60.00		Sqm	1	15.00	4.40	4.50	4.45		66.75		
60.00	75.00		Sqm	1	15.00	4.50	4.60	4.55		68.25		
75.00	90.00		Sqm	1	15.00	4.60	4.48	4.54		68.10		
90.00	105.00		Sqm	1	15.00	4.48	4.84	4.66		69.90		
105.00	108.60		Sqm	1	3.60	4.84	4.85	4.85		17.44		
108.60	117.40		Sqm	1	8.80	5.35	4.80	5.08		44.66		
117.40	120.00		Sqm	1	2.60	4.50	4.60	4.55		11.83		
120.00	135.00		Sqm	1	15.00	4.60	4.49	4.55		68.18		
135.00	150.00		Sqm	1	15.00	4.49	4.67	4.58		68.70		
150.00	165.00		Sqm	1	15.00	4.67	4.55	4.61		69.15		
165.00	167.60		Sqm	1	2.60	4.55	4.90	4.73		12.29		
		10th A Cross										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.00	5.75	5.88		88.13		
15.00	30.00		Sqm	1	15.00	5.75	5.40	5.58		83.63		
30.00	45.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
45.00	60.00		Sqm	1	15.00	5.40	5.10	5.25		78.75		
60.00	75.00		Sqm	1	15.00	5.10	5.35	5.23		78.38		
75.00	90.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
90.00	105.00		Sqm	1	15.00	5.55	6.00	5.78		86.63		
105.00	120.00		Sqm	1	15.00	6.00	6.10	6.05		90.75		
120.00	134.70		Sqm	1	14.70	6.10	6.20	6.15		90.40		
		10th A Cross										
		(From West to East)										
0.00	2.80		Sqm	1	2.80	4.80	4.50	4.65		13.02		
		2nd Main Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	8.80	8.70	8.75		131.25		
15.00	30.00		Sqm	1	15.00	8.70	9.13	8.92		133.73		
30.00	45.00		Sqm	1	15.00	9.13	8.50	8.82		132.23		
45.00	60.00		Sqm	1	15.00	8.50	8.40	8.45		126.75		
60.00	75.00		Sqm	1	15.00	8.40	8.55	8.48		127.13		
75.00	90.00		Sqm	1	15.00	8.55	8.10	8.33		124.88		
90.00	105.00		Sqm	1	15.00	8.10	7.60	7.85		117.75		
105.00	114.30		Sqm	1	9.30	7.60	8.00	7.80		72.54		
114.30	129.30		Sqm	1	15.00	8.00	7.45	7.73		115.88		
129.30	144.30		Sqm	1	15.00	7.45	6.85	7.15		107.25		
144.30	159.30		Sqm	1	15.00	6.85	6.80	6.83		102.38		
159.30	174.30		Sqm	1	15.00	6.80	6.90	6.85		102.75		
174.30	189.30		Sqm	1	15.00	6.90	7.65	7.28		109.13		
189.30	192.60		Sqm	1	3.30	7.65	7.40	7.53		24.83		
0.00	2.60	Cut Portion	Sqm	1	2.60	2.10	2.10	2.10		5.46		
		2nd Main Road To M S Nagar Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	5.10	4.36	4.73		70.95		
15.00	30.00		Sqm	1	15.00	4.36	4.40	4.38		65.70		
30.00	33.70		Sqm	1	3.70	4.40	4.60	4.50		16.65		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		(From South to North)										
0.00	15.00		Sqm	1	15.00	5.45	5.20	5.33		79.88		
15.00	30.00		Sqm	1	15.00	5.20	5.40	5.30		79.50		
30.00	45.00		Sqm	1	15.00	5.40	5.70	5.55		83.25		
45.00	60.00		Sqm	1	15.00	5.70	5.25	5.48		82.13		
60.00	75.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
75.00	90.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
90.00	105.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
105.00	120.00		Sqm	1	15.00	5.40	5.58	5.49		82.35		
120.00	135.00		Sqm	1	15.00	5.58	5.40	5.49		82.35		
135.00	150.00		Sqm	1	15.00	5.40	5.35	5.38		80.63		
150.00	165.00		Sqm	1	15.00	5.35	5.20	5.28		79.13		
165.00	180.00		Sqm	1	15.00	5.20	5.20	5.20		78.00		
180.00	195.00		Sqm	1	15.00	5.20	5.54	5.37		80.55		
195.00	197.80		Sqm	1	2.80	5.54	6.40	5.97		16.72		
		(From East to West)										
0.00	15.00		Sqm	1	15.00	3.90	3.65	3.78		56.63		
15.00	30.00		Sqm	1	15.00	3.65	3.68	3.67		54.98		
30.00	45.00		Sqm	1	15.00	3.68	3.98	3.83		57.45		
45.00	49.80		Sqm	1	4.80	3.98	4.20	4.09		19.63		
49.80	51.90		Sqm	1	2.10	4.20	7.50	5.85		12.29		
		3A Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	3.85	3.63	3.74		56.10		
15.00	30.00		Sqm	1	15.00	3.63	3.63	3.63		54.45		
30.00	41.40		Sqm	1	11.40	3.63	4.32	3.98		45.32		
41.40	44.50		Sqm	1	3.10	4.32	7.35	5.84		18.09		
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.10	3.60	3.85		57.75		
15.00	18.60		Sqm	1	3.60	3.60	3.65	3.63		13.05		
		5th Cross Road										
		(From North to South)										
0.00	3.40		Sqm	1	3.40	8.20	6.80	7.50		25.50		
3.40	15.00		Sqm	1	11.60	6.80	6.70	6.75		78.30		
15.00	30.00		Sqm	1	15.00	6.70	6.10	6.40		96.00		
30.00	45.00		Sqm	1	15.00	6.10	6.20	6.15		92.25		
45.00	56.60		Sqm	1	11.60	6.20	6.15	6.18		71.63		
		Cut Portion										
0.00	12.10		Sqm	1	12.10	2.40	2.40	2.40		29.04		
		Hegde Nagara										
		Win Field Garden										
		5th Cross Road (W1941)										
		(From South to North)										
0.00	2.70		Sqm	1	2.70	10.80	7.45	9.13		24.64		
2.70	15.00		Sqm	1	12.30	7.45	6.70	7.08		87.02		
15.00	30.00		Sqm	1	15.00	6.70	6.65	6.68		100.13		
30.00	45.00		Sqm	1	15.00	6.65	7.00	6.83		102.38		
45.00	60.00		Sqm	1	15.00	7.00	7.50	7.25		108.75		
60.00	75.00		Sqm	1	15.00	7.50	7.00	7.25		108.75		
75.00	90.00		Sqm	1	15.00	7.00	7.00	7.00		105.00		
90.00	105.00		Sqm	1	15.00	7.00	6.85	6.93		103.88		
105.00	120.00		Sqm	1	15.00	6.85	6.25	6.55		98.25		
120.00	135.00		Sqm	1	15.00	6.25	7.05	6.65		99.75		
135.00	150.00		Sqm	1	15.00	7.05	7.05	7.05		105.75		
150.00	165.00		Sqm	1	15.00	7.05	7.05	7.05		105.75		
165.00	180.00		Sqm	1	15.00	7.05	7.05	7.05		105.75		
180.00	185.20		Sqm	1	5.20	7.05	7.40	7.23		37.57		
185.20	188.00		Sqm	1	2.80	7.00	12.00	9.50		26.60		
188.00	190.50		Sqm	1	2.50	8.00	7.90	7.95		19.88		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		6th Cross Road (W1935)										
		(From South to North)										
			Sqm	1	2.00	7.50	5.90	6.70		13.40		
0.00	2.00		Sqm	1	13.00	5.90	5.95	5.93		77.03		
2.00	15.00		Sqm	1	15.00	5.95	6.00	5.98		89.63		
15.00	30.00		Sqm	1	15.00	6.00	5.50	5.75		86.25		
30.00	45.00		Sqm	1	15.00	5.50	5.35	5.43		81.38		
45.00	60.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
60.00	75.00		Sqm	1	15.00	5.55	5.55	5.55		83.25		
75.00	90.00		Sqm	1	15.00	5.55	5.60	5.58		83.63		
90.00	105.00		Sqm	1	15.00	5.60	5.60	5.60		84.00		
105.00	120.00		Sqm	1	15.00	5.60	5.75	5.68		85.13		
120.00	135.00		Sqm	1	15.00	5.75	4.85	5.30		79.50		
135.00	150.00		Sqm	1	15.00	4.85	4.80	4.83		72.38		
150.00	165.00		Sqm	1	15.00	4.80	6.10	5.45		81.75		
165.00	180.00		Sqm	1	1.50	6.10	5.40	5.75		8.63		
180.00	181.50											
		9th Cross Road										
		(From South to North)										
			Sqm	1	2.80	6.90	4.90	5.90		16.52		
0.00	2.80		Sqm	1	13.10	4.90	4.40	4.65		60.92		
2.80	15.90		Sqm	1	14.10	4.00	5.45	4.73		66.62		
15.90	30.00		Sqm	1	15.00	5.45	5.60	5.53		82.88		
30.00	45.00		Sqm	1	15.00	5.50	5.70	5.60		84.00		
45.00	60.00		Sqm	1	15.00	5.70	5.00	5.35		80.25		
60.00	75.00		Sqm	1	4.90	5.00	5.10	5.05		24.75		
75.00	79.90		Sqm	1	9.70	4.60	4.60	4.60		44.62		
79.90	89.60		Sqm	1	0.40	4.60	5.95	5.28		2.11		
89.60	90.00		Sqm	1	15.00	5.95	5.75	5.85		87.75		
90.00	105.00		Sqm	1	11.70	5.75	5.60	5.68		66.40		
105.00	116.70		Sqm	1	10.20	4.60	4.85	4.73		48.20		
116.70	126.90		Sqm	1	11.00	5.70	5.80	5.75		63.25		
126.90	137.90											
		MSR Mansion Road										
		(North to South)										
			Sqm	1	5.80	5.75	7.15	6.45		37.41		
0.00	5.80		Sqm	1	3.90	10.70	8.40	9.55		37.25		
5.80	9.70		Sqm	1	5.30	8.40	8.25	8.33		44.12		
9.70	15.00		Sqm	1	15.00	8.25	7.40	7.83		117.38		
15.00	30.00		Sqm	1	15.00	7.40	6.85	7.13		106.88		
30.00	45.00		Sqm	1	5.00	6.85	7.10	6.98		34.88		
45.00	50.00											
		Nisarga Layout										
		7th Cross, Zayan Travels Car Service Centre Road, North To South										
			Sqm	1	15.00	5.00	4.85	4.93		73.88		
0.00	15.00		Sqm	1	15.00	4.85	4.60	4.73		70.88		
15.00	30.00		Sqm	1	15.00	4.60	5.15	4.88		73.13		
30.00	45.00		Sqm	1	15.00	5.15	5.00	5.08		76.13		
45.00	60.00		Sqm	1	15.00	5.00	5.10	5.05		75.75		
60.00	75.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
75.00	90.00		Sqm	1	11.50	5.00	4.70	4.85		55.78		
90.00	101.50											
		West To East										
			Sqm	1	15.00	4.90	4.80	4.85		72.75		
0.00	15.00		Sqm	1	0.70	4.80	4.80	4.80		3.36		
15.00	15.70		Sqm	1	14.30	5.30	5.60	5.45		77.94		
15.70	30.00		Sqm	1	15.00	5.60	5.15	5.38		80.63		
30.00	45.00		Sqm	1	1.70	5.15	5.15	5.15		8.76		
45.00	46.70		Sqm	1	4.90	4.15	3.95	4.05		19.85		
46.70	51.60		Sqm	1	4.60	5.30	5.25	5.28		24.27		
51.60	56.20		Sqm	1	8.40	4.20	4.30	4.25		35.70		
56.20	64.60		Sqm	1	10.40	5.30	5.35	5.33		55.38		
64.60	75.00		Sqm	1	1.60	5.35	5.36	5.36		8.57		
75.00	76.60											

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		5th Cross Road, North To South										
0.00	11.10		Sqm	1	11.10	5.70	5.90	5.80		64.38		
11.10	20.00		Sqm	1	8.90	5.10	5.35	5.23		46.50		
20.00	23.80		Sqm	1	3.80	7.00	6.95	6.98		26.51		
23.80	30.00		Sqm	1	6.20	6.05	5.95	6.00		37.20		
30.00	45.00		Sqm	1	15.00	5.95	5.50	5.73		85.88		
45.00	60.00		Sqm	1	15.00	5.50	6.00	5.75		86.25		
60.00	66.90		Sqm	1	6.90	6.00	6.30	6.15		42.44		
66.90	75.00		Sqm	1	8.10	4.90	5.70	5.30		42.93		
75.00	75.60		Sqm	1	0.60	5.70	5.65	5.68		3.40		
75.60	76.80		Sqm	1	1.20	2.95	3.00	2.98		3.57		
		Mithun White Pearl Apartment Road (East To West)										
0.00	15.00		Sqm	1	15.00	6.60	6.75	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.75	6.50	6.63		99.38		
30.00	45.00		Sqm	1	15.00	6.50	6.45	6.48		97.13		
45.00	60.00		Sqm	1	15.00	6.45	6.45	6.45		96.75		
60.00	75.00		Sqm	1	15.00	6.45	6.25	6.35		95.25		
75.00	90.00		Sqm	1	15.00	6.25	6.20	6.23		93.38		
90.00	96.40		Sqm	1	6.40	6.20	5.85	6.03		38.56		
		Venkateshwara Layout 3rd Cross Road South to North										
0.00	15.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
15.00	30.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
30.00	45.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
45.00	60.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
60.00	75.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
75.00	90.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
90.00	105.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
105.00	120.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
120.00	135.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
135.00	150.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
150.00	165.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
165.00	180.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
180.00	195.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
195.00	210.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
210.00	220.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
		4th Cross Road North to South										
0.00	15.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
15.00	30.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
30.00	45.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
45.00	60.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
60.00	75.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
75.00	90.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
90.00	105.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
105.00	120.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
120.00	135.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
135.00	150.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
150.00	165.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
165.00	180.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
180.00	195.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
195.00	210.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
210.00	220.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
		5th Cross Road North to South										
0.00	15.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
15.00	30.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
30.00	45.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
45.00	60.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	75.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
75.00	90.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
90.00	105.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
105.00	120.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
120.00	135.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
135.00	150.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
150.00	165.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
165.00	180.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
180.00	195.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
195.00	210.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
210.00	220.00											
		Chembar	Sqm	-1	0.64					-0.64		
								Area of				
		Katgenahalli										
		Muneshwara Provision Store Beside Road										
		Kalidas Layout										
		3rd Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.70	6.65	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.65	6.65	6.65		99.75		
30.00	45.00		Sqm	1	15.00	6.65	6.00	6.33		94.88		
45.00	60.00		Sqm	1	15.00	6.00	5.80	5.90		88.50		
60.00	66.40		Sqm	1	6.40	5.80	5.60	5.70		36.48		
66.40	75.00		Sqm	1	8.60	5.60	5.60	5.60		48.16		
75.00	90.00		Sqm	1	15.00	5.60	5.50	5.55		83.25		
90.00	105.00		Sqm	1	15.00	5.50	5.80	5.65		84.75		
105.00	113.00		Sqm	1	8.00	5.80	4.30	5.05		40.40		
		Mk Provision Store Road										
		(From East to West)										
0.00	11.20		Sqm	1	11.20	6.20	6.10	6.15		68.88		
11.20	19.60		Sqm	1	8.40	5.60	4.94	5.27		44.27		
19.60	30.00		Sqm	1	10.40	5.40	5.30	5.35		55.64		
30.00	40.20		Sqm	1	10.20	5.30	5.40	5.35		54.57		
40.20	45.00		Sqm	1	4.80	5.40	6.30	5.85		28.08		
45.00	47.50		Sqm	1	2.50	6.30	7.00	6.65		16.63		
47.50	60.00		Sqm	1	12.50	5.00	4.50	4.75		59.38		
60.00	75.00		Sqm	1	15.00	4.50	5.75	5.13		76.88		
75.00	90.00		Sqm	1	15.00	5.75	5.38	5.57		83.48		
90.00	105.00		Sqm	1	15.00	5.38	5.10	5.24		78.60		
105.00	120.00		Sqm	1	15.00	5.10	4.85	4.98		74.63		
120.00	135.00		Sqm	1	15.00	4.85	4.80	4.83		72.38		
135.00	150.00		Sqm	1	15.00	4.80	5.50	5.15		77.25		
150.00	155.00		Sqm	1	5.00	5.50	5.88	5.69		28.45		
			Sqm	1	Triangular Portion 9.5*8.2*12.55=977.65			977.65		977.65		
			Sqm	1	Triangular Portion 10.5*3.3*11=381.15			381.15		381.15		
		Deduction										
0.00	1.40		Sqm	-1	1.40	1.00	1.00	1.00		-1.40		
		Cross Road - 2										
		(From North to South)										
0.00	4.30		Sqm	1	4.30	5.10	5.00	5.05		21.72		
4.30	15.00		Sqm	1	10.70	5.00	5.10	5.05		54.04		
15.00	20.60		Sqm	1	5.60	5.10	5.30	5.20		29.12		
20.60	30.00		Sqm	1	9.40	6.65	6.20	6.43		60.40		
30.00	40.60		Sqm	1	10.60	6.20	6.60	6.40		67.84		
40.60	45.00		Sqm	1	4.40	6.60	5.90	6.25		27.50		
45.00	60.00		Sqm	1	15.00	5.90	5.95	5.93		88.88		
60.00	75.00		Sqm	1	15.00	5.95	5.85	5.90		88.50		
75.00	90.00		Sqm	1	15.00	5.85	6.38	6.12		91.73		

Drainage From	Drainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	1	15.00	6.38	5.50	5.94		89.10		
90.00	105.00		Sqm	1	15.00	5.50	5.69	5.60		83.93		
105.00	120.00		Sqm	1	3.00	5.69	5.00	5.35		16.04		
120.00	123.00											
		Kattigenahalli										
		Durgamba Layout										
		Amulya Family Restaurant Road (N-S)										
			Sqm	1	15.00	6.90	6.40	6.65		99.75		
0.00	15.00		Sqm	1	15.00	6.40	6.05	6.23		93.38		
15.00	30.00		Sqm	1	15.00	5.60	5.30	5.45		81.75		
30.00	45.00		Sqm	1	15.00	5.30	4.95	5.13		76.88		
45.00	60.00		Sqm	1	15.00	4.95	5.05	5.00		75.00		
60.00	75.00		Sqm	1	6.00	5.05	5.05	5.05		30.30		
75.00	81.00		Sqm	1	9.00	5.70	5.90	5.80		52.20		
81.00	90.00		Sqm	1	15.00	5.90	5.30	5.60		84.00		
90.00	105.00		Sqm	1	13.80	5.30	4.60	4.95		68.31		
105.00	118.80		Sqm	1	9.10	5.80	5.85	5.83		53.01		
118.80	127.90		Sqm	1	7.10	4.95	4.85	4.90		34.79		
127.90	135.00		Sqm	1	2.10	4.85	5.05	4.95		10.40		
135.00	137.10		Sqm	1	12.90	4.35	4.95	4.65		59.99		
137.10	150.00		Sqm	1	15.00	4.95	4.60	4.78		71.63		
150.00	165.00		Sqm	1	15.00	4.60	5.25	4.93		73.88		
165.00	180.00		Sqm	1	2.50	5.25	5.15	5.20		13.00		
180.00	182.50		Sqm	1	12.50	5.85	6.60	6.23		77.81		
182.50	195.00		Sqm	1	15.00	6.60	6.15	6.38		95.63		
195.00	210.00		Sqm	1	8.00	6.15	6.00	6.08		48.60		
210.00	218.00											
		Kaustaba House Road #33 (W-E)										
0.00	6.30		Sqm	1	6.30	7.45	7.55	7.50		47.25		
6.30	15.00		Sqm	1	8.70	6.80	6.48	6.64		57.77		
15.00	30.00		Sqm	1	15.00	6.48	6.00	6.24		93.60		
30.00	45.00		Sqm	1	15.00	6.00	5.70	5.85		87.75		
45.00	57.90		Sqm	1	12.90	5.70	6.05	5.88		75.79		
57.90	60.00		Sqm	1	2.10	6.95	7.70	7.33		15.38		
60.00	63.60		Sqm	1	3.60	7.70	7.65	7.68		27.63		
		Sukruthi House Road #26 (S-N)										
0.00	8.30		Sqm	1	8.30	5.60	5.90	5.75		47.73		
8.30	15.00		Sqm	1	6.70	5.35	4.90	5.13		34.34		
15.00	30.00		Sqm	1	15.00	4.90	5.80	5.35		80.25		
30.00	45.00		Sqm	1	15.00	5.80	5.35	5.58		83.63		
45.00	60.00		Sqm	1	15.00	5.35	5.30	5.33		79.88		
60.00	60.50		Sqm	1	0.50	5.30	5.30	5.30		2.65		
60.50	75.00		Sqm	1	14.50	5.85	6.20	6.03		87.36		
75.00	90.00		Sqm	1	15.00	6.20	5.40	5.80		87.00		
90.00	98.70		Sqm	1	8.70	5.40	5.20	5.30		46.11		
98.70	105.00		Sqm	1	6.30	4.40	4.95	4.68		29.45		
105.00	108.20		Sqm	1	3.20	4.95	4.95	4.95		15.84		
108.20	112.20		Sqm	1	4.00	5.50	5.20	5.35		21.40		
112.20	120.00		Sqm	1	7.80	4.40	4.60	4.50		35.10		
120.00	125.80		Sqm	1	5.80	4.60	4.50	4.55		26.39		
125.80	135.70		Sqm	1	9.90	4.00	4.45	4.23		41.83		
135.70	143.90		Sqm	1	8.20	5.60	5.95	5.78		47.36		
143.90	150.00		Sqm	1	6.10	6.65	5.75	6.20		37.82		
150.00	164.30		Sqm	1	14.30	5.75	5.85	5.80		82.94		
		SP Singh House Road (E-W)										
0.00	15.00		Sqm	1	15.00	6.35	5.65	6.00		90.00		
15.00	19.10		Sqm	1	4.10	5.65	6.00	5.83		23.88		
19.10	30.00		Sqm	1	10.90	5.20	5.65	5.43		59.13		
30.00	34.20		Sqm	1	4.20	5.65	6.10	5.88		24.68		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Form mrd Main To Muneshwara provsion										
0.00	1.70		Sqm	1	1.70	5.05	5.05	5.05		8.59		
1.70	15.00		Sqm	1	13.30	7.30	7.40	7.35		97.76		
15.00	30.00		Sqm	1	15.00	7.40	7.10	7.25		108.75		
30.00	45.00		Sqm	1	15.00	7.10	6.75	6.93		103.88		
45.00	60.00		Sqm	1	15.00	6.75	7.55	7.15		107.25		
60.00	75.00		Sqm	1	15.00	7.55	6.45	7.00		105.00		
75.00	77.80		Sqm	1	2.80	6.45	5.70	6.08		17.01		
77.80	90.00		Sqm	1	12.20	6.80	7.15	6.98		85.10		
90.00	95.90		Sqm	1	5.90	7.15	6.95	7.05		41.60		
95.90	105.00		Sqm	1	9.10	6.25	6.30	6.28		57.10		
105.00	117.90		Sqm	1	12.90	6.30	5.90	6.10		78.69		
117.90	120.00		Sqm	1	2.10	6.75	6.80	6.78		14.23		
120.00	124.80		Sqm	1	4.80	6.80	5.80	6.30		30.24		
		Deduction										
		Chamber	Sqm	-1	0.70	1.00	1.00	1.00		-0.70		
		Manhole	Sqm	-1	0.64					-0.64		
								Area of Circle =				
		Manhole	Sqm	-1	1.13					-1.13		
								Area of Circle =				
		Cross Road 3 Near Pyramid apartment (North to South)										
0.00	2.90		Sqm	1	2.90	6.40	6.35	6.38		18.49		
2.90	15.00		Sqm	1	12.10	6.35	5.75	6.05		73.21		
15.00	30.00		Sqm	1	15.00	5.75	5.70	5.73		85.88		
30.00	44.00		Sqm	1	14.00	5.70	5.10	5.40		75.60		
		For Road Cut portion Green Garden Main Road (West to East)										
2.00	4.00		Sqm	1	2.00	1.60	1.60	1.60		3.20		
7.00	11.00		Sqm	1	4.00	1.20	1.20	1.20		4.80		
13.00	15.00		Sqm	1	2.00	1.30	1.30	1.30		2.60		
17.00	22.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
25.00	29.00		Sqm	1	4.00	2.00	2.00	2.00		8.00		
30.00	42.70		Sqm	1	12.70	1.60	1.60	1.60		20.32		
42.70	45.00		Sqm	1	2.30	2.10	2.10	2.10		4.83		
45.00	53.70		Sqm	1	8.70	1.10	1.10	1.10		9.57		
53.70	60.00		Sqm	1	6.30	1.60	1.60	1.60		10.08		
62.00	66.00		Sqm	1	4.00	1.60	1.60	1.60		6.40		
68.00	70.00		Sqm	1	2.00	1.80	1.80	1.80		3.60		
72.00	75.00		Sqm	1	3.00	1.40	1.40	1.40		4.20		
77.00	88.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
93.80	103.00		Sqm	1	9.20	1.00	1.00	1.00		9.20		
107.00	117.00		Sqm	1	10.00	1.70	1.70	1.70		17.00		
120.00	126.90		Sqm	1	6.90	1.30	1.30	1.30		8.97		
128.00	130.00		Sqm	1	2.00	1.40	1.40	1.40		2.80		
132.00	140.00		Sqm	1	8.00	1.60	1.60	1.60		12.80		
148.00	152.00		Sqm	1	4.00	2.10	2.10	2.10		8.40		
154.30	160.00		Sqm	1	5.70	1.60	1.60	1.60		9.12		
163.00	169.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
		Cross Road-4 (South to North)										
0.00	1.60		Sqm	1	1.60	1.30	1.30	1.30		2.08		
4.00	12.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
15.00	21.00		Sqm	1	6.00	1.60	1.60	1.60		9.60		
23.50	30.00		Sqm	1	6.50	2.60	2.60	2.60		16.90		
30.00	33.70		Sqm	1	3.70	3.00	3.00	3.00		11.10		
		Sri Ganga House Road East to West										
3.80	13.20		Sqm	1	9.40	1.00	1.00	1.00		9.40		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	15.00		Sqm	1	1.80	3.00	3.00	3.00		5.40		
15.20	26.00		Sqm	1	9.00	2.40	2.40	2.40		21.60		
27.00	30.00		Sqm	1	2.60	1.60	1.60	1.60		4.16		
32.40	41.00		Sqm	1	8.00	1.90	1.90	1.90		15.20		
48.00	57.60		Sqm	1	10.60	3.00	3.00	3.00		31.80		
49.00	66.00		Sqm	1	4.00	1.70	1.70	1.70		6.80		
66.00												
		Cross Road-3										
		(North to South)										
			Sqm	1	1.70	3.00	3.00	3.00		5.10		
0.00	1.70		Sqm	1	6.70	1.30	1.30	1.30		8.71		
2.50	10.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
10.00	14.00		Sqm	1	4.00	1.70	1.70	1.70		6.80		
17.00	21.00		Sqm	1	5.00	2.20	2.20	2.20		11.00		
24.00	29.00		Sqm	1	5.00	1.70	1.70	1.70		8.50		
33.00	38.00		Sqm	1	4.00	1.10	1.10	1.10		4.40		
40.00	44.00		Sqm	1	1.10	1.70	1.70	1.70		1.87		
45.00	46.10		Sqm	1	2.80	2.00	2.00	2.00		5.60		
46.10	48.90											
		Cross Road 2										
		(South to North)										
			Sqm	1	6.00	1.90	1.90	1.90		11.40		
3.00	9.00		Sqm	1	3.00	2.20	2.20	2.20		6.60		
12.00	15.00		Sqm	1	3.10	3.10	3.10	3.10		9.61		
18.00	21.10		Sqm	1	7.00	1.75	1.75	1.75		12.25		
23.00	30.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
33.00	45.00		Sqm	1	3.00	1.00	1.00	1.00		3.00		
48.00	51.00		Sqm	1	5.00	1.85	1.85	1.85		9.25		
53.00	58.00		Sqm	1	7.80	1.50	1.50	1.50		11.70		
64.20	72.00		Sqm	1	9.00	2.10	2.10	2.10		18.90		
78.00	87.00		Sqm	1	5.40	1.70	1.70	1.70		9.18		
92.60	98.00											
		Cross Road 1										
		(North to South)										
4.60	12.20		Sqm	1	7.60	1.20	1.20	1.20		9.12		
17.60	27.00		Sqm	1	9.40	1.80	1.80	1.80		16.92		
33.00	41.00		Sqm	1	8.00	2.30	2.30	2.30		18.40		
47.00	58.00		Sqm	1	11.00	2.70	2.70	2.70		29.70		
62.80	71.00		Sqm	1	8.20	1.60	1.60	1.60		13.12		
79.00	88.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
94.00	98.00		Sqm	1	4.00	1.70	1.70	1.70		6.80		
		Pyramid apartment main road										
		(East to West)										
0.00	1.10		Sqm	1	1.10	8.16	8.15	8.16		8.97		
1.10	2.40		Sqm	1	1.30	8.15	6.80	7.48		9.72		
2.40	4.70		Sqm	1	2.30	6.80	6.60	6.70		15.41		
4.70	12.40		Sqm	1	7.70	7.65	7.85	7.75		59.68		
12.40	15.00		Sqm	1	2.60	7.85	7.70	7.78		20.22		
15.00	30.00		Sqm	1	15.00	7.70	8.35	8.03		120.38		
30.00	32.00		Sqm	1	2.00	8.35	8.35	8.35		16.70		
32.00	45.00		Sqm	1	13.00	8.35	8.50	8.43		109.53		
45.00	60.00		Sqm	1	15.00	8.50	8.65	8.58		128.63		
60.00	75.00		Sqm	1	15.00	8.65	8.70	8.68		130.13		
75.00	81.10		Sqm	1	6.10	8.70	8.75	8.73		53.22		
81.10	90.00		Sqm	1	8.90	8.75	8.20	8.48		75.43		
90.00	105.00		Sqm	1	15.00	8.20	8.45	8.33		124.88		
105.00	120.00		Sqm	1	15.00	8.45	8.38	8.42		126.23		
120.00	128.00		Sqm	1	8.00	8.38	8.40	8.39		67.12		
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
3.60	11.00		Sqm	1	5.40	1.40	1.40	1.40		7.56		
17.00	27.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
30.00	32.80		Sqm	1	2.80	1.70	1.70	1.70		4.76		

Ward (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	1	9.50	2.00	2.00	2.00		19.00		
42.80	45.10		Sqm	1	2.80	1.30	1.30	1.30		3.64		
42.30	48.30		Sqm	1	3.20	1.00	1.00	1.00		3.20		
		Cross Road 1 Near Pyramid apartment (North to South)										
			Sqm	1	8.50	1.70	1.70	1.70		14.45		
8.50	13.00		Sqm	1	11.00	1.40	1.40	1.40		15.40		
16.00	27.00		Sqm	1	7.00	1.70	1.70	1.70		11.90		
34.00	41.00		Sqm	1	3.70	1.25	1.25	1.25		4.63		
48.00	51.70		Sqm	1	5.70	2.10	2.10	2.10		11.97		
53.00	58.70		Sqm	1	8.00	1.70	1.70	1.70		13.60		
63.00	71.00		Sqm	1	7.00	1.40	1.40	1.40		9.80		
79.00	86.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
85.00	102.00		Sqm	1	10.60	1.80	1.80	1.80		19.08		
106.40	117.00		Sqm	1	3.00	1.20	1.20	1.20		3.60		
122.00	125.00											
		Profile Correction Green Garden Main Road (West to East)										
			Sqm	1	15.00	1.00	1.00	1.00		15.00		
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	12.70	1.20	1.20	1.20		15.24		
30.00	42.70		Sqm	1	2.30	0.90	0.90	0.90		2.07		
42.70	45.00		Sqm	1	8.70	1.00	1.00	1.00		8.70		
45.00	53.70		Sqm	1	6.30	1.30	1.30	1.30		8.19		
53.70	60.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
60.00	75.00		Sqm	1	15.00	1.15	1.15	1.15		17.25		
75.00	90.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
90.00	105.00		Sqm	1	15.00	1.15	1.15	1.15		17.25		
105.00	120.00		Sqm	1	6.90	0.75	0.75	0.75		5.18		
120.00	126.90		Sqm	1	3.10	0.90	0.90	0.90		2.79		
126.90	130.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
130.00	145.00		Sqm	1	9.30	1.00	1.00	1.00		9.30		
145.00	154.30		Sqm	1	5.70	0.95	0.95	0.95		5.41		
154.30	160.00		Sqm	1	11.40	1.00	1.00	1.00		11.40		
160.00	171.40											
		Cross Road-4 (South to North)										
0.00	1.60		Sqm	1	1.60	1.10	1.10	1.10		1.76		
1.60	15.00		Sqm	1	13.40	1.20	1.20	1.20		16.08		
15.00	23.50		Sqm	1	8.50	0.90	0.90	0.90		7.65		
23.50	30.00		Sqm	1	6.50	1.00	1.00	1.00		6.50		
30.00	33.70		Sqm	1	3.70	1.20	1.20	1.20		4.44		
		Sri Ganga House Road East to West										
0.00	3.80		Sqm	1	3.80	0.90	0.90	0.90		3.42		
3.80	13.20		Sqm	1	9.40	1.00	1.00	1.00		9.40		
13.20	15.00		Sqm	1	1.80	1.30	1.30	1.30		2.34		
15.00	27.40		Sqm	1	12.40	1.00	1.00	1.00		12.40		
27.40	30.00		Sqm	1	2.60	1.20	1.20	1.20		3.12		
30.00	45.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
45.00	60.00		Sqm	1	15.00	1.15	1.15	1.15		17.25		
60.00	69.30		Sqm	1	9.30	0.75	0.75	0.75		6.98		
		Cross Road-3 (North to South)										
0.00	1.70		Sqm	1	1.70	1.00	1.00	1.00		1.70		
1.70	15.00		Sqm	1	13.30	0.90	0.90	0.90		11.97		
15.00	30.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
30.00	45.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
45.00	46.10		Sqm	1	1.10	1.30	1.30	1.30		1.43		
46.10	48.90		Sqm	1	2.80	1.40	1.40	1.40		3.92		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road 2										
		(South to North)										
			Sqm	1	11.80	0.90	0.90	0.90		10.62		
0.00	11.80		Sqm	1	3.20	1.00	1.00	1.00		3.20		
11.80	15.00		Sqm	1	6.10	1.30	1.30	1.30		7.93		
15.00	21.10		Sqm	1	8.90	1.00	1.00	1.00		8.90		
21.10	30.00		Sqm	1	15.00	1.15	1.15	1.15		17.25		
30.00	45.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
45.00	60.00		Sqm	1	15.00	1.15	1.15	1.15		17.25		
60.00	75.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75.00	90.00		Sqm	1	10.30	1.10	1.10	1.10		11.33		
90.00	100.30		Sqm	1	2.10	1.20	1.20	1.20		2.52		
100.30	102.40											
		Cross Road 1										
		(North to South)										
			Sqm	1	2.90	1.00	1.00	1.00		2.90		
0.00	2.90		Sqm	1	12.10	0.90	0.90	0.90		10.89		
2.90	15.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
15.00	30.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
30.00	45.00		Sqm	1	15.00	1.30	1.30	1.30		19.50		
45.00	60.00		Sqm	1	15.00	1.40	1.40	1.40		21.00		
60.00	75.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75.00	90.00		Sqm	1	12.30	1.30	1.30	1.30		15.99		
90.00	102.30											
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
			Sqm	1	3.60	1.30	1.30	1.30		4.68		
0.00	3.60		Sqm	1	11.40	1.00	1.00	1.00		11.40		
3.60	15.00		Sqm	1	15.00	1.20	1.20	1.20		18.00		
15.00	30.00		Sqm	1	2.80	1.00	1.00	1.00		2.80		
30.00	32.80		Sqm	1	9.50	1.15	1.15	1.15		10.93		
32.80	42.30		Sqm	1	2.80	0.75	0.75	0.75		2.10		
42.30	45.10		Sqm	1	3.20	1.30	1.30	1.30		4.16		
45.10	48.30											
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
			Sqm	1	4.50	1.15	1.15	1.15		5.18		
0.00	4.50		Sqm	1	10.50	1.00	1.00	1.00		10.50		
4.50	15.00		Sqm	1	15.00	1.15	1.15	1.15		17.25		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	6.70	1.10	1.10	1.10		7.37		
45.00	51.70		Sqm	1	7.80	1.00	1.00	1.00		7.80		
52.20	60.00		Sqm	1	15.00	1.15	1.15	1.15		17.25		
60.00	75.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75.00	90.00		Sqm	1	15.00	1.30	1.30	1.30		19.50		
90.00	105.00		Sqm	1	15.00	1.15	1.15	5.63		84.38		
105.00	120.00		Sqm	1	7.20	0.90	0.90	5.58		40.14		
120.00	127.20											
		Car 24 Beside Road										
		From Agrahara Main Road to Lake										
		East to West										
0.00	15.00		Sqm	1	15.00	4.80	4.60	4.70		70.50		
15.00	27.00		Sqm	1	12.00	4.60	4.65	4.63		55.50		
27.00	30.00		Sqm	1	3.00	5.40	5.70	5.55		16.65		
30.00	45.00		Sqm	1	15.00	5.70	5.70	5.70		85.50		
45.00	60.00		Sqm	1	15.00	5.70	6.30	6.00		90.00		
60.00	75.00		Sqm	1	15.00	6.30	6.30	6.30		94.50		
75.00	90.00		Sqm	1	15.00	6.30	6.50	6.40		96.00		
90.00	105.00		Sqm	1	15.00	6.50	6.65	6.58		98.63		
105.00	120.00		Sqm	1	15.00	6.65	6.40	6.53		97.88		
120.00	135.00		Sqm	1	15.00	6.40	6.20	6.30		94.50		
135.00	150.00		Sqm	1	15.00	6.20	6.10	6.15		92.25		
150.00	165.00		Sqm	1	15.00	6.10	6.30	6.20		93.00		
165.00	180.00		Sqm	1	15.00	6.30	6.10	6.20		93.00		

BMP (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
180.00	195.00		Sqm	1	15.00	6.10	6.25	6.18		92.63		
195.00	210.00		Sqm	1	15.00	6.25	6.50	6.38		95.63		
210.00	225.00		Sqm	1	15.00	6.50	6.40	6.45		96.75		
225.00	240.00		Sqm	1	15.00	6.40	6.50	6.45		96.75		
240.00	255.00		Sqm	1	15.00	6.50	6.65	6.58		98.63		
255.00	270.00		Sqm	1	15.00	6.65	6.70	6.68		100.13		
270.00	285.00		Sqm	1	15.00	6.70	6.45	6.58		98.63		
285.00	300.00		Sqm	1	15.00	6.45	6.20	6.33		94.88		
300.00	315.00		Sqm	1	15.00	6.20	6.10	6.15		92.25		
315.00	330.00		Sqm	1	15.00	6.10	6.10	6.10		91.50		
330.00	345.00		Sqm	1	15.00	6.10	6.00	6.05		90.75		
345.00	360.00		Sqm	1	15.00	6.00	6.60	6.30		94.50		
360.00	375.00		Sqm	1	15.00	6.60	6.00	6.30		94.50		
375.00	390.00		Sqm	1	15.00	6.00	6.10	6.05		90.75		
390.00	405.00		Sqm	1	15.00	6.10	6.30	6.20		93.00		
405.00	410.00		Sqm	1	5.00	6.30	6.40	6.35		31.75		
410.00	419.00		Sqm	1	9.00	4.70	4.50	4.60		41.40		
419.00	420.00		Sqm	1	1.00	6.30	6.30	6.30		6.30		
420.00	435.00		Sqm	1	15.00	6.30	6.30	6.30		94.50		
435.00	450.00		Sqm	1	15.00	6.30	6.80	6.55		98.25		
450.00	465.00		Sqm	1	15.00	6.80	7.10	6.95		104.25		
465.00	480.00		Sqm	1	15.00	7.10	5.80	6.45		96.75		
480.00	495.00		Sqm	1	15.00	5.80	5.20	5.50		82.50		
495.00	510.00		Sqm	1	15.00	5.20	3.95	4.58		68.63		
510.00	512.00		Sqm	1	2.00	3.95	3.80	3.88		7.75		
512.00	525.00		Sqm	1	13.00	4.70	5.45	5.08		65.98		
525.00	540.00		Sqm	1	15.00	5.45	6.10	5.78		86.63		
540.00	546.00		Sqm	1	6.00	6.10	5.50	5.80		34.80		
		Cross Road-1										
		South to North										
0.00	6.00		Sqm	1	6.00	12.00	5.90	8.95		53.70		
6.00	12.00		Sqm	1	6.00	5.90	5.00	5.45		32.70		
12.00	15.00		Sqm	1	3.00	6.00	6.00	6.00		18.00		
15.00	19.00		Sqm	1	4.00	6.00	5.70	5.85		23.40		
		Cross Road-2										
		South to north										
0.00	15.00		Sqm	1	15.00	6.50	6.00	6.25		93.75		
15.00	30.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
30.00	45.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
45.00	60.00		Sqm	1	15.00	6.00	6.30	6.15		92.25		
60.00	67.70		Sqm	1	7.70	6.30	6.60	6.45		49.67		
67.70	69.70		Sqm	1	2.00	6.60	7.30	6.95		13.90		
		MCECHS layout										
		22nd Cross Road										
		North to South										
0.00	15.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15.00	30.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30.00	45.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45.00	60.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60.00	75.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75.00	90.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
90.00	105.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
105.00	120.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
120.00	135.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
135.00	141.10		Sqm	1	6.10	0.75	0.75	0.75		4.58		
		Vidhana Soudha Layout										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.10	5.45	5.78		86.63		
15.00	29.30		Sqm	1	14.30	5.45	8.30	6.88		98.31		
		(From East to West)										
0.00	15.00		Sqm	1	15.00	9.40	8.90	9.15		137.25		
15.00	30.00		Sqm	1	15.00	8.90	8.60	8.75		131.25		

MSHP (Ward No.04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
30.00	45.00		Sqm	1	15.00	8.60	8.90	8.75		131.25		
45.00	60.00		Sqm	1	15.00	8.90	8.20	8.55		128.25		
60.00	75.00		Sqm	1	15.00	8.20	8.25	8.23		123.38		
75.00	90.00		Sqm	1	15.00	8.25	8.50	8.38		125.63		
90.00	105.00		Sqm	1	15.00	8.50	8.30	8.40		126.00		
105.00	117.80		Sqm	1	12.80	8.30	8.25	8.28		105.92		
117.80	125.10		Sqm	1	7.30	11.35	11.25	11.30		82.49		
125.10	135.00		Sqm	1	9.90	8.20	8.05	8.13		80.44		
135.00	150.00		Sqm	1	15.00	8.05	8.05	8.05		120.75		
150.00	150.90		Sqm	1	0.90	10.95	10.95	10.95		9.86		
150.90	165.00		Sqm	1	14.10	8.30	8.35	8.33		117.38		
165.00	180.00		Sqm	1	15.00	8.35	8.42	8.39		125.78		
180.00	184.90		Sqm	1	4.90	8.42	8.55	8.49		41.58		
184.90	193.50		Sqm	1	8.60	11.20	11.30	11.25		96.75		
193.50	195.00		Sqm	1	1.50	8.30	8.30	8.30		12.45		
195.00	210.00		Sqm	1	15.00	8.30	8.15	8.23		123.38		
210.00	225.00		Sqm	1	15.00	8.15	8.30	8.23		123.38		
225.00	240.00		Sqm	1	15.00	8.30	9.00	8.65		129.75		
240.00	255.00		Sqm	1	15.00	9.00	8.85	8.93		133.88		
255.00	258.00		Sqm	1	3.00	8.85	8.25	8.55		25.65		
258.00	265.10		Sqm	1	7.10	9.70	9.80	9.75		69.23		
265.10	270.00		Sqm	1	4.90	8.40	8.35	8.38		41.04		
270.00	285.00		Sqm	1	15.00	8.35	8.25	8.30		124.50		
285.00	291.00		Sqm	1	6.00	8.25	8.20	8.23		49.35		
291.00	299.80		Sqm	1	8.80	9.55	9.40	9.48		83.38		
299.80	300.00		Sqm	1	0.20	8.15	8.14	8.15		1.63		
300.00	301.00		Sqm	1	1.00	8.14	8.15	8.15		8.15		
301.00	307.30		Sqm	1	6.30	9.81	9.80	9.81		61.77		
307.30	315.00		Sqm	1	7.70	8.10	8.15	8.13		62.56		
315.00	323.00		Sqm	1	8.00	8.15	8.25	8.20		65.60		
323.00	332.00		Sqm	1	9.00	9.60	9.60	9.60		86.40		
332.00	343.00		Sqm	1	11.00	9.40	9.60	9.50		104.50		
343.00	345.00		Sqm	1	2.00	8.10	8.20	8.15		16.30		
345.00	358.90		Sqm	1	13.90	8.20	8.15	8.18		113.63		
358.90	368.10		Sqm	1	9.20	9.70	9.71	9.71		89.29		
368.10	375.00		Sqm	1	6.90	8.15	8.15	8.15		56.23		
375.00	382.60		Sqm	1	7.60	8.15	8.30	8.23		62.51		
382.60	391.90		Sqm	1	9.30	9.90	9.50	9.70		90.21		
391.90	393.30		Sqm	1	1.40	7.90	8.00	7.95		11.13		
393.30	400.00		Sqm	1	6.70	9.20	9.20	9.20		61.64		
400.00	405.00		Sqm	1	5.00	7.90	7.40	7.65		38.25		
405.00	420.00		Sqm	1	15.00	7.40	7.60	7.50		112.50		
420.00	435.00		Sqm	1	15.00	7.60	7.40	7.50		112.50		
435.00	444.20		Sqm	1	9.20	9.00	9.10	9.05		83.26		
444.20	446.30		Sqm	1	2.10	7.30	7.45	7.38		15.49		
446.30	456.40		Sqm	1	10.10	9.15	9.10	9.13		92.16		
456.40	465.00		Sqm	1	8.60	7.45	7.35	7.40		63.64		
465.00	480.00		Sqm	1	15.00	7.35	7.25	7.30		109.50		
480.00	495.00		Sqm	1	15.00	7.25	7.65	7.45		111.75		
495.00	510.00		Sqm	1	15.00	7.65	8.50	8.08		121.13		
510.00	525.20		Sqm	1	15.20	10.00	10.60	10.30		156.56		
525.20	540.00		Sqm	1	14.80	8.50	7.60	8.05		119.14		
540.00	555.00		Sqm	1	15.00	7.60	7.50	7.55		113.25		
555.00	560.90		Sqm	1	5.90	7.50	7.50	7.50		44.25		
560.90	562.70		Sqm	1	1.80	4.80	4.80	4.80		8.64		
										34718.83		
		Total Executed Quantity								**28661.26**		
		Tender Quantity								**34718.83**	**34.26**	**1189468.00**
		Quantity Upto 125%										
		Item no. 16 Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specification and directions of the Engineer in charge.											
		Defence Colony										
		6th Main Road										
0.00	15.00	(From North to South)	Cum	1	15.00	4.95	5.20	5.08	0.05	3.81		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	15.00	5.20	5.20	5.20	0.05	3.90		
15.00	30.00		Cum	1	10.10	5.20	5.50	5.35	0.05	2.70		
30.00	40.10		Cum	1	3.60	4.32	4.75	4.54	0.05	0.82		
40.10	43.70		Cum	1	1.30	5.28	5.20	5.24	0.05	0.34		
43.70	45.00		Cum	1	15.00	5.20	4.90	5.05	0.05	3.79		
45.00	60.00		Cum	1	15.00	4.90	5.50	5.20	0.05	3.90		
60.00	75.00		Cum	1	15.00	5.50	5.10	5.30	0.05	3.98		
75.00	90.00		Cum	1	15.00	5.10	5.00	5.05	0.05	3.79		
90.00	105.00		Cum	1	5.80	5.00	5.10	5.05	0.05	1.46		
105.00	110.80	8th Main Road										
		(From East to West)										
			Cum	1	15.00	4.40	4.45	4.43	0.05	3.32		
0.00	15.00		Cum	1	15.00	4.45	4.90	4.68	0.05	3.51		
15.00	30.00		Cum	1	15.00	4.95	5.10	5.03	0.05	3.77		
30.00	45.00		Cum	1	15.00	5.10	5.00	5.05	0.05	3.79		
45.00	60.00		Cum	1	15.00	4.95	5.10	5.03	0.05	3.77		
60.00	75.00		Cum	1	15.00	5.10	5.05	5.08	0.05	3.81		
75.00	90.00		Cum	1	15.00	4.95	5.20	5.08	0.05	3.81		
90.00	105.00		Cum	1	15.00	5.20	5.05	5.13	0.05	3.84		
105.00	120.00		Cum	1	11.00	4.95	4.95	4.95	0.05	2.72		
120.00	131.00	Cross Road 2										
		(From East to West)										
			Cum	1	15.00	4.25	4.10	4.18	0.05	3.13		
0.00	15.00		Cum	1	15.00	4.10	4.00	4.05	0.05	3.04		
15.00	30.00		Cum	1	1.50	4.00	4.00	4.00	0.05	0.30		
30.00	31.50	Cross Road 1										
		(From East to West)										
			Cum	1	15.00	4.40	4.48	4.44	0.05	3.33		
0.00	15.00		Cum	1	14.50	4.48	4.65	4.57	0.05	3.31		
15.00	29.50	Nithish Central Park Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.80	5.40	5.60	0.05	4.20		
15.00	21.40		Cum	1	6.40	5.40	5.70	5.55	0.05	1.78		
21.40	29.60		Cum	1	8.20	5.05	4.80	4.93	0.05	2.02		
29.60	30.00		Cum	1	0.40	5.52	5.50	5.51	0.05	0.11		
30.00	45.00		Cum	1	15.00	5.50	5.15	5.33	0.05	3.99		
45.00	60.00		Cum	1	15.00	5.15	5.15	5.15	0.05	3.86		
60.00	75.00		Cum	1	15.00	5.15	5.04	5.10	0.05	3.82		
75.00	80.00		Cum	1	5.00	5.04	6.00	5.52	0.05	1.38		
80.00	83.70		Cum	1	3.70	6.00	5.95	5.98	0.05	1.11		
83.70	87.60		Cum	1	3.90	5.30	5.30	5.30	0.05	1.03		
87.60	93.20		Cum	1	5.60	6.30	6.20	6.25	0.05	1.75		
93.20	96.20		Cum	1	3.00	5.40	5.00	5.20	0.05	0.78		
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.80	5.30	5.05	0.05	3.79		
15.00	22.80		Cum	1	7.80	5.30	5.40	5.35	0.05	2.09		
22.80	32.00		Cum	1	9.20	4.95	4.80	4.88	0.05	2.24		
32.00	45.00		Cum	1	13.00	4.75	5.03	4.89	0.05	3.18		
45.00	60.00		Cum	1	15.00	5.03	4.95	4.99	0.05	3.74		
60.00	75.00		Cum	1	15.00	4.95	5.30	5.13	0.05	3.84		
75.00	90.00		Cum	1	15.00	4.95	5.45	5.20	0.05	3.90		
90.00	95.10		Cum	1	5.10	5.45	5.65	5.55	0.05	1.42		
		Deducation										
		Chamber	Cum	-1	1.90			1.40	0.05	-0.13		
		Tree Pot	Cum	-9	0.20			0.10	0.05	-0.01		
		Electric Pole	Cum	-1	0.90			0.50	0.05	-0.02		
		Man Hole (1m Dia)	Cum	-1	Area = 0.25*3.142*1^2=0.785				0.05	-0.04		
		7th Main Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.35	4.06	4.21	0.05	3.15		
15.00	17.40		Cum	1	2.40	4.06	4.25	4.16	0.05	0.50		
17.40	26.70		Cum	1	9.30	5.05	5.20	5.13	0.05	2.38		
26.70	41.70		Cum	1	15.00	4.10	4.10	4.10	0.05	3.08		

BMP (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	3.40	4.10	3.75	3.93	0.05	0.67		
41.70	45.10		Cum	1	14.90	5.10	5.10	5.10	0.05	3.80		
45.10	60.00		Cum	1	15.00	5.10	5.17	5.14	0.05	3.85		
60.00	75.00		Cum	1	8.70	5.17	5.00	5.09	0.05	2.21		
75.00	83.70		Cum	1	15.00	4.35	4.00	4.18	0.05	3.13		
83.70	98.70		Cum	1	1.70	4.00	4.00	4.00	0.05	0.34		
98.70	100.40		Cum	1	3.70	5.10	5.10	5.10	0.05	0.94		
100.40	104.10											
		2nd Cross										
		(From North to South										
			Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
4.00	11.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
17.00	27.00		Cum	1	7.00	1.60	1.60	1.60	0.05	0.56		
34.00	41.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
48.00	56.00		Cum	1	6.00	1.20	1.20	1.20	0.05	0.36		
61.00	67.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
71.00	78.00		Cum	1	6.00	2.10	2.10	2.10	0.05	0.63		
82.00	88.00		Cum	1	4.40	1.10	1.10	1.10	0.05	0.24		
92.00	96.40											
		1st Cross Road										
		(From East to West)										
			Cum	1	15.00	6.50	5.40	5.95	0.05	4.46		
0.00	15.00		Cum	1	10.40	5.40	6.00	5.70	0.05	2.96		
15.00	25.40											
		8th Main Road										
		North to South										
			Cum	1	2.00	1.10	1.10	1.10	0.05	0.11		
6.00	8.00		Cum	1	4.00	1.30	1.30	1.30	0.05	0.26		
12.00	16.00		Cum	1	3.00	1.00	1.00	1.00	0.05	0.15		
26.00	29.00		Cum	1	5.00	1.20	1.20	1.20	0.05	0.30		
42.00	47.00		Cum	1	5.00	0.90	0.90	0.90	0.05	0.23		
88.00	93.00											
		Vinayak Nagar										
		6th B Main Road										
		North to South										
			Cum	1	3.00	1.30	1.30	1.30	0.05	0.20		
8.00	11.00		Cum	1	4.00	1.40	1.40	1.40	0.05	0.28		
55.00	59.00		Cum	1	4.00	1.20	1.20	1.20	0.05	0.24		
63.00	67.00		Cum	1	3.00	0.85	0.85	0.85	0.05	0.13		
76.00	79.00											
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	4.80	5.80	5.30	0.05	3.98		
15.00	30.00		Cum	1	15.00	5.80	5.30	5.55	0.05	4.16		
30.00	45.00		Cum	1	15.00	5.30	6.15	5.73	0.05	4.29		
45.00	60.00		Cum	1	15.00	6.15	6.48	6.32	0.05	4.74		
60.00	65.80		Cum	1	5.80	6.48	6.49	6.49	0.05	1.88		
		11th Cross Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	4.20	4.10	4.15	0.05	3.11		
15.00	30.00		Cum	1	15.00	4.10	3.80	3.95	0.05	2.96		
30.00	45.00		Cum	1	15.00	3.80	3.65	3.73	0.05	2.79		
45.00	60.00		Cum	1	15.00	3.65	4.00	3.83	0.05	2.87		
60.00	70.00		Cum	1	10.00	4.00	4.10	4.05	0.05	2.03		
70.00	75.00		Cum	1	5.00	4.10	4.00	4.05	0.05	1.01		
75.00	90.00		Cum	1	15.00	4.00	4.64	4.32	0.05	3.24		
90.00	105.00		Cum	1	15.00	4.64	4.90	4.77	0.05	3.58		
105.00	120.00		Cum	1	15.00	4.90	4.90	4.90	0.05	3.68		
120.00	135.00		Cum	1	15.00	4.90	4.90	4.90	0.05	3.68		
135.00	150.00		Cum	1	15.00	4.90	5.00	4.95	0.05	3.71		
150.00	165.00		Cum	1	15.00	5.00	4.90	4.95	0.05	3.71		
165.00	168.00		Cum	1	3.00	4.90	4.75	4.83	0.05	0.72		

...ndal (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		10th Cross Road										
		(From North to South)										
			Cum	1	15.00	5.35	5.30	5.33	0.05	3.99		
0.00	15.00		Cum	1	15.00	5.30	5.10	5.20	0.05	3.90		
15.00	30.00		Cum	1	15.00	5.10	4.40	4.75	0.05	3.56		
30.00	45.00		Cum	1	15.00	4.40	4.50	4.45	0.05	3.34		
45.00	60.00		Cum	1	15.00	4.50	4.60	4.55	0.05	3.41		
60.00	75.00		Cum	1	15.00	4.60	4.48	4.54	0.05	3.41		
75.00	90.00		Cum	1	15.00	4.48	4.84	4.66	0.05	3.50		
90.00	105.00		Cum	1	3.60	4.84	4.85	4.85	0.05	0.87		
105.00	108.60		Cum	1	8.80	5.35	4.80	5.08	0.05	2.23		
108.60	117.40		Cum	1	2.60	4.50	4.60	4.55	0.05	0.59		
117.40	120.00		Cum	1	15.00	4.60	4.49	4.55	0.05	3.41		
120.00	135.00		Cum	1	15.00	4.49	4.67	4.58	0.05	3.44		
135.00	150.00		Cum	1	15.00	4.67	4.55	4.61	0.05	3.46		
150.00	165.00		Cum	1	2.60	4.55	4.90	4.73	0.05	0.61		
165.00	167.60											
		10th A Cross										
		(From North to South)										
			Cum	1	15.00	6.00	5.75	5.88	0.05	4.41		
0.00	15.00		Cum	1	15.00	5.75	5.40	5.58	0.05	4.18		
15.00	30.00		Cum	1	15.00	5.40	5.40	5.40	0.05	4.05		
30.00	45.00		Cum	1	15.00	5.40	5.10	5.25	0.05	3.94		
45.00	60.00		Cum	1	15.00	5.10	5.35	5.23	0.05	3.92		
60.00	75.00		Cum	1	15.00	5.35	5.55	5.45	0.05	4.09		
75.00	90.00		Cum	1	15.00	5.55	6.00	5.78	0.05	4.33		
90.00	105.00		Cum	1	15.00	6.00	6.10	6.05	0.05	4.54		
105.00	120.00		Cum	1	14.70	6.10	6.20	6.15	0.05	4.52		
120.00	134.70											
		10th A Cross										
		(From West to East)										
			Cum	1	2.80	4.80	4.50	4.65	0.05	0.65		
0.00	2.80											
		2nd Main Road										
		(From West to East)										
			Cum	1	15.00	8.80	8.70	8.75	0.05	6.56		
0.00	15.00		Cum	1	15.00	8.70	9.13	8.92	0.05	6.69		
15.00	30.00		Cum	1	15.00	9.13	8.50	8.82	0.05	6.61		
30.00	45.00		Cum	1	15.00	8.50	8.40	8.45	0.05	6.34		
45.00	60.00		Cum	1	15.00	8.40	8.55	8.48	0.05	6.36		
60.00	75.00		Cum	1	15.00	8.55	8.10	8.33	0.05	6.24		
75.00	90.00		Cum	1	15.00	8.10	7.60	7.85	0.05	5.89		
90.00	105.00		Cum	1	9.30	7.60	8.00	7.80	0.05	3.63		
105.00	114.30		Cum	1	15.00	8.00	7.45	7.73	0.05	5.79		
114.30	129.30		Cum	1	15.00	7.45	6.85	7.15	0.05	5.36		
129.30	144.30		Cum	1	15.00	6.85	6.80	6.83	0.05	5.12		
144.30	159.30		Cum	1	15.00	6.80	6.90	6.85	0.05	5.14		
159.30	174.30		Cum	1	15.00	6.90	7.65	7.28	0.05	5.46		
174.30	189.30		Cum	1	3.30	7.65	7.40	7.53	0.05	1.24		
189.30	192.60											
		Cut Portion										
0.00	2.60		Cum	1	2.60	2.10	2.10	2.10	0.05	0.27		
		2nd Main Road To M S Nagar Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	5.10	4.36	4.73	0.05	3.55		
15.00	30.00		Cum	1	15.00	4.36	4.40	4.38	0.05	3.29		
30.00	33.70		Cum	1	3.70	4.40	4.60	4.50	0.05	0.83		
		(From South to North)										
0.00	15.00		Cum	1	15.00	5.45	5.20	5.33	0.05	3.99		
15.00	30.00		Cum	1	15.00	5.20	5.40	5.30	0.05	3.98		
30.00	45.00		Cum	1	15.00	5.40	5.70	5.55	0.05	4.16		
45.00	60.00		Cum	1	15.00	5.70	5.25	5.48	0.05	4.11		
60.00	75.00		Cum	1	15.00	5.25	5.40	5.33	0.05	3.99		
75.00	90.00		Cum	1	15.00	5.40	5.40	5.40	0.05	4.05		

WP (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	15.00	5.40	5.40	5.40	0.05	4.05		
	105.00		Cum	1	15.00	5.40	5.58	5.49	0.05	4.12		
00.00	120.00		Cum	1	15.00	5.58	5.40	5.49	0.05	4.12		
15.00	135.00		Cum	1	15.00	5.40	5.35	5.38	0.05	4.03		
30.00	150.00		Cum	1	15.00	5.35	5.20	5.28	0.05	3.96		
45.00	165.00		Cum	1	15.00	5.20	5.20	5.20	0.05	3.90		
60.00	180.00		Cum	1	15.00	5.20	5.54	5.37	0.05	4.03		
75.00	195.00		Cum	1	2.80	5.54	6.40	5.97	0.05	0.84		
180.00	197.80											
185.00		(From East to West)										
			Cum	1	15.00	3.90	3.65	3.78	0.05	2.83		
	15.00		Cum	1	15.00	3.65	3.68	3.67	0.05	2.75		
0.00	30.00		Cum	1	15.00	3.68	3.98	3.83	0.05	2.87		
15.00	45.00		Cum	1	4.80	3.98	4.20	4.09	0.05	0.98		
30.00	49.80		Cum	1	2.10	4.20	7.50	5.85	0.05	0.61		
45.00	51.90											
49.80		3A Cross Road										
		(From East to West)										
			Cum	1	15.00	3.85	3.63	3.74	0.05	2.81		
0.00	15.00		Cum	1	15.00	3.63	3.63	3.63	0.05	2.72		
15.00	30.00		Cum	1	11.40	3.63	4.32	3.98	0.05	2.27		
30.00	41.40		Cum	1	3.10	4.32	7.35	5.84	0.05	0.90		
41.40	44.50											
		(From North to South)										
			Cum	1	15.00	4.10	3.60	3.85	0.05	2.89		
0.00	15.00		Cum	1	3.60	3.60	3.65	3.63	0.05	0.65		
15.00	18.60											
		5th Cross Road										
		(From North to South)										
			Cum	1	3.40	8.20	6.80	7.50	0.05	1.28		
0.00	3.40		Cum	1	11.60	6.80	6.70	6.75	0.05	3.92		
3.40	15.00		Cum	1	15.00	6.70	6.10	6.40	0.05	4.80		
15.00	30.00		Cum	1	15.00	6.10	6.20	6.15	0.05	4.61		
30.00	45.00		Cum	1	11.60	6.20	6.15	6.18	0.05	3.58		
45.00	56.60											
		Cut Portion										
			Cum	1	12.10	2.40	2.40	2.40	0.05	1.45		
0.00	12.10											
		Hegde Nagara										
		Win Field Garden										
		5th Cross Road (W1941)										
		(From South to North)										
			Cum	1	2.70	10.80	7.45	9.13	0.05	1.23		
0.00	2.70		Cum	1	12.30	7.45	6.70	7.08	0.05	4.35		
2.70	15.00		Cum	1	15.00	6.70	6.65	6.68	0.05	5.01		
15.00	30.00		Cum	1	15.00	6.65	7.00	6.83	0.05	5.12		
30.00	45.00		Cum	1	15.00	7.00	7.50	7.25	0.05	5.44		
45.00	60.00		Cum	1	15.00	7.50	7.00	7.25	0.05	5.44		
60.00	75.00		Cum	1	15.00	7.00	7.00	7.00	0.05	5.25		
75.00	90.00		Cum	1	15.00	7.00	6.85	6.93	0.05	5.19		
90.00	105.00		Cum	1	15.00	6.85	6.25	6.55	0.05	4.91		
105.00	120.00		Cum	1	15.00	6.25	7.05	6.65	0.05	4.99		
120.00	135.00		Cum	1	15.00	7.05	7.05	7.05	0.05	5.29		
135.00	150.00		Cum	1	15.00	7.05	7.05	7.05	0.05	5.29		
150.00	165.00		Cum	1	15.00	7.05	7.05	7.05	0.05	5.29		
165.00	180.00		Cum	1	5.20	7.05	7.40	7.23	0.05	1.88		
180.00	185.20		Cum	1	2.80	7.00	12.00	9.50	0.05	1.33		
185.20	188.00		Cum	1	2.50	8.00	7.90	7.95	0.05	0.99		
188.00	190.50											
		6th Cross Road (W1935)										
		(From South to North)										
0.00	2.00		Cum	1	2.00	7.50	5.90	6.70	0.05	0.67		
2.00	15.00		Cum	1	13.00	5.90	5.95	5.93	0.05	3.85		
15.00	30.00		Cum	1	15.00	5.95	6.00	5.98	0.05	4.48		
30.00	45.00		Cum	1	15.00	6.00	5.50	5.75	0.05	4.31		
45.00	60.00		Cum	1	15.00	5.50	5.35	5.43	0.05	4.07		
60.00	75.00		Cum	1	15.00	5.35	5.55	5.45	0.05	4.09		
75.00	90.00		Cum	1	15.00	5.55	5.55	5.55	0.05	4.16		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
m	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	105.00		Cum	1	15.00	5.55	5.60	5.58	0.05	4.18		
105.00	120.00		Cum	1	15.00	5.60	5.60	5.60	0.05	4.20		
120.00	135.00		Cum	1	15.00	5.60	5.75	5.68	0.05	4.26		
135.00	150.00		Cum	1	15.00	5.75	4.85	5.30	0.05	3.98		
150.00	165.00		Cum	1	15.00	4.85	4.80	4.83	0.05	3.62		
165.00	180.00		Cum	1	15.00	4.80	6.10	5.45	0.05	4.09		
180.00	181.50		Cum	1	1.50	6.10	5.40	5.75	0.05	0.43		
		9th Cross Road										
		(From South to North)										
0.00	2.80		Cum	1	2.80	6.90	4.90	5.90	0.05	0.83		
2.80	15.90		Cum	1	13.10	4.90	4.40	4.65	0.05	3.05		
15.90	30.00		Cum	1	14.10	4.00	5.45	4.73	0.05	3.33		
30.00	45.00		Cum	1	15.00	5.45	5.60	5.53	0.05	4.14		
45.00	60.00		Cum	1	15.00	5.50	5.70	5.60	0.05	4.20		
60.00	75.00		Cum	1	15.00	5.70	5.00	5.35	0.05	4.01		
75.00	79.90		Cum	1	4.90	5.00	5.10	5.05	0.05	1.24		
79.90	89.60		Cum	1	9.70	4.60	4.60	4.60	0.05	2.23		
89.60	90.00		Cum	1	0.40	4.60	5.95	5.28	0.05	0.11		
90.00	105.00		Cum	1	15.00	5.95	5.75	5.85	0.05	4.39		
105.00	116.70		Cum	1	11.70	5.75	5.60	5.68	0.05	3.32		
116.70	126.90		Cum	1	10.20	4.60	4.85	4.73	0.05	2.41		
126.90	137.90		Cum	1	11.00	5.70	5.80	5.75	0.05	3.16		
		MSR Mansion Road										
		(North to South)										
0.00	5.80		Cum	1	5.80	5.75	7.15	6.45	0.05	1.87		
5.80	9.70		Cum	1	3.90	10.70	8.40	9.55	0.05	1.86		
9.70	15.00		Cum	1	5.30	8.40	8.25	8.33	0.05	2.21		
15.00	30.00		Cum	1	15.00	8.25	7.40	7.83	0.05	5.87		
30.00	45.00		Cum	1	15.00	7.40	6.85	7.13	0.05	5.34		
45.00	50.00		Cum	1	5.00	6.85	7.10	6.98	0.05	1.74		
		Nisarga Layout										
		7th Cross, Zayan Travels Car Service Centre Road, North To South										
0.00	15.00		Cum	1	15.00	5.00	4.85	4.93	0.05	3.69		
15.00	30.00		Cum	1	15.00	4.85	4.60	4.73	0.05	3.54		
30.00	45.00		Cum	1	15.00	4.60	5.15	4.88	0.05	3.66		
45.00	60.00		Cum	1	15.00	5.15	5.00	5.08	0.05	3.81		
60.00	75.00		Cum	1	15.00	5.00	5.10	5.05	0.05	3.79		
75.00	90.00		Cum	1	15.00	5.10	5.00	5.05	0.05	3.79		
90.00	101.50		Cum	1	11.50	5.00	4.70	4.85	0.05	2.79		
		West To East										
0.00	15.00		Cum	1	15.00	4.90	4.80	4.85	0.05	3.64		
15.00	15.70		Cum	1	0.70	4.80	4.80	4.80	0.05	0.17		
15.70	30.00		Cum	1	14.30	5.30	5.60	5.45	0.05	3.90		
30.00	45.00		Cum	1	15.00	5.60	5.15	5.38	0.05	4.03		
45.00	46.70		Cum	1	1.70	5.15	5.15	5.15	0.05	0.44		
46.70	51.60		Cum	1	4.90	4.15	3.95	4.05	0.05	0.99		
51.60	56.20		Cum	1	4.60	5.30	5.25	5.28	0.05	1.21		
56.20	64.60		Cum	1	8.40	4.20	4.30	4.25	0.05	1.79		
64.60	75.00		Cum	1	10.40	5.30	5.35	5.33	0.05	2.77		
75.00	76.60		Cum	1	1.60	5.35	5.36	5.36	0.05	0.43		
		5th Cross Road, North To South										
0.00	11.10		Cum	1	11.10	5.70	5.90	5.80	0.05	3.22		
11.10	20.00		Cum	1	8.90	5.10	5.35	5.23	0.05	2.33		
20.00	23.80		Cum	1	3.80	7.00	6.95	6.98	0.05	1.33		
23.80	30.00		Cum	1	6.20	6.05	5.95	6.00	0.05	1.86		
30.00	45.00		Cum	1	15.00	5.95	5.50	5.73	0.05	4.29		
45.00	60.00		Cum	1	15.00	5.50	6.00	5.75	0.05	4.31		
60.00	66.90		Cum	1	6.90	6.00	6.30	6.15	0.05	2.12		
66.90	75.00		Cum	1	8.10	4.90	5.70	5.30	0.05	2.15		
75.00	75.60		Cum	1	0.60	5.70	5.65	5.68	0.05	0.17		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	76.80		Cum	1	1.20	2.95	3.00	2.98	0.05	0.18		
		Mithun White Pearl Apartment Road										
		(East To West)										
			Cum	1	15.00	6.60	6.75	6.68	0.05	5.01		
0.00	15.00		Cum	1	15.00	6.75	6.50	6.63	0.05	4.97		
15.00	30.00		Cum	1	15.00	6.50	6.45	6.48	0.05	4.86		
30.00	45.00		Cum	1	15.00	6.45	6.45	6.45	0.05	4.84		
45.00	60.00		Cum	1	15.00	6.45	6.25	6.35	0.05	4.76		
60.00	75.00		Cum	1	15.00	6.25	6.20	6.23	0.05	4.67		
75.00	90.00		Cum	1	6.40	6.20	5.85	6.03	0.05	1.93		
90.00	96.40											
		Venkateshwara Layout										
		3rd Cross Road										
		South to North										
			Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
195.00	210.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
210.00	220.00											
		4th Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
195.00	210.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
210.00	220.00											
		5th Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
30.00	45.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
45.00	60.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
60.00	75.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
75.00	90.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
90.00	105.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
105.00	120.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
120.00	135.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
135.00	150.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
150.00	165.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
165.00	180.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
180.00	195.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
195.00	210.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	220.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
		Chembar	Cum	-1	0.64				0.05	-0.03		
								Area of				
		Katgenahalli										
		Muneshwara Provision Store Beside Road										
		Kalidas Layout										
		3rd Main Road										
		(From North to South)										
			Cum	1	15.00	6.70	6.65	6.68	0.05	5.01		
0.00	15.00		Cum	1	15.00	6.65	6.65	6.65	0.05	4.99		
15.00	30.00		Cum	1	15.00	6.65	6.00	6.33	0.05	4.74		
30.00	45.00		Cum	1	15.00	6.00	5.80	5.90	0.05	4.43		
45.00	60.00		Cum	1	6.40	5.80	5.60	5.70	0.05	1.82		
60.00	66.40		Cum	1	8.60	5.60	5.60	5.60	0.05	2.41		
66.40	75.00		Cum	1	15.00	5.60	5.50	5.55	0.05	4.16		
75.00	90.00		Cum	1	15.00	5.50	5.80	5.65	0.05	4.24		
90.00	105.00		Cum	1	8.00	5.80	4.30	5.05	0.05	2.02		
105.00	113.00											
		Mk Provision Store Road										
		(From East to West)										
			Cum	1	11.20	6.20	6.10	6.15	0.05	3.44		
0.00	11.20		Cum	1	8.40	5.60	4.94	5.27	0.05	2.21		
11.20	19.60		Cum	1	10.40	5.40	5.30	5.35	0.05	2.78		
19.60	30.00		Cum	1	10.20	5.30	5.40	5.35	0.05	2.73		
30.00	40.20		Cum	1	4.80	5.40	6.30	5.85	0.05	1.40		
40.20	45.00		Cum	1	2.50	6.30	7.00	6.65	0.05	0.83		
45.00	47.50		Cum	1	12.50	5.00	4.50	4.75	0.05	2.97		
47.50	60.00		Cum	1	15.00	4.50	5.75	5.13	0.05	3.84		
60.00	75.00		Cum	1	15.00	5.75	5.38	5.57	0.05	4.17		
75.00	90.00		Cum	1	15.00	5.38	5.10	5.24	0.05	3.93		
90.00	105.00		Cum	1	15.00	5.10	4.85	4.98	0.05	3.73		
105.00	120.00		Cum	1	15.00	4.85	4.80	4.83	0.05	3.62		
120.00	135.00		Cum	1	15.00	4.80	5.50	5.15	0.05	3.86		
135.00	150.00		Cum	1	5.00	5.50	5.88	5.69	0.05	1.42		
150.00	155.00		Cum	1	Triangular Portion 9.5*8.2*12.55=977.65			977.65	0.05	48.88		
			Cum	1	Triangular Portion 10.5*3.3*11=381.15			381.15	0.05	19.06		
		Deduction										
0.00	1.40		Cum	-1	1.40	1.00	1.00	1.00	0.05	-0.07		
		Cross Road - 2										
		(From North to South)										
0.00	4.30		Cum	1	4.30	5.10	5.00	5.05	0.05	1.09		
4.30	15.00		Cum	1	10.70	5.00	5.10	5.05	0.05	2.70		
15.00	20.60		Cum	1	5.60	5.10	5.30	5.20	0.05	1.46		
20.60	30.00		Cum	1	9.40	6.65	6.20	6.43	0.05	3.02		
30.00	40.60		Cum	1	10.60	6.20	6.60	6.40	0.05	3.39		
40.60	45.00		Cum	1	4.40	6.60	5.90	6.25	0.05	1.38		
45.00	60.00		Cum	1	15.00	5.90	5.95	5.93	0.05	4.44		
60.00	75.00		Cum	1	15.00	5.95	5.85	5.90	0.05	4.43		
75.00	90.00		Cum	1	15.00	5.85	6.38	6.12	0.05	4.59		
90.00	105.00		Cum	1	15.00	6.38	5.50	5.94	0.05	4.46		
105.00	120.00		Cum	1	15.00	5.50	5.69	5.60	0.05	4.20		
120.00	123.00		Cum	1	3.00	5.69	5.00	5.35	0.05	0.80		
		Kattigenahalli										
		Durgamba Layout										
		Amulya Family Restaurant Road (N-S)										
0.00	15.00		Cum	1	15.00	6.90	6.40	6.65	0.05	4.99		
15.00	30.00		Cum	1	15.00	6.40	6.05	6.23	0.05	4.67		
30.00	45.00		Cum	1	15.00	5.60	5.30	5.45	0.05	4.09		

(Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	15.00	5.30	4.95	5.13	0.05	3.84		
	60.00		Cum	1	15.00	4.95	5.05	5.00	0.05	3.75		
60.00	75.00		Cum	1	6.00	5.05	5.05	5.05	0.05	1.52		
75.00	81.00		Cum	1	9.00	5.70	5.90	5.80	0.05	2.61		
81.00	90.00		Cum	1	15.00	5.90	5.30	5.60	0.05	4.20		
90.00	105.00		Cum	1	13.80	5.30	4.60	4.95	0.05	3.42		
105.00	118.80		Cum	1	9.10	5.80	5.85	5.83	0.05	2.65		
118.80	127.90		Cum	1	7.10	4.95	4.85	4.90	0.05	1.74		
127.90	135.00		Cum	1	2.10	4.85	5.05	4.95	0.05	0.52		
135.00	137.10		Cum	1	12.90	4.35	4.95	4.65	0.05	3.00		
137.10	150.00		Cum	1	15.00	4.95	4.60	4.78	0.05	3.58		
150.00	165.00		Cum	1	15.00	4.60	5.25	4.93	0.05	3.69		
165.00	180.00		Cum	1	2.50	5.25	5.15	5.20	0.05	0.65		
180.00	182.50		Cum	1	12.50	5.85	6.60	6.23	0.05	3.89		
182.50	195.00		Cum	1	15.00	6.60	6.15	6.38	0.05	4.78		
195.00	210.00		Cum	1	8.00	6.15	6.00	6.08	0.05	2.43		
210.00	218.00											
		Kaustaba House Road #33 (W-E)										
			Cum	1	6.30	7.45	7.55	7.50	0.05	2.36		
0.00	6.30		Cum	1	8.70	6.80	6.48	6.64	0.05	2.89		
6.30	15.00		Cum	1	15.00	6.48	6.00	6.24	0.05	4.68		
15.00	30.00		Cum	1	15.00	6.00	5.70	5.85	0.05	4.39		
30.00	45.00		Cum	1	12.90	5.70	6.05	5.88	0.05	3.79		
45.00	57.90		Cum	1	2.10	6.95	7.70	7.33	0.05	0.77		
57.90	60.00		Cum	1	3.60	7.70	7.65	7.68	0.05	1.38		
60.00	63.60											
		Sukruthi House Road #26 (S-N)										
			Cum	1	8.30	5.60	5.90	5.75	0.05	2.39		
0.00	8.30		Cum	1	6.70	5.35	4.90	5.13	0.05	1.72		
8.30	15.00		Cum	1	15.00	4.90	5.80	5.35	0.05	4.01		
15.00	30.00		Cum	1	15.00	5.80	5.35	5.58	0.05	4.18		
30.00	45.00		Cum	1	15.00	5.35	5.30	5.33	0.05	3.99		
45.00	60.00		Cum	1	0.50	5.30	5.30	5.30	0.05	0.13		
60.00	60.50		Cum	1	14.50	5.85	6.20	6.03	0.05	4.37		
60.50	75.00		Cum	1	15.00	6.20	5.40	5.80	0.05	4.35		
75.00	90.00		Cum	1	8.70	5.40	5.20	5.30	0.05	2.31		
90.00	98.70		Cum	1	6.30	4.40	4.95	4.68	0.05	1.47		
98.70	105.00		Cum	1	3.20	4.95	4.95	4.95	0.05	0.79		
105.00	108.20		Cum	1	4.00	5.50	5.20	5.35	0.05	1.07		
108.20	112.20		Cum	1	7.80	4.40	4.60	4.50	0.05	1.76		
112.20	120.00		Cum	1	5.80	4.60	4.50	4.55	0.05	1.32		
120.00	125.80		Cum	1	9.90	4.00	4.45	4.23	0.05	2.09		
125.80	135.70		Cum	1	8.20	5.60	5.95	5.78	0.05	2.37		
135.70	143.90		Cum	1	6.10	6.65	5.75	6.20	0.05	1.89		
143.90	150.00		Cum	1	14.30	5.75	5.85	5.80	0.05	4.15		
150.00	164.30											
		SP Singh House Road (E-W)										
0.00	15.00		Cum	1	15.00	6.35	5.65	6.00	0.05	4.50		
15.00	19.10		Cum	1	4.10	5.65	6.00	5.83	0.05	1.19		
19.10	30.00		Cum	1	10.90	5.20	5.65	5.43	0.05	2.96		
30.00	34.20		Cum	1	4.20	5.65	6.10	5.88	0.05	1.23		
		Form mrd Main To Muneshwara provsion										
0.00	1.70		Cum	1	1.70	5.05	5.05	5.05	0.05	0.43		
1.70	15.00		Cum	1	13.30	7.30	7.40	7.35	0.05	4.89		
15.00	30.00		Cum	1	15.00	7.40	7.10	7.25	0.05	5.44		
30.00	45.00		Cum	1	15.00	7.10	6.75	6.93	0.05	5.19		
45.00	60.00		Cum	1	15.00	6.75	7.55	7.15	0.05	5.36		
60.00	75.00		Cum	1	15.00	7.55	6.45	7.00	0.05	5.25		
75.00	77.80		Cum	1	2.80	6.45	5.70	6.08	0.05	0.85		
77.80	90.00		Cum	1	12.20	6.80	7.15	6.98	0.05	4.25		
90.00	95.90		Cum	1	5.90	7.15	6.95	7.05	0.05	2.08		
95.90	105.00		Cum	1	9.10	6.25	6.30	6.28	0.05	2.86		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	12.90	6.30	5.90	6.10	0.05	3.93		
	117.90		Cum	1	2.10	6.75	6.80	6.78	0.05	0.71		
	120.00		Cum	1	4.80	6.80	5.80	6.30	0.05	1.51		
	124.80											
		Deduction										
		Chamber	Cum	-1	0.70	1.00	1.00	1.00	0.05	-0.04		
		Manhole	Cum	-1	0.64				0.05	-0.03		
							Area of Circle =					
		Manhole	Cum	-1	1.13				0.05	-0.06		
							Area of Circle =					
		Cross Road 3 Near Pyramid apartment (North to South)										
			Cum	1	2.90	6.40	6.35	6.38	0.05	0.92		
2.00	2.90		Cum	1	12.10	6.35	5.75	6.05	0.05	3.66		
2.90	15.00		Cum	1	15.00	5.75	5.70	5.73	0.05	4.29		
5.00	30.00		Cum	1	14.00	5.70	5.10	5.40	0.05	3.78		
30.00	44.00											
		For Road Cut portion Green Garden Main Road (West to East)										
			Cum	1	2.00	1.60	1.60	1.60	0.05	0.16		
2.00	4.00		Cum	1	4.00	1.20	1.20	1.20	0.05	0.24		
7.00	11.00		Cum	1	2.00	1.30	1.30	1.30	0.05	0.13		
13.00	15.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
17.00	22.00		Cum	1	4.00	2.00	2.00	2.00	0.05	0.40		
25.00	29.00		Cum	1	12.70	1.60	1.60	1.60	0.05	1.02		
30.00	42.70		Cum	1	2.30	2.10	2.10	2.10	0.05	0.24		
42.70	45.00		Cum	1	8.70	1.10	1.10	1.10	0.05	0.48		
45.00	53.70		Cum	1	6.30	1.60	1.60	1.60	0.05	0.50		
53.70	60.00		Cum	1	4.00	1.60	1.60	1.60	0.05	0.32		
62.00	66.00		Cum	1	2.00	1.80	1.80	1.80	0.05	0.18		
68.00	70.00		Cum	1	3.00	1.40	1.40	1.40	0.05	0.21		
72.00	75.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
77.00	88.00		Cum	1	9.20	1.00	1.00	1.00	0.05	0.46		
93.80	103.00		Cum	1	10.00	1.70	1.70	1.70	0.05	0.85		
107.00	117.00		Cum	1	6.90	1.30	1.30	1.30	0.05	0.45		
120.00	126.90		Cum	1	2.00	1.40	1.40	1.40	0.05	0.14		
126.00	130.00		Cum	1	8.00	1.60	1.60	1.60	0.05	0.64		
132.00	140.00		Cum	1	4.00	2.10	2.10	2.10	0.05	0.42		
148.00	152.00		Cum	1	5.70	1.60	1.60	1.60	0.05	0.46		
154.30	160.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
163.00	169.00											
		Cross Road-4 (South to North)										
0.00	1.60		Cum	1	1.60	1.30	1.30	1.30	0.05	0.10		
4.00	12.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
15.00	21.00		Cum	1	6.00	1.60	1.60	1.60	0.05	0.48		
23.50	30.00		Cum	1	6.50	2.60	2.60	2.60	0.05	0.85		
30.00	33.70		Cum	1	3.70	3.00	3.00	3.00	0.05	0.56		
		Sri Ganga House Road East to West										
3.80	13.20		Cum	1	9.40	1.00	1.00	1.00	0.05	0.47		
13.20	15.00		Cum	1	1.80	3.00	3.00	3.00	0.05	0.27		
17.00	26.00		Cum	1	9.00	2.40	2.40	2.40	0.05	1.08		
27.40	30.00		Cum	1	2.60	1.60	1.60	1.60	0.05	0.21		
33.90	41.00		Cum	1	8.00	1.90	1.90	1.90	0.05	0.76		
47.00	57.60		Cum	1	10.60	3.00	3.00	3.00	0.05	1.59		
62.00	66.00		Cum	1	4.00	1.70	1.70	1.70	0.05	0.34		
		Cross Road-3 (North to South)										
0.00	1.70		Cum	1	1.70	3.00	3.00	3.00	0.05	0.26		
3.30	10.00		Cum	1	6.70	1.30	1.30	1.30	0.05	0.44		
12.00	14.00		Cum	1	2.00	0.90	0.90	0.90	0.05	0.09		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
	21.00		Cum	1	4.00	1.70	1.70	1.70	0.05	0.34		
	29.00		Cum	1	5.00	2.20	2.20	2.20	0.05	0.55		
	38.00		Cum	1	5.00	1.70	1.70	1.70	0.05	0.43		
	44.00		Cum	1	4.00	1.10	1.10	1.10	0.05	0.22		
	46.10		Cum	1	1.10	1.70	1.70	1.70	0.05	0.09		
	48.90		Cum	1	2.80	2.00	2.00	2.00	0.05	0.28		
		Cross Road 2										
		(South to North)										
	9.00		Cum	1	6.00	1.90	1.90	1.90	0.05	0.57		
	15.00		Cum	1	3.00	2.20	2.20	2.20	0.05	0.33		
	21.10		Cum	1	3.10	3.10	3.10	3.10	0.05	0.48		
	30.00		Cum	1	7.00	1.75	1.75	1.75	0.05	0.61		
	45.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
	51.00		Cum	1	3.00	1.00	1.00	1.00	0.05	0.15		
	58.00		Cum	1	5.00	1.85	1.85	1.85	0.05	0.46		
	72.00		Cum	1	7.80	1.50	1.50	1.50	0.05	0.59		
	87.00		Cum	1	9.00	2.10	2.10	2.10	0.05	0.95		
	98.00		Cum	1	5.40	1.70	1.70	1.70	0.05	0.46		
		Cross Road 1										
		(North to South)										
	12.20		Cum	1	7.60	1.20	1.20	1.20	0.05	0.46		
	27.00		Cum	1	9.40	1.80	1.80	1.80	0.05	0.85		
	41.00		Cum	1	8.00	2.30	2.30	2.30	0.05	0.92		
	58.00		Cum	1	11.00	2.70	2.70	2.70	0.05	1.49		
	71.00		Cum	1	8.20	1.60	1.60	1.60	0.05	0.66		
	88.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
	98.00		Cum	1	4.00	1.70	1.70	1.70	0.05	0.34		
		Pyramid apartment main road										
		(East to West)										
	1.10		Cum	1	1.10	8.16	8.15	8.16	0.05	0.45		
	2.40		Cum	1	1.30	8.15	6.80	7.48	0.05	0.49		
	4.70		Cum	1	2.30	6.80	6.60	6.70	0.05	0.77		
	12.40		Cum	1	7.70	7.65	7.85	7.75	0.05	2.98		
	15.00		Cum	1	2.60	7.85	7.70	7.78	0.05	1.01		
	30.00		Cum	1	15.00	7.70	8.35	8.03	0.05	6.02		
	32.00		Cum	1	2.00	8.35	8.35	8.35	0.05	0.84		
	45.00		Cum	1	13.00	8.35	8.50	8.43	0.05	5.48		
	60.00		Cum	1	15.00	8.50	8.65	8.58	0.05	6.43		
	75.00		Cum	1	15.00	8.65	8.70	8.68	0.05	6.51		
	81.10		Cum	1	6.10	8.70	8.75	8.73	0.05	2.66		
	90.00		Cum	1	8.90	8.75	8.20	8.48	0.05	3.77		
	105.00		Cum	1	15.00	8.20	8.45	8.33	0.05	6.24		
	120.00		Cum	1	15.00	8.45	8.38	8.42	0.05	6.31		
	128.00		Cum	1	8.00	8.38	8.40	8.39	0.05	3.36		
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
	11.00		Cum	1	5.40	1.40	1.40	1.40	0.05	0.38		
	27.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
	32.80		Cum	1	2.80	1.70	1.70	1.70	0.05	0.24		
	42.30		Cum	1	9.50	2.00	2.00	2.00	0.05	0.95		
	45.10		Cum	1	2.80	1.30	1.30	1.30	0.05	0.18		
	48.30		Cum	1	3.20	1.00	1.00	1.00	0.05	0.16		
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
	13.00		Cum	1	8.50	1.70	1.70	1.70	0.05	0.72		
	27.00		Cum	1	11.00	1.40	1.40	1.40	0.05	0.77		
	41.00		Cum	1	7.00	1.70	1.70	1.70	0.05	0.60		
	51.70		Cum	1	3.70	1.25	1.25	1.25	0.05	0.23		
	58.70		Cum	1	5.70	2.10	2.10	2.10	0.05	0.60		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	71.00		Cum	1	8.00	1.70	1.70	1.70	0.05	0.68		
71.00	86.00		Cum	1	7.00	1.40	1.40	1.40	0.05	0.49		
86.00	102.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
102.00	117.00		Cum	1	10.60	1.80	1.80	1.80	0.05	0.95		
117.00	125.00		Cum	1	3.00	1.20	1.20	1.20	0.05	0.18		
		Profile Correction										
		Green Garden Main Road										
		(West to East)										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.05	0.68		
30.00	42.70		Cum	1	12.70	1.20	1.20	1.20	0.05	0.76		
42.70	45.00		Cum	1	2.30	0.90	0.90	0.90	0.05	0.10		
45.00	53.70		Cum	1	8.70	1.00	1.00	1.00	0.05	0.44		
53.70	60.00		Cum	1	6.30	1.30	1.30	1.30	0.05	0.41		
60.00	75.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
75.00	90.00		Cum	1	15.00	1.15	1.15	1.15	0.05	0.86		
90.00	105.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
105.00	120.00		Cum	1	15.00	1.15	1.15	1.15	0.05	0.86		
120.00	126.90		Cum	1	6.90	0.75	0.75	0.75	0.05	0.26		
126.90	130.00		Cum	1	3.10	0.90	0.90	0.90	0.05	0.14		
130.00	145.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
145.00	154.30		Cum	1	9.30	1.00	1.00	1.00	0.05	0.47		
154.30	160.00		Cum	1	5.70	0.95	0.95	0.95	0.05	0.27		
160.00	171.40		Cum	1	11.40	1.00	1.00	1.00	0.05	0.57		
		Cross Road-4										
		(South to North)										
0.00	1.60		Cum	1	1.60	1.10	1.10	1.10	0.05	0.09		
1.60	15.00		Cum	1	13.40	1.20	1.20	1.20	0.05	0.80		
15.00	23.50		Cum	1	8.50	0.90	0.90	0.90	0.05	0.38		
23.50	30.00		Cum	1	6.50	1.00	1.00	1.00	0.05	0.33		
30.00	33.70		Cum	1	3.70	1.20	1.20	1.20	0.05	0.22		
		Sri Ganga House Road										
		East to West										
0.00	3.80		Cum	1	3.80	0.90	0.90	0.90	0.05	0.17		
3.80	13.20		Cum	1	9.40	1.00	1.00	1.00	0.05	0.47		
13.20	15.00		Cum	1	1.80	1.30	1.30	1.30	0.05	0.12		
15.00	27.40		Cum	1	12.40	1.00	1.00	1.00	0.05	0.62		
27.40	30.00		Cum	1	2.60	1.20	1.20	1.20	0.05	0.16		
30.00	45.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
45.00	60.00		Cum	1	15.00	1.15	1.15	1.15	0.05	0.86		
60.00	69.30		Cum	1	9.30	0.75	0.75	0.75	0.05	0.35		
		Cross Road-3										
		(North to South)										
0.00	1.70		Cum	1	1.70	1.00	1.00	1.00	0.05	0.09		
1.70	15.00		Cum	1	13.30	0.90	0.90	0.90	0.05	0.60		
15.00	30.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
30.00	45.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
45.00	46.10		Cum	1	1.10	1.30	1.30	1.30	0.05	0.07		
46.10	48.90		Cum	1	2.80	1.40	1.40	1.40	0.05	0.20		
		Cross Road 2										
		(South to North)										
0.00	11.80		Cum	1	11.80	0.90	0.90	0.90	0.05	0.53		
11.80	15.00		Cum	1	3.20	1.00	1.00	1.00	0.05	0.16		
15.00	21.10		Cum	1	6.10	1.30	1.30	1.30	0.05	0.40		
21.10	30.00		Cum	1	8.90	1.00	1.00	1.00	0.05	0.45		
30.00	45.00		Cum	1	15.00	1.15	1.15	1.15	0.05	0.86		
45.00	60.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
60.00	75.00		Cum	1	15.00	1.15	1.15	1.15	0.05	0.86		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.05	0.68		
90.00	100.30		Cum	1	10.30	1.10	1.10	1.10	0.05	0.57		
100.30	102.40		Cum	1	2.10	1.20	1.20	1.20	0.05	0.13		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road 1										
		(North to South)										
			Cum	1	2.90	1.00	1.00	1.00	0.05	0.15		
	2.90		Cum	1	12.10	0.90	0.90	0.90	0.05	0.54		
.00	15.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
.90	30.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
.00	45.00		Cum	1	15.00	1.30	1.30	1.30	0.05	0.98		
.00	60.00		Cum	1	15.00	1.40	1.40	1.40	0.05	1.05		
.00	75.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
.00	90.00		Cum	1	12.30	1.30	1.30	1.30	0.05	0.80		
.00	102.30											
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
	3.60		Cum	1	3.60	1.30	1.30	1.30	0.05	0.23		
.00	15.00		Cum	1	11.40	1.00	1.00	1.00	0.05	0.57		
.60	30.00		Cum	1	15.00	1.20	1.20	1.20	0.05	0.90		
.00	32.80		Cum	1	2.80	1.00	1.00	1.00	0.05	0.14		
.00	42.30		Cum	1	9.50	1.15	1.15	1.15	0.05	0.55		
.80	45.10		Cum	1	2.80	0.75	0.75	0.75	0.05	0.11		
.30	48.30		Cum	1	3.20	1.30	1.30	1.30	0.05	0.21		
.10												
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
.00	4.50		Cum	1	4.50	1.15	1.15	1.15	0.05	0.26		
.50	15.00		Cum	1	10.50	1.00	1.00	1.00	0.05	0.53		
.00	30.00		Cum	1	15.00	1.15	1.15	1.15	0.05	0.86		
.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.05	0.68		
.00	51.70		Cum	1	6.70	1.10	1.10	1.10	0.05	0.37		
.20	60.00		Cum	1	7.80	1.00	1.00	1.00	0.05	0.39		
.00	75.00		Cum	1	15.00	1.15	1.15	1.15	0.05	0.86		
.00	90.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
.00	105.00		Cum	1	15.00	1.30	1.30	1.30	0.05	0.98		
.00	120.00		Cum	1	15.00	1.15	1.15	5.63	0.05	4.22		
.00	127.20		Cum	1	7.20	0.90	0.90	5.58	0.05	2.01		
		Car 24 Beside Road										
		From Agrahara Main Road to Lake										
		East to West										
.00	15.00		Cum	1	15.00	4.80	4.60	4.70	0.05	3.53		
.00	27.00		Cum	1	12.00	4.60	4.65	4.63	0.05	2.78		
.00	30.00		Cum	1	3.00	5.40	5.70	5.55	0.05	0.83		
.00	45.00		Cum	1	15.00	5.70	5.70	5.70	0.05	4.28		
.00	60.00		Cum	1	15.00	5.70	6.30	6.00	0.05	4.50		
.00	75.00		Cum	1	15.00	6.30	6.30	6.30	0.05	4.73		
.00	90.00		Cum	1	15.00	6.30	6.50	6.40	0.05	4.80		
.00	105.00		Cum	1	15.00	6.50	6.65	6.58	0.05	4.93		
.00	120.00		Cum	1	15.00	6.65	6.40	6.53	0.05	4.89		
.00	135.00		Cum	1	15.00	6.40	6.20	6.30	0.05	4.73		
.00	150.00		Cum	1	15.00	6.20	6.10	6.15	0.05	4.61		
.00	165.00		Cum	1	15.00	6.10	6.30	6.20	0.05	4.65		
.00	180.00		Cum	1	15.00	6.30	6.10	6.20	0.05	4.65		
.00	195.00		Cum	1	15.00	6.10	6.25	6.18	0.05	4.63		
.00	210.00		Cum	1	15.00	6.25	6.50	6.38	0.05	4.78		
.00	225.00		Cum	1	15.00	6.50	6.40	6.45	0.05	4.84		
.00	240.00		Cum	1	15.00	6.40	6.50	6.45	0.05	4.84		
.00	255.00		Cum	1	15.00	6.50	6.65	6.58	0.05	4.93		
.00	270.00		Cum	1	15.00	6.65	6.70	6.68	0.05	5.01		
.00	285.00		Cum	1	15.00	6.70	6.45	6.58	0.05	4.93		
.00	300.00		Cum	1	15.00	6.45	6.20	6.33	0.05	4.74		
.00	315.00		Cum	1	15.00	6.20	6.10	6.15	0.05	4.61		
.00	330.00		Cum	1	15.00	6.10	6.10	6.10	0.05	4.58		
.00	345.00		Cum	1	15.00	6.10	6.00	6.05	0.05	4.54		
.00	360.00		Cum	1	15.00	6.00	6.60	6.30	0.05	4.73		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg.B	Depth (m)	Quantity	Rate in Rs.	Amount in Rs.
0.00	375.00		Cum	1	15.00	6.60	6.00	6.30	0.05	4.73		
375.00	390.00		Cum	1	15.00	6.00	6.10	6.05	0.05	4.54		
390.00	405.00		Cum	1	15.00	6.10	6.30	6.20	0.05	4.65		
405.00	410.00		Cum	1	5.00	6.30	6.40	6.35	0.05	1.59		
410.00	419.00		Cum	1	9.00	4.70	4.50	4.60	0.05	2.07		
419.00	420.00		Cum	1	1.00	6.30	6.30	6.30	0.05	0.32		
420.00	435.00		Cum	1	15.00	6.30	6.30	6.30	0.05	4.73		
435.00	450.00		Cum	1	15.00	6.30	6.80	6.55	0.05	4.91		
450.00	465.00		Cum	1	15.00	6.80	7.10	6.95	0.05	5.21		
465.00	480.00		Cum	1	15.00	7.10	5.80	6.45	0.05	4.84		
480.00	495.00		Cum	1	15.00	5.80	5.20	5.50	0.05	4.13		
495.00	510.00		Cum	1	15.00	5.20	3.95	4.58	0.05	3.43		
510.00	512.00		Cum	1	2.00	3.95	3.80	3.88	0.05	0.39		
512.00	525.00		Cum	1	13.00	4.70	5.45	5.08	0.05	3.30		
525.00	540.00		Cum	1	15.00	5.45	6.10	5.78	0.05	4.33		
540.00	546.00		Cum	1	6.00	6.10	5.50	5.80	0.05	1.74		
		Cross Road-1										
		South to North										
0.00	6.00		Cum	1	6.00	12.00	5.90	8.95	0.05	2.69		
6.00	12.00		Cum	1	6.00	5.90	5.00	5.45	0.05	1.64		
12.00	15.00		Cum	1	3.00	6.00	6.00	6.00	0.05	0.90		
15.00	19.00		Cum	1	4.00	6.00	5.70	5.85	0.05	1.17		
		Cross Road-2										
		South to north										
0.00	15.00		Cum	1	15.00	6.50	6.00	6.25	0.05	4.69		
15.00	30.00		Cum	1	15.00	6.00	6.00	6.00	0.05	4.50		
30.00	45.00		Cum	1	15.00	6.00	6.00	6.00	0.05	4.50		
45.00	60.00		Cum	1	15.00	6.00	6.30	6.15	0.05	4.61		
60.00	67.70		Cum	1	7.70	6.30	6.60	6.45	0.05	2.48		
67.70	69.70		Cum	1	2.00	6.60	7.30	6.95	0.05	0.70		
		MCECHS layout										
		22nd Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
30.00	45.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
45.00	60.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
60.00	75.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
75.00	90.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
90.00	105.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
105.00	120.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
120.00	135.00		Cum	1	15.00	0.75	0.75	0.75	0.05	0.56		
135.00	141.10		Cum	1	6.10	0.75	0.75	0.75	0.05	0.23		
		Vidhana Soudha Layout										
		(From North to South)										
0.00	15.00		Cum	1	15.00	6.10	5.45	5.78	0.05	4.33		
15.00	29.30		Cum	1	14.30	5.45	8.30	6.88	0.05	4.92		
		(From East to West)										
0.00	15.00		Cum	1	15.00	9.40	8.90	9.15	0.05	6.86		
15.00	30.00		Cum	1	15.00	8.90	8.60	8.75	0.05	6.56		
30.00	45.00		Cum	1	15.00	8.60	8.90	8.75	0.05	6.56		
45.00	60.00		Cum	1	15.00	8.90	8.20	8.55	0.05	6.41		
60.00	75.00		Cum	1	15.00	8.20	8.25	8.23	0.05	6.17		
75.00	90.00		Cum	1	15.00	8.25	8.50	8.38	0.05	6.28		
90.00	105.00		Cum	1	15.00	8.50	8.30	8.40	0.05	6.30		
105.00	117.80		Cum	1	12.80	8.30	8.25	8.28	0.05	5.30		
117.80	125.10		Cum	1	7.30	11.35	11.25	11.30	0.05	4.12		
125.10	135.00		Cum	1	9.90	8.20	8.05	8.13	0.05	4.02		
135.00	150.00		Cum	1	15.00	8.05	8.05	8.05	0.05	6.04		
150.00	150.90		Cum	1	0.90	10.95	10.95	10.95	0.05	0.49		
150.90	165.00		Cum	1	14.10	8.30	8.35	8.33	0.05	5.87		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	180.00		Cum	1	15.00	8.35	8.42	8.39	0.05	6.29		
180.00	184.90		Cum	1	4.90	8.42	8.55	8.49	0.05	2.08		
184.90	193.50		Cum	1	8.60	11.20	11.30	11.25	0.05	4.84		
193.50	195.00		Cum	1	1.50	8.30	8.30	8.30	0.05	0.62		
195.00	210.00		Cum	1	15.00	8.30	8.15	8.23	0.05	6.17		
210.00	225.00		Cum	1	15.00	8.15	8.30	8.23	0.05	6.17		
225.00	240.00		Cum	1	15.00	8.30	9.00	8.65	0.05	6.49		
240.00	255.00		Cum	1	15.00	9.00	8.85	8.93	0.05	6.69		
255.00	258.00		Cum	1	3.00	8.85	8.25	8.55	0.05	1.28		
258.00	265.10		Cum	1	7.10	9.70	9.80	9.75	0.05	3.46		
265.10	270.00		Cum	1	4.90	8.40	8.35	8.38	0.05	2.05		
270.00	285.00		Cum	1	15.00	8.35	8.25	8.30	0.05	6.23		
285.00	291.00		Cum	1	6.00	8.25	8.20	8.23	0.05	2.47		
291.00	299.80		Cum	1	8.80	9.55	9.40	9.48	0.05	4.17		
299.80	300.00		Cum	1	0.20	8.15	8.14	8.15	0.05	0.08		
300.00	301.00		Cum	1	1.00	8.14	8.15	8.15	0.05	0.41		
301.00	307.30		Cum	1	6.30	9.81	9.80	9.81	0.05	3.09		
307.30	315.00		Cum	1	7.70	8.10	8.15	8.13	0.05	3.13		
315.00	323.00		Cum	1	8.00	8.15	8.25	8.20	0.05	3.28		
323.00	332.00		Cum	1	9.00	9.60	9.60	9.60	0.05	4.32		
332.00	343.00		Cum	1	11.00	9.40	9.60	9.50	0.05	5.23		
343.00	345.00		Cum	1	2.00	8.10	8.20	8.15	0.05	0.82		
345.00	358.90		Cum	1	13.90	8.20	8.15	8.18	0.05	5.68		
358.90	368.10		Cum	1	9.20	9.70	9.71	9.71	0.05	4.46		
368.10	375.00		Cum	1	6.90	8.15	8.15	8.15	0.05	2.81		
375.00	382.60		Cum	1	7.60	8.15	8.30	8.23	0.05	3.13		
382.60	391.90		Cum	1	9.30	9.90	9.50	9.70	0.05	4.51		
391.90	393.30		Cum	1	1.40	7.90	8.00	7.95	0.05	0.56		
393.30	400.00		Cum	1	6.70	9.20	9.20	9.20	0.05	3.08		
400.00	405.00		Cum	1	5.00	7.90	7.40	7.65	0.05	1.91		
405.00	420.00		Cum	1	15.00	7.40	7.60	7.50	0.05	5.63		
420.00	435.00		Cum	1	15.00	7.60	7.40	7.50	0.05	5.63		
435.00	444.20		Cum	1	9.20	9.00	9.10	9.05	0.05	4.16		
444.20	446.30		Cum	1	2.10	7.30	7.45	7.38	0.05	0.77		
446.30	456.40		Cum	1	10.10	9.15	9.10	9.13	0.05	4.61		
456.40	465.00		Cum	1	8.60	7.45	7.35	7.40	0.05	3.18		
465.00	480.00		Cum	1	15.00	7.35	7.25	7.30	0.05	5.48		
480.00	495.00		Cum	1	15.00	7.25	7.65	7.45	0.05	5.59		
495.00	510.00		Cum	1	15.00	7.65	8.50	8.08	0.05	6.06		
510.00	525.20		Cum	1	15.20	10.00	10.60	10.30	0.05	7.83		
525.20	540.00		Cum	1	14.80	8.50	7.60	8.05	0.05	5.96		
540.00	555.00		Cum	1	15.00	7.60	7.50	7.55	0.05	5.66		
555.00	560.90		Cum	1	5.90	7.50	7.50	7.50	0.05	2.21		
560.90	562.70		Cum	1	1.80	4.80	4.80	4.80	0.05	0.43		
		Total Executed Quantity								**1735.94**		
		Tender Quantity								**1433.06**		
		Quantity Upto 125%								**1735.94**	**5923.63**	**10283077.00**
Item no. 17		Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specification and directions of the Engineer in charge.										
		Venkateshwara Layout										
		3rd Cross Road										
		South to North										
0.00	15.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
15.00	30.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
30.00	45.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
45.00	60.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
60.00	75.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
75.00	90.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
90.00	105.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
105.00	120.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
120.00	135.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
135.00	150.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	1	15.00	5.50	5.50	5.50		82.50		
	165.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
165.00	180.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
180.00	195.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
195.00	210.00		Sqm	1	10.00	5.50	5.50	5.50		55.00		
210.00	220.00											
		4th Cross Road										
		North to South										
			Sqm	1	15.00	5.50	5.50	5.50		82.50		
0.00	15.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
15.00	30.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
30.00	45.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
45.00	60.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
60.00	75.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
75.00	90.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
90.00	105.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
105.00	120.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
120.00	135.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
135.00	150.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
150.00	165.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
165.00	180.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
180.00	195.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
195.00	210.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
210.00	220.00		Sqm	1	10.00	5.50	5.50	5.50		55.00		
		5th Cross Road										
		North to South										
0.00	15.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
15.00	30.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
30.00	45.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
45.00	60.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
60.00	75.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
75.00	90.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
90.00	105.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
105.00	120.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
120.00	135.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
135.00	150.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
150.00	165.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
165.00	180.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
180.00	195.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
195.00	210.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
210.00	220.00		Sqm	1	10.00	5.50	5.50	5.50		55.00		
									Total Executed Quantity	**3630.00**	**5.35**	**19421.00**
									Tender Quantity	**21788.70**		
Item no. 18		Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specification and directions of the Engineer in charge.										
		Defence Colony										
		6th Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.95	5.20	5.08		76.13		
15.00	30.00		Sqm	1	15.00	5.20	5.20	5.20		78.00		
30.00	40.10		Sqm	1	10.10	5.20	5.50	5.35		54.04		
40.10	43.70		Sqm	1	3.60	4.32	4.75	4.54		16.33		
43.70	45.00		Sqm	1	1.30	5.28	5.20	5.24		6.81		
45.00	60.00		Sqm	1	15.00	5.20	4.90	5.05		75.75		
60.00	75.00		Sqm	1	15.00	4.90	5.50	5.20		78.00		
75.00	90.00		Sqm	1	15.00	5.50	5.10	5.30		79.50		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
90.00	105.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
105.00	110.80		Sqm	1	5.80	5.00	5.10	5.05		29.29		
		8th Main Road										
		(From East to West)										
			Sqm	1	15.00	4.40	4.45	4.43		66.38		
0.00	15.00		Sqm	1	15.00	4.45	4.90	4.68		70.13		
15.00	30.00		Sqm	1	15.00	4.95	5.10	5.03		75.38		
30.00	45.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
45.00	60.00		Sqm	1	15.00	4.95	5.10	5.03		75.38		
60.00	75.00		Sqm	1	15.00	5.10	5.05	5.08		76.13		
75.00	90.00		Sqm	1	15.00	4.95	5.20	5.08		76.13		
90.00	105.00		Sqm	1	15.00	5.20	5.05	5.13		76.88		
105.00	120.00		Sqm	1	11.00	4.95	4.95	4.95		54.45		
120.00	131.00											
		Cross Road 2										
		(From East to West)										
			Sqm	1	15.00	4.25	4.10	4.18		62.63		
0.00	15.00		Sqm	1	15.00	4.10	4.00	4.05		60.75		
15.00	30.00		Sqm	1	1.50	4.00	4.00	4.00		6.00		
30.00	31.50											
		Cross Road 1										
		(From East to West)										
			Sqm	1	15.00	4.40	4.48	4.44		66.60		
0.00	15.00		Sqm	1	14.50	4.48	4.65	4.57		66.19		
15.00	29.50											
		Nithish Central Park Road										
		(From North to South)										
			Sqm	1	15.00	5.80	5.40	5.60		84.00		
0.00	15.00		Sqm	1	6.40	5.40	5.70	5.55		35.52		
15.00	21.40		Sqm	1	8.20	5.05	4.80	4.93		40.39		
21.40	29.60		Sqm	1	0.40	5.52	5.50	5.51		2.20		
29.60	30.00		Sqm	1	15.00	5.50	5.15	5.33		79.88		
30.00	45.00		Sqm	1	15.00	5.15	5.15	5.15		77.25		
45.00	60.00		Sqm	1	15.00	5.15	5.04	5.10		76.43		
60.00	75.00		Sqm	1	5.00	5.04	6.00	5.52		27.60		
75.00	80.00		Sqm	1	3.70	6.00	5.95	5.98		22.11		
80.00	83.70		Sqm	1	3.90	5.30	5.30	5.30		20.67		
83.70	87.60		Sqm	1	5.60	6.30	6.20	6.25		35.00		
87.60	93.20		Sqm	1	3.00	5.40	5.00	5.20		15.60		
93.20	96.20											
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.80	5.30	5.05		75.75		
15.00	22.80		Sqm	1	7.80	5.30	5.40	5.35		41.73		
22.80	32.00		Sqm	1	9.20	4.95	4.80	4.88		44.85		
32.00	45.00		Sqm	1	13.00	4.75	5.03	4.89		63.57		
45.00	60.00		Sqm	1	15.00	5.03	4.95	4.99		74.85		
60.00	75.00		Sqm	1	15.00	4.95	5.30	5.13		76.88		
75.00	90.00		Sqm	1	15.00	4.95	5.45	5.20		78.00		
90.00	95.10		Sqm	1	5.10	5.45	5.65	5.55		28.31		
		Palanahalli										
		For Cut Portions										
		(From West to East)										
0.00	8.40		Sqm	1	8.40	1.30	1.30	1.30		10.92		
8.40	24.00		Sqm	1	15.60	2.50	3.10	2.80		43.68		
24.00	27.60	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
27.60	42.60		Sqm	1	15.00	3.35	2.52	2.94		44.03		
42.60	45.00		Sqm	1	2.40	2.52	2.50	2.51		6.02		
45.00	60.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
60.00	75.00		Sqm	1	15.00	2.50	1.95	2.23		33.38		
75.00	90.00		Sqm	1	15.00	1.95	2.50	2.23		33.38		
90.00	105.00		Sqm	1	15.00	2.50	1.85	2.18		32.63		
105.00	115.80		Sqm	1	10.80	1.85	3.00	2.43		26.19		
115.80	119.00		Sqm	1	3.20	3.00	4.30	3.65		11.68		
119.00	125.50		Sqm	1	6.50	1.30	0.85	1.08		6.99		
125.50	132.60	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
132.60	135.60		Sqm	1	3.00	1.50	1.65	1.58		4.73		
135.60	150.60		Sqm	1	15.00	1.65	1.20	1.43		21.38		
150.60	152.60		Sqm	1	2.00	4.10	4.10	4.10		8.20		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
152.60	159.50		Sqm	1	6.90	2.10	2.10	2.10		14.49		
159.50	174.50		Sqm	1	15.00	2.10	1.00	1.55		23.25		
174.50	183.90		Sqm	1	9.40	1.00	1.00	1.00		9.40		
183.90	198.90		Sqm	1	15.00	1.00	1.00	1.00		15.00		
198.90	213.90		Sqm	1	15.00	1.00	1.00	1.00		15.00		
213.90	214.30		Sqm	1	0.40	1.00	1.70	1.35		0.54		
214.30	229.30		Sqm	1	15.00	1.83	1.50	1.67		24.98		
229.30	243.20		Sqm	1	13.90	1.83	1.50	1.67		23.14		
243.20	246.30		Sqm	1	3.10	1.95	1.90	1.93		5.97		
		For Road Cutting										
0.00	4.50		Sqm	1	4.50	0.40	0.25	0.33		1.46		
0.00	5.00		Sqm	1	5.00	0.40	0.20	0.30		1.50		
0.00	2.80		Sqm	1	2.80	3.20	3.25	3.23		9.03		
0.00	4.70		Sqm	1	4.70	0.70	0.45	0.58		2.70		
0.00	2.60		Sqm	1	2.60	1.20	1.25	1.23		3.19		
		Deducation										
		Chamber	Sqm	-1	1.90			1.40		-2.66		
		Tree Pot	Sqm	-9	0.20			0.10		-0.18		
		Electric Pole	Sqm	-1	0.90			0.50		-0.45		
		Man Hole (1m Dia)	Sqm	-1			Area =			-0.79		
		7th Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.35	4.06	4.21		63.08		
15.00	17.40		Sqm	1	2.40	4.06	4.25	4.16		9.97		
17.40	26.70		Sqm	1	9.30	5.05	5.20	5.13		47.66		
26.70	41.70		Sqm	1	15.00	4.10	4.10	4.10		61.50		
41.70	45.10		Sqm	1	3.40	4.10	3.75	3.93		13.35		
45.10	60.00		Sqm	1	14.90	5.10	5.10	5.10		75.99		
60.00	75.00		Sqm	1	15.00	5.10	5.17	5.14		77.03		
75.00	83.70		Sqm	1	8.70	5.17	5.00	5.09		44.24		
83.70	98.70		Sqm	1	15.00	4.35	4.00	4.18		62.63		
98.70	100.40		Sqm	1	1.70	4.00	4.00	4.00		6.80		
100.40	104.10		Sqm	1	3.70	5.10	5.10	5.10		18.87		
		2nd Cross										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.40	6.00	5.20		78.00		
15.00	30.00		Sqm	1	15.00	6.00	5.75	5.88		88.13		
30.00	45.00		Sqm	1	15.00	5.75	5.80	5.78		86.63		
45.00	60.00		Sqm	1	15.00	5.80	6.05	5.93		88.88		
60.00	69.30		Sqm	1	9.30	6.05	5.68	5.87		54.54		
69.30	77.50		Sqm	1	8.20	4.35	4.60	4.48		36.70		
77.50	90.00		Sqm	1	12.50	6.10	5.40	5.75		71.88		
90.00	96.40		Sqm	1	6.40	5.40	5.90	5.65		36.16		
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	6.50	5.40	5.95		89.25		
15.00	25.40		Sqm	1	10.40	5.40	6.00	5.70		59.28		
		8th Main Road										
		North to South										
0.00	15.00		Sqm	1	15.00	6.20	5.75	5.98		89.63		
15.00	19.40		Sqm	1	4.40	5.75	5.75	5.75		25.30		
19.40	30.00		Sqm	1	10.60	4.85	5.85	5.35		56.71		
30.00	37.20		Sqm	1	7.20	5.85	6.40	6.13		44.10		
37.20	45.00		Sqm	1	7.80	4.90	5.50	5.20		40.56		
45.00	46.40		Sqm	1	1.40	5.50	5.50	5.50		7.70		
46.40	64.00		Sqm	1	17.60	4.20	5.10	4.65		81.84		
64.00	75.00		Sqm	1	11.00	5.95	6.25	6.10		67.10		
75.00	90.00		Sqm	1	15.00	6.25	6.25	6.25		93.75		
90.00	105.00		Sqm	1	15.00	6.25	5.90	6.08		91.13		
105.00	108.00		Sqm	1	3.00	5.90	5.90	5.90		17.70		

(Ward No 04)

Drainage From	Drainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Vinayak Nagar										
		6th B Main Road										
		North to South										
	9.10		Sqm	1	9.10	5.10	4.95	5.03		45.73		
9.10	15.00		Sqm	1	5.90	4.40	3.95	4.18		24.63		
15.00	19.70		Sqm	1	4.70	3.95	4.25	4.10		19.27		
19.70	30.00		Sqm	1	10.30	4.25	4.30	4.28		44.03		
30.00	45.00		Sqm	1	15.00	4.30	3.45	3.88		58.13		
45.00	60.00		Sqm	1	15.00	3.45	4.35	3.90		58.50		
60.00	75.00		Sqm	1	15.00	4.35	4.65	4.50		67.50		
75.00	79.80		Sqm	1	4.80	4.65	5.15	4.90		23.52		
79.80	88.10		Sqm	1	8.30	4.25	3.80	4.03		33.41		
88.10	90.00		Sqm	1	1.90	4.50	3.50	4.00		7.60		
90.00	91.90		Sqm	1	1.90	3.50	3.55	3.53		6.70		
91.90	97.00		Sqm	1	5.10	5.05	5.10	5.08		25.88		
97.00	99.80		Sqm	1	2.80	4.25	4.25	4.25		11.90		
99.80	105.00		Sqm	1	5.20	3.55	4.25	3.90		20.28		
105.00	108.00		Sqm	1	3.00	4.25	4.15	4.20		12.60		
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
	15.00		Sqm	1	15.00	4.80	5.80	5.30		79.50		
15.00	30.00		Sqm	1	15.00	5.80	5.30	5.55		83.25		
30.00	45.00		Sqm	1	15.00	5.30	6.15	5.73		85.88		
45.00	60.00		Sqm	1	15.00	6.15	6.48	6.32		94.73		
60.00	65.80		Sqm	1	5.80	6.48	6.49	6.49		37.61		
		11th Cross Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.20	4.10	4.15		62.25		
15.00	30.00		Sqm	1	15.00	4.10	3.80	3.95		59.25		
30.00	45.00		Sqm	1	15.00	3.80	3.65	3.73		55.88		
45.00	60.00		Sqm	1	15.00	3.65	4.00	3.83		57.38		
60.00	70.00		Sqm	1	10.00	4.00	4.10	4.05		40.50		
70.00	75.00		Sqm	1	5.00	4.10	4.00	4.05		20.25		
75.00	90.00		Sqm	1	15.00	4.00	4.64	4.32		64.80		
90.00	105.00		Sqm	1	15.00	4.64	4.90	4.77		71.55		
105.00	120.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
120.00	135.00		Sqm	1	15.00	4.90	4.90	4.90		73.50		
135.00	150.00		Sqm	1	15.00	4.90	5.00	4.95		74.25		
150.00	165.00		Sqm	1	15.00	5.00	4.90	4.95		74.25		
165.00	168.00		Sqm	1	3.00	4.90	4.75	4.83		14.48		
		10th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.35	5.30	5.33		79.88		
15.00	30.00		Sqm	1	15.00	5.30	5.10	5.20		78.00		
30.00	45.00		Sqm	1	15.00	5.10	4.40	4.75		71.25		
45.00	60.00		Sqm	1	15.00	4.40	4.50	4.45		66.75		
60.00	75.00		Sqm	1	15.00	4.50	4.60	4.55		68.25		
75.00	90.00		Sqm	1	15.00	4.60	4.48	4.54		68.10		
90.00	105.00		Sqm	1	15.00	4.48	4.84	4.66		69.90		
105.00	108.60		Sqm	1	3.60	4.84	4.85	4.85		17.44		
108.60	117.40		Sqm	1	8.80	5.35	4.80	5.08		44.66		
117.40	120.00		Sqm	1	2.60	4.50	4.60	4.55		11.83		
120.00	135.00		Sqm	1	15.00	4.60	4.49	4.55		68.18		
135.00	150.00		Sqm	1	15.00	4.49	4.67	4.58		68.70		
150.00	165.00		Sqm	1	15.00	4.67	4.55	4.61		69.15		
165.00	167.60		Sqm	1	2.60	4.55	4.90	4.73		12.29		
		10th A Cross										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.00	5.75	5.88		88.13		
15.00	30.00		Sqm	1	15.00	5.75	5.40	5.58		83.63		
30.00	45.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
45.00	60.00		Sqm	1	15.00	5.40	5.10	5.25		78.75		

Part (Ward No 04)

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	75.00		Sqm	1	15.00	5.10	5.35	5.23		78.38		
75.00	90.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
90.00	105.00		Sqm	1	15.00	5.55	6.00	5.78		86.63		
105.00	120.00		Sqm	1	15.00	6.00	6.10	6.05		90.75		
120.00	134.70		Sqm	1	14.70	6.10	6.20	6.15		90.40		
		10th A Cross										
		(From West to East)										
0.00	2.80		Sqm	1	2.80	4.80	4.50	4.65		13.02		
		2nd Main Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	8.80	8.70	8.75		131.25		
15.00	30.00		Sqm	1	15.00	8.70	9.13	8.92		133.73		
30.00	45.00		Sqm	1	15.00	9.13	8.50	8.82		132.23		
45.00	60.00		Sqm	1	15.00	8.50	8.40	8.45		126.75		
60.00	75.00		Sqm	1	15.00	8.40	8.55	8.48		127.13		
75.00	90.00		Sqm	1	15.00	8.55	8.10	8.33		124.88		
90.00	105.00		Sqm	1	15.00	8.10	7.60	7.85		117.75		
105.00	114.30		Sqm	1	9.30	7.60	8.00	7.80		72.54		
114.30	129.30		Sqm	1	15.00	8.00	7.45	7.73		115.88		
129.30	144.30		Sqm	1	15.00	7.45	6.85	7.15		107.25		
144.30	159.30		Sqm	1	15.00	6.85	6.80	6.83		102.38		
159.30	174.30		Sqm	1	15.00	6.80	6.90	6.85		102.75		
174.30	189.30		Sqm	1	15.00	6.90	7.65	7.28		109.13		
189.30	192.60		Sqm	1	3.30	7.65	7.40	7.53		24.83		
		Cut Portion										
0.00	2.60		Sqm	1	2.60	2.10	2.10	2.10		5.46		
		2nd Main Road To M S Nagar Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	5.10	4.36	4.73		70.95		
15.00	30.00		Sqm	1	15.00	4.36	4.40	4.38		65.70		
30.00	33.70		Sqm	1	3.70	4.40	4.60	4.50		16.65		
		(From South to North)										
0.00	15.00		Sqm	1	15.00	5.45	5.20	5.33		79.88		
15.00	30.00		Sqm	1	15.00	5.20	5.40	5.30		79.50		
30.00	45.00		Sqm	1	15.00	5.40	5.70	5.55		83.25		
45.00	60.00		Sqm	1	15.00	5.70	5.25	5.48		82.13		
60.00	75.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
75.00	90.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
90.00	105.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
105.00	120.00		Sqm	1	15.00	5.40	5.58	5.49		82.35		
120.00	135.00		Sqm	1	15.00	5.58	5.40	5.49		82.35		
135.00	150.00		Sqm	1	15.00	5.40	5.35	5.38		80.63		
150.00	165.00		Sqm	1	15.00	5.35	5.20	5.28		79.13		
165.00	180.00		Sqm	1	15.00	5.20	5.20	5.20		78.00		
180.00	195.00		Sqm	1	15.00	5.20	5.54	5.37		80.55		
195.00	197.80		Sqm	1	2.80	5.54	6.40	5.97		16.72		
		(From East to West)										
0.00	15.00		Sqm	1	15.00	3.90	3.65	3.78		56.63		
15.00	30.00		Sqm	1	15.00	3.65	3.68	3.67		54.98		
30.00	45.00		Sqm	1	15.00	3.68	3.98	3.83		57.45		
45.00	49.80		Sqm	1	4.80	3.98	4.20	4.09		19.63		
49.80	51.90		Sqm	1	2.10	4.20	7.50	5.85		12.29		
		3A Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	3.85	3.63	3.74		56.10		
15.00	30.00		Sqm	1	15.00	3.63	3.63	3.63		54.45		
30.00	41.40		Sqm	1	11.40	3.63	4.32	3.98		45.32		
41.40	44.50		Sqm	1	3.10	4.32	7.35	5.84		18.09		

Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		(From North to South)										
			Sqm	1	15.00	4.10	3.60	3.85		57.75		
			Sqm	1	3.60	3.60	3.65	3.63		13.05		
0.00	15.00											
15.00	18.60											
		5th Cross Road										
		(From North to South)										
			Sqm	1	3.40	8.20	6.80	7.50		25.50		
0.00	3.40		Sqm	1	11.60	6.80	6.70	6.75		78.30		
3.40	15.00		Sqm	1	15.00	6.70	6.10	6.40		96.00		
15.00	30.00		Sqm	1	15.00	6.10	6.20	6.15		92.25		
30.00	45.00		Sqm	1	11.60	6.20	6.15	6.18		71.63		
45.00	56.60											
		Cut Portion	Sqm	1	12.10	2.40	2.40	2.40		29.04		
0.00	12.10											
		Hegde Nagara										
		Win Field Garden										
		5th Cross Road (W1941)										
		(From South to North)										
			Sqm	1	2.70	10.80	7.45	9.13		24.64		
0.00	2.70		Sqm	1	12.30	7.45	6.70	7.08		87.02		
2.70	15.00		Sqm	1	15.00	6.70	6.65	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.65	7.00	6.83		102.38		
30.00	45.00		Sqm	1	15.00	7.00	7.50	7.25		108.75		
45.00	60.00		Sqm	1	15.00	7.50	7.00	7.25		108.75		
60.00	75.00		Sqm	1	15.00	7.00	7.00	7.00		105.00		
75.00	90.00		Sqm	1	15.00	7.00	6.85	6.93		103.88		
90.00	105.00		Sqm	1	15.00	6.85	6.25	6.55		98.25		
105.00	120.00		Sqm	1	15.00	6.25	7.05	6.65		99.75		
120.00	135.00		Sqm	1	15.00	7.05	7.05	7.05		105.75		
135.00	150.00		Sqm	1	15.00	7.05	7.05	7.05		105.75		
150.00	165.00		Sqm	1	15.00	7.05	7.05	7.05		105.75		
165.00	180.00		Sqm	1	5.20	7.05	7.40	7.23		37.57		
180.00	185.20		Sqm	1	2.80	7.00	12.00	9.50		26.60		
185.20	188.00		Sqm	1	2.50	8.00	7.90	7.95		19.88		
188.00	190.50											
		6th Cross Road (W1935)										
		(From South to North)										
0.00	2.00		Sqm	1	2.00	7.50	5.90	6.70		13.40		
2.00	15.00		Sqm	1	13.00	5.90	5.95	5.93		77.03		
15.00	30.00		Sqm	1	15.00	5.95	6.00	5.98		89.63		
30.00	45.00		Sqm	1	15.00	6.00	5.50	5.75		86.25		
45.00	60.00		Sqm	1	15.00	5.50	5.35	5.43		81.38		
60.00	75.00		Sqm	1	15.00	5.35	5.55	5.45		81.75		
75.00	90.00		Sqm	1	15.00	5.55	5.55	5.55		83.25		
90.00	105.00		Sqm	1	15.00	5.55	5.60	5.58		83.63		
105.00	120.00		Sqm	1	15.00	5.60	5.60	5.60		84.00		
120.00	135.00		Sqm	1	15.00	5.60	5.75	5.68		85.13		
135.00	150.00		Sqm	1	15.00	5.75	4.85	5.30		79.50		
150.00	165.00		Sqm	1	15.00	4.85	4.80	4.83		72.38		
165.00	180.00		Sqm	1	15.00	4.80	6.10	5.45		81.75		
180.00	181.50		Sqm	1	1.50	6.10	5.40	5.75		8.63		
		9th Cross Road										
		(From South to North)										
0.00	2.80		Sqm	1	2.80	6.90	4.90	5.90		16.52		
2.80	15.90		Sqm	1	13.10	4.90	4.40	4.65		60.92		
15.90	30.00		Sqm	1	14.10	4.00	5.45	4.73		66.62		
30.00	45.00		Sqm	1	15.00	5.45	5.60	5.53		82.88		
45.00	60.00		Sqm	1	15.00	5.50	5.70	5.60		84.00		
60.00	75.00		Sqm	1	15.00	5.70	5.00	5.35		80.25		
75.00	79.90		Sqm	1	4.90	5.00	5.10	5.05		24.75		
79.90	89.60		Sqm	1	9.70	4.60	4.60	4.60		44.62		
89.60	90.00		Sqm	1	0.40	4.60	5.95	5.28		2.11		
90.00	105.00		Sqm	1	15.00	5.95	5.75	5.85		87.75		
105.00	116.70		Sqm	1	11.70	5.75	5.60	5.68		66.40		
116.70	126.90		Sqm	1	10.20	4.60	4.85	4.73		48.20		
126.90	137.90		Sqm	1	11.00	5.70	5.80	5.75		63.25		

(Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		MSR Mansion Road										
		(North to South)										
	5.80		Sqm	1	5.80	5.75	7.15	6.45		37.41		
5.80	9.70		Sqm	1	3.90	10.70	8.40	9.55		37.25		
9.70	15.00		Sqm	1	5.30	8.40	8.25	8.33		44.12		
15.00	30.00		Sqm	1	15.00	8.25	7.40	7.83		117.38		
30.00	45.00		Sqm	1	15.00	7.40	6.85	7.13		106.88		
45.00	50.00		Sqm	1	5.00	6.85	7.10	6.98		34.88		
		Nisarga Layout										
		7th Cross, Zayan Travels Car Service Centre Road, North To South										
	15.00		Sqm	1	15.00	5.00	4.85	4.93		73.88		
15.00	30.00		Sqm	1	15.00	4.85	4.60	4.73		70.88		
30.00	45.00		Sqm	1	15.00	4.60	5.15	4.88		73.13		
45.00	60.00		Sqm	1	15.00	5.15	5.00	5.08		76.13		
60.00	75.00		Sqm	1	15.00	5.00	5.10	5.05		75.75		
75.00	90.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
90.00	101.50		Sqm	1	11.50	5.00	4.70	4.85		55.78		
		West To East										
0.00	15.00		Sqm	1	15.00	4.90	4.80	4.85		72.75		
15.00	15.70		Sqm	1	0.70	4.80	4.80	4.80		3.36		
15.70	30.00		Sqm	1	14.30	5.30	5.60	5.45		77.94		
30.00	45.00		Sqm	1	15.00	5.60	5.15	5.38		80.63		
45.00	46.70		Sqm	1	1.70	5.15	5.15	5.15		8.76		
46.70	51.60		Sqm	1	4.90	4.15	3.95	4.05		19.85		
51.60	56.20		Sqm	1	4.60	5.30	5.25	5.28		24.27		
56.20	64.60		Sqm	1	8.40	4.20	4.30	4.25		35.70		
64.60	75.00		Sqm	1	10.40	5.30	5.35	5.33		55.38		
75.00	76.60		Sqm	1	1.60	5.35	5.36	5.36		8.57		
		5th Cross Road, North To South										
0.00	11.10		Sqm	1	11.10	5.70	5.90	5.80		64.38		
11.10	20.00		Sqm	1	8.90	5.10	5.35	5.23		46.50		
20.00	23.80		Sqm	1	3.80	7.00	6.95	6.98		26.51		
23.80	30.00		Sqm	1	6.20	6.05	5.95	6.00		37.20		
30.00	45.00		Sqm	1	15.00	5.95	5.50	5.73		85.88		
45.00	60.00		Sqm	1	15.00	5.50	6.00	5.75		86.25		
60.00	66.90		Sqm	1	6.90	6.00	6.30	6.15		42.44		
66.90	75.00		Sqm	1	8.10	4.90	5.70	5.30		42.93		
75.00	75.60		Sqm	1	0.60	5.70	5.65	5.68		3.40		
75.60	76.80		Sqm	1	1.20	2.95	3.00	2.98		3.57		
		Mithun White Pearl Apartment Road										
		(East To West)										
0.00	15.00		Sqm	1	15.00	6.60	6.75	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.75	6.50	6.63		99.38		
30.00	45.00		Sqm	1	15.00	6.50	6.45	6.48		97.13		
45.00	60.00		Sqm	1	15.00	6.45	6.45	6.45		96.75		
60.00	75.00		Sqm	1	15.00	6.45	6.25	6.35		95.25		
75.00	90.00		Sqm	1	15.00	6.25	6.20	6.23		93.38		
90.00	96.40		Sqm	1	6.40	6.20	5.85	6.03		38.56		
		Venkateshwara Layout										
		3rd Cross Road										
		South to North										
0.00	15.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
15.00	30.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
30.00	45.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
45.00	60.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
60.00	75.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
75.00	90.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
90.00	105.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	120.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
15.00	135.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
30.00	150.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
45.00	165.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
60.00	180.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
75.00	195.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
90.00	210.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
105.00	220.00		Sqm	1	10.00	5.50	5.50	5.50		55.00		
		4th Cross Road										
		North to South										
0.00	15.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
15.00	30.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
30.00	45.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
45.00	60.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
60.00	75.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
75.00	90.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
90.00	105.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
105.00	120.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
120.00	135.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
135.00	150.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
150.00	165.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
165.00	180.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
180.00	195.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
195.00	210.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
210.00	220.00		Sqm	1	10.00	5.50	5.50	5.50		55.00		
		5th Cross Road										
		North to South										
0.00	15.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
15.00	30.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
30.00	45.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
45.00	60.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
60.00	75.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
75.00	90.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
90.00	105.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
105.00	120.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
120.00	135.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
135.00	150.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
150.00	165.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
165.00	180.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
180.00	195.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
195.00	210.00		Sqm	1	15.00	5.50	5.50	5.50		82.50		
210.00	220.00		Sqm	1	10.00	5.50	5.50	5.50		55.00		
		Chembar	Sqm	-1	0.64					-0.64		
					Area of Circle=(3.14X0.9²)/4=0.64							
			Sqm	-4	0.70	1.00	1.00	1.00		-2.80		
			Sqm	-3	0.90	0.80	0.80	0.80		-2.16		
		Katgenahalli										
		Muneshwara Provision Store										
		Kalidas Layout										
		3rd Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.70	6.65	6.68		100.13		
15.00	30.00		Sqm	1	15.00	6.65	6.65	6.65		99.75		
30.00	45.00		Sqm	1	15.00	6.65	6.00	6.33		94.88		
45.00	60.00		Sqm	1	15.00	6.00	5.80	5.90		88.50		
60.00	66.40		Sqm	1	6.40	5.80	5.60	5.70		36.48		
66.40	75.00		Sqm	1	8.60	5.60	5.60	5.60		48.16		
75.00	90.00		Sqm	1	15.00	5.60	5.50	5.55		83.25		
90.00	105.00		Sqm	1	15.00	5.50	5.80	5.65		84.75		
105.00	113.00		Sqm	1	8.00	5.80	4.30	5.05		40.40		

Ward (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	1	2.50	5.25	5.15	5.20		13.00		
			Sqm	1	12.50	5.85	6.60	6.23		77.81		
			Sqm	1	15.00	6.60	6.15	6.38		95.63		
			Sqm	1	8.00	6.15	6.00	6.08		48.60		
		Kaustaba House Road #33 (W-E)										
			Sqm	1	6.30	7.45	7.55	7.50		47.25		
			Sqm	1	8.70	6.80	6.48	6.64		57.77		
			Sqm	1	15.00	6.48	6.00	6.24		93.60		
			Sqm	1	15.00	6.00	5.70	5.85		87.75		
			Sqm	1	12.90	5.70	6.05	5.88		75.79		
			Sqm	1	2.10	6.95	7.70	7.33		15.38		
			Sqm	1	3.60	7.70	7.65	7.68		27.63		
		Sukruthi House Road #26 (S-N)										
			Sqm	1	8.30	5.60	5.90	5.75		47.73		
			Sqm	1	6.70	5.35	4.90	5.13		34.34		
			Sqm	1	15.00	4.90	5.80	5.35		80.25		
			Sqm	1	15.00	5.80	5.35	5.58		83.63		
			Sqm	1	15.00	5.35	5.30	5.33		79.88		
			Sqm	1	0.50	5.30	5.30	5.30		2.65		
			Sqm	1	14.50	5.85	6.20	6.03		87.36		
			Sqm	1	15.00	6.20	5.40	5.80		87.00		
			Sqm	1	8.70	5.40	5.20	5.30		46.11		
			Sqm	1	6.30	4.40	4.95	4.68		29.45		
			Sqm	1	3.20	4.95	4.95	4.95		15.84		
			Sqm	1	4.00	5.50	5.20	5.35		21.40		
			Sqm	1	7.80	4.40	4.60	4.50		35.10		
			Sqm	1	5.80	4.60	4.50	4.55		26.39		
			Sqm	1	9.90	4.00	4.45	4.23		41.83		
			Sqm	1	8.20	5.60	5.95	5.78		47.36		
			Sqm	1	6.10	6.65	5.75	6.20		37.82		
			Sqm	1	14.30	5.75	5.85	5.80		82.94		
		SP Singh House Road (E-W)										
			Sqm	1	15.00	6.35	5.65	6.00		90.00		
			Sqm	1	4.10	5.65	6.00	5.83		23.88		
			Sqm	1	10.90	5.20	5.65	5.43		59.13		
			Sqm	1	4.20	5.65	6.10	5.88		24.68		
		Form mrd Main To Muneshwara provsion										
			Sqm	1	1.70	5.05	5.05	5.05		8.59		
			Sqm	1	13.30	7.30	7.40	7.35		97.76		
			Sqm	1	15.00	7.40	7.10	7.25		108.75		
			Sqm	1	15.00	7.10	6.75	6.93		103.88		
			Sqm	1	15.00	6.75	7.55	7.15		107.25		
			Sqm	1	15.00	7.55	6.45	7.00		105.00		
			Sqm	1	2.80	6.45	5.70	6.08		17.01		
			Sqm	1	12.20	6.80	7.15	6.98		85.10		
			Sqm	1	5.90	7.15	6.95	7.05		41.60		
			Sqm	1	9.10	6.25	6.30	6.28		57.10		
			Sqm	1	12.90	6.30	5.90	6.10		78.69		
			Sqm	1	2.10	6.75	6.80	6.78		14.23		
			Sqm	1	4.80	6.80	5.80	6.30		30.24		
		Deduction										
		Chamber	Sqm	-1	0.70	1.00	1.00	1.00		-0.70		
		Manhole	Sqm	-1	0.64					-0.64		
					Area of Circle = (3.142*0.9^2)/4= 0.64							

Drainage From	Drainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Manhole	Sqm	-1	1.13					-1.13		
					Area of Circle = (3.142*1.2^2)/4= 1.13							
		Green Garden Main Road (West to East)										
0.00	15.00		Sqm	1	15.00	6.00	6.18	6.09		91.35		
15.00	30.00		Sqm	1	15.00	6.18	6.18	6.18		92.70		
30.00	42.70		Sqm	1	12.70	6.18	5.75	5.97		75.76		
42.70	45.00		Sqm	1	2.30	5.00	4.90	4.95		11.39		
45.00	53.70		Sqm	1	8.70	4.90	4.95	4.93		42.85		
53.70	60.00		Sqm	1	6.30	6.80	5.85	6.33		39.85		
60.00	75.00		Sqm	1	15.00	5.85	6.00	5.93		88.88		
75.00	90.00		Sqm	1	15.00	6.00	5.95	5.98		89.63		
90.00	105.00		Sqm	1	15.00	5.95	6.10	6.03		90.38		
105.00	120.00		Sqm	1	15.00	6.10	5.35	5.73		85.88		
120.00	126.90		Sqm	1	6.90	5.35	5.50	5.43		37.43		
126.90	130.00		Sqm	1	3.10	6.00	6.00	6.00		18.60		
130.00	145.00		Sqm	1	15.00	6.00	6.05	6.03		90.38		
145.00	154.30		Sqm	1	9.30	6.05	6.10	6.08		56.50		
154.30	160.00		Sqm	1	5.70	5.10	5.00	5.05		28.78		
160.00	171.40		Sqm	1	11.40	5.00	4.85	4.93		56.15		
		Cross Road-4 (South to North)										
0.00	1.60		Sqm	1	1.60	4.70	4.60	4.65		7.44		
1.60	15.00		Sqm	1	13.40	6.15	5.50	5.83		78.06		
15.00	23.50		Sqm	1	8.50	5.50	5.60	5.55		47.18		
23.50	30.00		Sqm	1	6.50	5.15	5.45	5.30		34.45		
30.00	33.70		Sqm	1	3.70	5.45	5.70	5.58		20.63		
		Sri Ganga House Road East to West										
0.00	3.80		Sqm	1	3.80	5.70	5.70	5.70		21.66		
3.80	13.20		Sqm	1	9.40	5.40	5.40	5.40		50.76		
13.20	15.00		Sqm	1	1.80	5.75	5.70	5.73		10.31		
15.00	27.40		Sqm	1	12.40	5.70	5.45	5.58		69.13		
27.40	30.00		Sqm	1	2.60	5.25	4.80	5.03		13.07		
30.00	45.00		Sqm	1	15.00	4.80	5.30	5.05		75.75		
45.00	60.00		Sqm	1	15.00	5.30	5.55	5.43		81.38		
60.00	69.30		Sqm	1	9.30	5.55	6.40	5.98		55.57		
		Cross Road-3 (North to South)										
0.00	1.70		Sqm	1	1.70	4.70	4.70	4.70		7.99		
1.70	15.00		Sqm	1	13.30	6.80	5.50	6.15		81.80		
15.00	30.00		Sqm	1	15.00	5.50	5.40	5.45		81.75		
30.00	45.00		Sqm	1	15.00	5.40	5.45	5.43		81.38		
45.00	46.10		Sqm	1	1.10	5.45	5.45	5.45		6.00		
46.10	48.90		Sqm	1	2.80	6.15	6.40	6.28		17.57		
		Cross Road 2 (South to North)										
0.00	11.80		Sqm	1	11.80	5.75	5.60	5.68		66.97		
11.80	15.00		Sqm	1	3.20	4.90	4.70	4.80		15.36		
15.00	21.10		Sqm	1	6.10	4.70	4.65	4.68		28.52		
21.10	30.00		Sqm	1	8.90	5.20	5.25	5.23		46.50		
30.00	45.00		Sqm	1	15.00	5.25	5.35	5.30		79.50		
45.00	60.00		Sqm	1	15.00	5.35	5.40	5.38		80.63		
60.00	75.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
75.00	90.00		Sqm	1	15.00	5.40	5.65	5.53		82.88		
90.00	100.30		Sqm	1	10.30	5.65	5.85	5.75		59.23		
100.30	102.40		Sqm	1	2.10	5.85	6.00	5.93		12.44		

(Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road 1										
		(North to South)										
0.00	2.90		Sqm	1	2.90	6.50	6.40	6.45		18.71		
2.90	15.00		Sqm	1	12.10	6.40	5.90	6.15		74.42		
15.00	30.00		Sqm	1	15.00	5.90	5.75	5.83		87.38		
30.00	45.00		Sqm	1	15.00	5.75	5.70	5.73		85.88		
45.00	60.00		Sqm	1	15.00	5.70	5.50	5.60		84.00		
60.00	75.00		Sqm	1	15.00	5.50	5.40	5.45		81.75		
75.00	90.00		Sqm	1	15.00	5.40	5.55	5.48		82.13		
90.00	102.30		Sqm	1	12.30	5.55	5.80	5.68		69.80		
		Pyramid apartment main road										
		(East to West)										
0.00	1.10		Sqm	1	1.10	8.16	8.15	8.16		8.97		
1.10	2.40		Sqm	1	1.30	8.15	6.80	7.48		9.72		
2.40	4.70		Sqm	1	2.30	6.80	6.60	6.70		15.41		
4.70	12.40		Sqm	1	7.70	7.65	7.85	7.75		59.68		
12.40	15.00		Sqm	1	2.60	7.85	7.70	7.78		20.22		
15.00	30.00		Sqm	1	15.00	7.70	8.35	8.03		120.38		
30.00	32.00		Sqm	1	2.00	8.35	8.35	8.35		16.70		
32.00	45.00		Sqm	1	13.00	8.35	8.50	8.43		109.53		
45.00	60.00		Sqm	1	15.00	8.50	8.65	8.58		128.63		
60.00	75.00		Sqm	1	15.00	8.65	8.70	8.68		130.13		
75.00	81.10		Sqm	1	6.10	8.70	8.75	8.73		53.22		
81.10	90.00		Sqm	1	8.90	8.75	8.20	8.48		75.43		
90.00	105.00		Sqm	1	15.00	8.20	8.45	8.33		124.88		
105.00	120.00		Sqm	1	15.00	8.45	8.38	8.42		126.23		
120.00	128.00		Sqm	1	8.00	8.38	8.40	8.39		67.12		
		Cross Road 3 Near Pyramid apartment										
		(North to South)										
0.00	2.90		Sqm	1	2.90	6.40	6.35	6.38		18.49		
2.90	15.00		Sqm	1	12.10	6.35	5.75	6.05		73.21		
15.00	30.00		Sqm	1	15.00	5.75	5.70	5.73		85.88		
30.00	44.00		Sqm	1	14.00	5.70	5.10	5.40		75.60		
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
0.00	3.60		Sqm	1	3.60	6.40	6.40	6.40		23.04		
3.60	15.00		Sqm	1	11.40	5.00	5.10	5.05		57.57		
15.00	30.00		Sqm	1	15.00	5.10	4.85	4.98		74.63		
30.00	32.80		Sqm	1	2.80	4.85	4.85	4.85		13.58		
32.80	42.30		Sqm	1	9.50	3.80	4.00	3.90		37.05		
42.30	45.10		Sqm	1	2.80	5.10	5.10	5.10		14.28		
45.10	48.30		Sqm	1	3.20	5.10	5.00	5.05		16.16		
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
0.00	4.50		Sqm	1	4.50	6.40	5.50	5.95		26.78		
4.50	15.00		Sqm	1	10.50	5.50	5.25	5.38		56.44		
15.00	30.00		Sqm	1	15.00	5.25	5.25	5.25		78.75		
30.00	45.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
45.00	51.70		Sqm	1	6.70	5.00	4.70	4.85		32.50		
51.70	52.20		Sqm	1	0.50	4.70	5.20	4.95		2.48		
52.20	60.00		Sqm	1	7.80	5.20	5.45	5.33		41.54		
60.00	75.00		Sqm	1	15.00	5.45	5.45	5.45		81.75		
75.00	90.00		Sqm	1	15.00	5.45	4.85	5.15		77.25		
90.00	105.00		Sqm	1	15.00	4.85	5.65	5.25		78.75		
105.00	120.00		Sqm	1	15.00	5.65	5.60	5.63		84.38		
120.00	127.20		Sqm	1	7.20	5.60	5.55	5.58		40.14		

Road (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road 1										
		(North to South)										
			Sqm	1	2.90	6.50	6.40	6.45		18.71		
	2.90		Sqm	1	12.10	6.40	5.90	6.15		74.42		
2.90	15.00		Sqm	1	15.00	5.90	5.75	5.83		87.38		
15.00	30.00		Sqm	1	15.00	5.75	5.70	5.73		85.88		
30.00	45.00		Sqm	1	15.00	5.70	5.50	5.60		84.00		
45.00	60.00		Sqm	1	15.00	5.50	5.40	5.45		81.75		
60.00	75.00		Sqm	1	15.00	5.40	5.55	5.48		82.13		
75.00	90.00		Sqm	1	12.30	5.55	5.80	5.68		69.80		
90.00	102.30											
		Pyramid apartment main road										
		(East to West)										
			Sqm	1	1.10	8.16	8.15	8.16		8.97		
0.00	1.10		Sqm	1	1.30	8.15	6.80	7.48		9.72		
1.10	2.40		Sqm	1	2.30	6.80	6.60	6.70		15.41		
2.40	4.70		Sqm	1	7.70	7.65	7.85	7.75		59.68		
4.70	12.40		Sqm	1	2.60	7.85	7.70	7.78		20.22		
12.40	15.00		Sqm	1	15.00	7.70	8.35	8.03		120.38		
15.00	30.00		Sqm	1	2.00	8.35	8.35	8.35		16.70		
30.00	32.00		Sqm	1	13.00	8.35	8.50	8.43		109.53		
32.00	45.00		Sqm	1	15.00	8.50	8.65	8.58		128.63		
45.00	60.00		Sqm	1	15.00	8.65	8.70	8.68		130.13		
60.00	75.00		Sqm	1	6.10	8.70	8.75	8.73		53.22		
75.00	81.10		Sqm	1	8.90	8.75	8.20	8.48		75.43		
81.10	90.00		Sqm	1	15.00	8.20	8.45	8.33		124.88		
90.00	105.00		Sqm	1	15.00	8.45	8.38	8.42		126.23		
105.00	120.00		Sqm	1	8.00	8.38	8.40	8.39		67.12		
120.00	128.00											
		Cross Road 3 Near Pyramid apartment										
		(North to South)										
			Sqm	1	2.90	6.40	6.35	6.38		18.49		
0.00	2.90		Sqm	1	12.10	6.35	5.75	6.05		73.21		
2.90	15.00		Sqm	1	15.00	5.75	5.70	5.73		85.88		
15.00	30.00		Sqm	1	14.00	5.70	5.10	5.40		75.60		
30.00	44.00											
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
0.00	3.60		Sqm	1	3.60	6.40	6.40	6.40		23.04		
3.60	15.00		Sqm	1	11.40	5.00	5.10	5.05		57.57		
15.00	30.00		Sqm	1	15.00	5.10	4.85	4.98		74.63		
30.00	32.80		Sqm	1	2.80	4.85	4.85	4.85		13.58		
32.80	42.30		Sqm	1	9.50	3.80	4.00	3.90		37.05		
42.30	45.10		Sqm	1	2.80	5.10	5.10	5.10		14.28		
45.10	48.30		Sqm	1	3.20	5.10	5.00	5.05		16.16		
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
0.00	4.50		Sqm	1	4.50	6.40	5.50	5.95		26.78		
4.50	15.00		Sqm	1	10.50	5.50	5.25	5.38		56.44		
15.00	30.00		Sqm	1	15.00	5.25	5.25	5.25		78.75		
30.00	45.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
45.00	51.70		Sqm	1	6.70	5.00	4.70	4.85		32.50		
51.70	52.20		Sqm	1	0.50	4.70	5.20	4.95		2.48		
52.20	60.00		Sqm	1	7.80	5.20	5.45	5.33		41.54		
60.00	75.00		Sqm	1	15.00	5.45	5.45	5.45		81.75		
75.00	90.00		Sqm	1	15.00	5.45	4.85	5.15		77.25		
90.00	105.00		Sqm	1	15.00	4.85	5.65	5.25		78.75		
105.00	120.00		Sqm	1	15.00	5.65	5.60	5.63		84.38		
120.00	127.20		Sqm	1	7.20	5.60	5.55	5.58		40.14		

(Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Car 24 Beside Road										
		From Agrahara Main Road to Lake										
		East to West										
			Sqm	1	15.00	4.80	4.60	4.70		70.50		
			Sqm	1	12.00	4.60	4.65	4.63		55.50		
			Sqm	1	3.00	5.40	5.70	5.55		16.65		
			Sqm	1	15.00	5.70	5.70	5.70		85.50		
			Sqm	1	15.00	5.70	6.30	6.00		90.00		
			Sqm	1	15.00	6.30	6.30	6.30		94.50		
			Sqm	1	15.00	6.30	6.50	6.40		96.00		
			Sqm	1	15.00	6.50	6.65	6.58		98.63		
			Sqm	1	15.00	6.65	6.40	6.53		97.88		
			Sqm	1	15.00	6.40	6.20	6.30		94.50		
			Sqm	1	15.00	6.20	6.10	6.15		92.25		
			Sqm	1	15.00	6.10	6.30	6.20		93.00		
			Sqm	1	15.00	6.30	6.10	6.20		93.00		
			Sqm	1	15.00	6.10	6.25	6.18		92.63		
			Sqm	1	15.00	6.25	6.50	6.38		95.63		
			Sqm	1	15.00	6.50	6.40	6.45		96.75		
			Sqm	1	15.00	6.40	6.50	6.45		96.75		
			Sqm	1	15.00	6.50	6.65	6.58		98.63		
			Sqm	1	15.00	6.65	6.70	6.68		100.13		
			Sqm	1	15.00	6.70	6.45	6.58		98.63		
			Sqm	1	15.00	6.45	6.20	6.33		94.88		
			Sqm	1	15.00	6.20	6.10	6.15		92.25		
			Sqm	1	15.00	6.10	6.10	6.10		91.50		
			Sqm	1	15.00	6.10	6.00	6.05		90.75		
			Sqm	1	15.00	6.00	6.60	6.30		94.50		
			Sqm	1	15.00	6.60	6.00	6.30		94.50		
			Sqm	1	15.00	6.00	6.10	6.05		90.75		
			Sqm	1	15.00	6.10	6.30	6.20		93.00		
			Sqm	1	5.00	6.30	6.40	6.35		31.75		
			Sqm	1	9.00	4.70	4.50	4.60		41.40		
			Sqm	1	1.00	6.30	6.30	6.30		6.30		
			Sqm	1	15.00	6.30	6.30	6.30		94.50		
			Sqm	1	15.00	6.30	6.80	6.55		98.25		
			Sqm	1	15.00	6.80	7.10	6.95		104.25		
			Sqm	1	15.00	7.10	5.80	6.45		96.75		
			Sqm	1	15.00	5.80	5.20	5.50		82.50		
			Sqm	1	15.00	5.20	3.95	4.58		68.63		
			Sqm	1	2.00	3.95	3.80	3.88		7.75		
			Sqm	1	13.00	4.70	5.45	5.08		65.98		
			Sqm	1	15.00	5.45	6.10	5.78		86.63		
			Sqm	1	6.00	6.10	5.50	5.80		34.80		
		Cross Road-1										
		South to North										
0.00	6.00		Sqm	1	6.00	12.00	5.90	8.95		53.70		
6.00	12.00		Sqm	1	6.00	5.90	5.00	5.45		32.70		
12.00	15.00		Sqm	1	3.00	6.00	6.00	6.00		18.00		
15.00	19.00		Sqm	1	4.00	6.00	5.70	5.85		23.40		
		Cross Road-2										
		South to north										
0.00	15.00		Sqm	1	15.00	6.50	6.00	6.25		93.75		
15.00	30.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
30.00	45.00		Sqm	1	15.00	6.00	6.00	6.00		90.00		
45.00	60.00		Sqm	1	15.00	6.00	6.30	6.15		92.25		
60.00	67.70		Sqm	1	7.70	6.30	6.60	6.45		49.67		
67.70	69.70		Sqm	1	2.00	6.60	7.30	6.95		13.90		
		MCECHS layout										
		22nd Cross Road										
		North to South										
0.00	15.00		Sqm	1	15.00	5.05	4.95	5.00		75.00		
15.00	30.00		Sqm	1	15.00	4.95	4.30	4.63		69.38		

Layout (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	1	15.00	4.30	3.90	4.10		61.50		
	45.00		Sqm	1	15.00	3.90	4.95	4.43		66.38		
45.00	60.00		Sqm	1	15.00	4.95	4.90	4.93		73.88		
60.00	75.00		Sqm	1	15.00	4.90	3.90	4.40		66.00		
75.00	90.00		Sqm	1	15.00	3.90	4.20	4.05		60.75		
90.00	105.00		Sqm	1	15.00	3.90	4.30	4.10		61.50		
105.00	120.00		Sqm	1	15.00	4.30	4.10	4.20		63.00		
120.00	135.00		Sqm	1	6.10	4.10	4.70	4.40		26.84		
135.00	141.10											
		Deduction										
		Electric Pole	Sqm	-1	1.50	1.00	1.00	1.00		-1.50		
			Sqm	-4	0.64					-2.55		
					Area=3.142*0.9^2/4=0.64							
			Sqm	-4	1.00	1.00	1.00	1.00		-4.00		
			Sqm	-1	0.79					-0.79		
					Area=3.142*1^2/4=0.79							
		Vidhana Soudha Layout										
		(From North to South)										
			Sqm	1	15.00	6.10	5.45	5.78		86.63		
0.00	15.00		Sqm	1	14.30	5.45	8.30	6.88		98.31		
15.00	29.30											
		(From East to West)										
			Sqm	1	15.00	9.40	8.90	9.15		137.25		
0.00	15.00		Sqm	1	15.00	8.90	8.60	8.75		131.25		
15.00	30.00		Sqm	1	15.00	8.60	8.90	8.75		131.25		
30.00	45.00		Sqm	1	15.00	8.90	8.20	8.55		128.25		
45.00	60.00		Sqm	1	15.00	8.20	8.25	8.23		123.38		
60.00	75.00		Sqm	1	15.00	8.25	8.50	8.38		125.63		
75.00	90.00		Sqm	1	15.00	8.50	8.30	8.40		126.00		
90.00	105.00		Sqm	1	12.80	8.30	8.25	8.28		105.92		
105.00	117.80		Sqm	1	7.30	11.35	11.25	11.30		82.49		
117.80	125.10		Sqm	1	9.90	8.20	8.05	8.13		80.44		
125.10	135.00		Sqm	1	15.00	8.05	8.05	8.05		120.75		
135.00	150.00		Sqm	1	0.90	10.95	10.95	10.95		9.86		
150.00	150.90		Sqm	1	14.10	8.30	8.35	8.33		117.38		
150.90	165.00		Sqm	1	15.00	8.35	8.42	8.39		125.78		
165.00	180.00		Sqm	1	4.90	8.42	8.55	8.49		41.58		
180.00	184.90		Sqm	1	8.60	11.20	11.30	11.25		96.75		
184.90	193.50		Sqm	1	1.50	8.30	8.30	8.30		12.45		
193.50	195.00		Sqm	1	15.00	8.30	8.15	8.23		123.38		
195.00	210.00		Sqm	1	15.00	8.15	8.30	8.23		123.38		
210.00	225.00		Sqm	1	15.00	8.30	9.00	8.65		129.75		
225.00	240.00		Sqm	1	15.00	9.00	8.85	8.93		133.88		
240.00	255.00		Sqm	1	3.00	8.85	8.25	8.55		25.65		
255.00	258.00		Sqm	1	7.10	9.70	9.80	9.75		69.23		
258.00	265.10		Sqm	1	4.90	8.40	8.35	8.38		41.04		
265.10	270.00		Sqm	1	15.00	8.35	8.25	8.30		124.50		
270.00	285.00		Sqm	1	6.00	8.25	8.20	8.23		49.35		
285.00	291.00		Sqm	1	8.80	9.55	9.40	9.48		83.38		
291.00	299.80		Sqm	1	0.20	8.15	8.14	8.15		1.63		
299.80	300.00		Sqm	1	1.00	8.14	8.15	8.15		8.15		
300.00	301.00		Sqm	1	6.30	9.81	9.80	9.81		61.77		
301.00	307.30		Sqm	1	7.70	8.10	8.15	8.13		62.56		
307.30	315.00		Sqm	1	8.00	8.15	8.25	8.20		65.60		
315.00	323.00		Sqm	1	9.00	9.60	9.60	9.60		86.40		
323.00	332.00		Sqm	1	11.00	9.40	9.60	9.50		104.50		
332.00	343.00		Sqm	1	2.00	8.10	8.20	8.15		16.30		
343.00	345.00		Sqm	1	13.90	8.20	8.15	8.18		113.63		
345.00	358.90		Sqm	1	9.20	9.70	9.71	9.71		89.29		
358.90	368.10		Sqm	1	6.90	8.15	8.15	8.15		56.23		
368.10	375.00		Sqm	1	7.60	8.15	8.30	8.23		62.51		
375.00	382.60		Sqm	1	9.30	9.90	9.50	9.70		90.21		
382.60	391.90		Sqm	1	1.40	7.90	8.00	7.95		11.13		
391.90	393.30		Sqm	1	6.70	9.20	9.20	9.20		61.64		
393.30	400.00		Sqm	1	5.00	7.90	7.40	7.65		38.25		
400.00	405.00											

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	1	15.00	7.40	7.60	7.50		112.50		
			Sqm	1	15.00	7.60	7.40	7.50		112.50		
			Sqm	1	9.20	9.00	9.10	9.05		83.26		
			Sqm	1	2.10	7.30	7.45	7.38		15.49		
			Sqm	1	10.10	9.15	9.10	9.13		92.16		
			Sqm	1	8.60	7.45	7.35	7.40		63.64		
			Sqm	1	15.00	7.35	7.25	7.30		109.50		
			Sqm	1	15.00	7.25	7.65	7.45		111.75		
			Sqm	1	15.00	7.65	8.50	8.08		121.13		
			Sqm	1	15.20	10.00	10.60	10.30		156.56		
			Sqm	1	14.80	8.50	7.60	8.05		119.14		
			Sqm	1	15.00	7.60	7.50	7.55		113.25		
			Sqm	1	5.90	7.50	7.50	7.50		44.25		
			Sqm	1	1.80	4.80	4.80	4.80		8.64		
		Total Executed Quantity								**42717.17**	**12.85**	**548916.00**
		Tender Quantity								**48128.40**		
		Item no. 19 Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specification and directions of the Engineer in charge.										
		Defence Colony										
		6th Main Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.95	5.20	5.08	0.04	3.05		
15.00	30.00		Cum	1	15.00	5.20	5.20	5.20	0.04	3.12		
30.00	40.10		Cum	1	10.10	5.20	5.50	5.35	0.04	2.16		
40.10	43.70		Cum	1	3.60	4.32	4.75	4.54	0.04	0.65		
43.70	45.00		Cum	1	1.30	5.28	5.20	5.24	0.04	0.27		
45.00	60.00		Cum	1	15.00	5.20	4.90	5.05	0.04	3.03		
60.00	75.00		Cum	1	15.00	4.90	5.50	5.20	0.04	3.12		
75.00	90.00		Cum	1	15.00	5.50	5.10	5.30	0.04	3.18		
90.00	105.00		Cum	1	15.00	5.10	5.00	5.05	0.04	3.03		
105.00	110.80		Cum	1	5.80	5.00	5.10	5.05	0.04	1.17		
		8th Main Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.40	4.45	4.43	0.04	2.66		
15.00	30.00		Cum	1	15.00	4.45	4.90	4.68	0.04	2.81		
30.00	45.00		Cum	1	15.00	4.95	5.10	5.03	0.04	3.02		
45.00	60.00		Cum	1	15.00	5.10	5.00	5.05	0.04	3.03		
60.00	75.00		Cum	1	15.00	4.95	5.10	5.03	0.04	3.02		
75.00	90.00		Cum	1	15.00	5.10	5.05	5.08	0.04	3.05		
90.00	105.00		Cum	1	15.00	4.95	5.20	5.08	0.04	3.05		
105.00	120.00		Cum	1	15.00	5.20	5.05	5.13	0.04	3.08		
120.00	131.00		Cum	1	11.00	4.95	4.95	4.95	0.04	2.18		
		Cross Road 2										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.25	4.10	4.18	0.04	2.51		
15.00	30.00		Cum	1	15.00	4.10	4.00	4.05	0.04	2.43		
30.00	31.50		Cum	1	1.50	4.00	4.00	4.00	0.04	0.24		
		Cross Road 1										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.40	4.48	4.44	0.04	2.66		
15.00	29.50		Cum	1	14.50	4.48	4.65	4.57	0.04	2.65		
		Nithish Central Park Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.80	5.40	5.60	0.04	3.36		
15.00	21.40		Cum	1	6.40	5.40	5.70	5.55	0.04	1.42		
21.40	29.60		Cum	1	8.20	5.05	4.80	4.93	0.04	1.62		
29.60	30.00		Cum	1	0.40	5.52	5.50	5.51	0.04	0.09		
30.00	45.00		Cum	1	15.00	5.50	5.15	5.33	0.04	3.20		
45.00	60.00		Cum	1	15.00	5.15	5.15	5.15	0.04	3.09		
60.00	75.00		Cum	1	15.00	5.15	5.04	5.10	0.04	3.06		
75.00	80.00		Cum	1	5.00	5.04	6.00	5.52	0.04	1.10		
80.00	83.70		Cum	1	3.70	6.00	5.95	5.98	0.04	0.88		
83.70	87.60		Cum	1	3.90	5.30	5.30	5.30	0.04	0.83		
87.60	93.20		Cum	1	5.60	6.30	6.20	6.25	0.04	1.40		
93.20	96.20		Cum	1	3.00	5.40	5.00	5.20	0.04	0.62		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
			Cum	1	15.00	4.80	5.30	5.05	0.04	3.03		
0.00	15.00		Cum	1	7.80	5.30	5.40	5.35	0.04	1.67		
15.00	22.80		Cum	1	9.20	4.95	4.80	4.88	0.04	1.79		
22.80	32.00		Cum	1	13.00	4.75	5.03	4.89	0.04	2.54		
32.00	45.00		Cum	1	15.00	5.03	4.95	4.99	0.04	2.99		
45.00	60.00		Cum	1	15.00	4.95	5.30	5.13	0.04	3.08		
60.00	75.00		Cum	1	15.00	4.95	5.45	5.20	0.04	3.12		
75.00	90.00		Cum	1	5.10	5.45	5.65	5.55	0.04	1.13		
90.00	95.10	Palanahalli										
		For Cut Portions										
		(From West to East)										
			Cum	1	8.40	1.30	1.30	1.30	0.04	0.44		
0.00	8.40		Cum	1	15.60	2.50	3.10	2.80	0.04	1.75		
8.40	24.00	No Work	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
24.00	27.60		Cum	1	15.00	3.35	2.52	2.94	0.04	1.76		
27.60	42.60		Cum	1	2.40	2.52	2.50	2.51	0.04	0.24		
42.60	45.00		Cum	1	15.00	2.50	2.50	2.50	0.04	1.50		
45.00	60.00		Cum	1	15.00	2.50	1.95	2.23	0.04	1.34		
60.00	75.00		Cum	1	15.00	1.95	2.50	2.23	0.04	1.34		
75.00	90.00		Cum	1	15.00	2.50	1.85	2.18	0.04	1.31		
90.00	105.00		Cum	1	10.80	1.85	3.00	2.43	0.04	1.05		
105.00	115.80		Cum	1	3.20	3.00	4.30	3.65	0.04	0.47		
115.80	119.00		Cum	1	6.50	1.30	0.85	1.08	0.04	0.28		
119.00	125.50	No Work	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
125.50	132.60		Cum	1	3.00	1.50	1.65	1.58	0.04	0.19		
132.60	135.60		Cum	1	15.00	1.65	1.20	1.43	0.04	0.86		
135.60	150.60		Cum	1	2.00	4.10	4.10	4.10	0.04	0.33		
150.60	152.60		Cum	1	6.90	2.10	2.10	2.10	0.04	0.58		
152.60	159.50		Cum	1	15.00	2.10	1.00	1.55	0.04	0.93		
159.50	174.50		Cum	1	9.40	1.00	1.00	1.00	0.04	0.38		
174.50	183.90		Cum	1	15.00	1.00	1.00	1.00	0.04	0.60		
183.90	198.90		Cum	1	15.00	1.00	1.00	1.00	0.04	0.60		
198.90	213.90		Cum	1	0.40	1.00	1.70	1.35	0.04	0.02		
213.90	214.30		Cum	1	15.00	1.83	1.50	1.67	0.04	1.00		
214.30	229.30		Cum	1	13.90	1.83	1.50	1.67	0.04	0.93		
229.30	243.20		Cum	1	3.10	1.95	1.90	1.93	0.04	0.24		
243.20	246.30											
		For Road Cutting										
0.00	4.50		Cum	1	4.50	0.40	0.25	0.33	0.04	0.06		
0.00	5.00		Cum	1	5.00	0.40	0.20	0.30	0.04	0.06		
0.00	2.80		Cum	1	2.80	3.20	3.25	3.23	0.04	0.36		
0.00	4.70		Cum	1	4.70	0.70	0.45	0.58	0.04	0.11		
0.00	2.60		Cum	1	2.60	1.20	1.25	1.23	0.04	0.13		
		Deducation										
		Chamber	Cum	-1	1.90			1.40	0.04	-0.11		
		Tree Pot	Cum	-9	0.20			0.10	0.04	-0.01		
		Electric Pole	Cum	-1	0.90			0.50	0.04	-0.02		
		Man Hole (1m Dia)	Cum	-1	Area = 0.25*3.142*1^2=0.785				0.04	-0.03		
		7th Main Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.35	4.06	4.21	0.04	2.52		
15.00	17.40		Cum	1	2.40	4.06	4.25	4.16	0.04	0.40		
17.40	26.70		Cum	1	9.30	5.05	5.20	5.13	0.04	1.91		
26.70	41.70		Cum	1	15.00	4.10	4.10	4.10	0.04	2.46		
41.70	45.10		Cum	1	3.40	4.10	3.75	3.93	0.04	0.53		
45.10	60.00		Cum	1	14.90	5.10	5.10	5.10	0.04	3.04		
60.00	75.00		Cum	1	15.00	5.10	5.17	5.14	0.04	3.08		
75.00	83.70		Cum	1	8.70	5.17	5.00	5.09	0.04	1.77		
83.70	98.70		Cum	1	15.00	4.35	4.00	4.18	0.04	2.51		
98.70	100.40		Cum	1	1.70	4.00	4.00	4.00	0.04	0.27		
100.40	104.10		Cum	1	3.70	5.10	5.10	5.10	0.04	0.75		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		2nd Cross										
		(From North to South)										
			Cum	1	15.00	4.40	6.00	5.20	0.04	3.12		
			Cum	1	15.00	6.00	5.75	5.88	0.04	3.53		
			Cum	1	15.00	5.75	5.80	5.78	0.04	3.47		
			Cum	1	15.00	5.80	6.05	5.93	0.04	3.56		
			Cum	1	9.30	6.05	5.68	5.87	0.04	2.18		
			Cum	1	8.20	4.35	4.60	4.48	0.04	1.47		
			Cum	1	12.50	6.10	5.40	5.75	0.04	2.88		
			Cum	1	6.40	5.40	5.90	5.65	0.04	1.45		
		1st Cross Road										
		(From East to West)										
			Cum	1	15.00	6.50	5.40	5.95	0.04	3.57		
			Cum	1	10.40	5.40	6.00	5.70	0.04	2.37		
		8th Main Road										
		North to South										
			Cum	1	15.00	6.20	5.75	5.98	0.04	3.59		
			Cum	1	4.40	5.75	5.75	5.75	0.04	1.01		
			Cum	1	10.60	4.85	5.85	5.35	0.04	2.27		
			Cum	1	7.20	5.85	6.40	6.13	0.04	1.76		
			Cum	1	7.80	4.90	5.50	5.20	0.04	1.62		
			Cum	1	1.40	5.50	5.50	5.50	0.04	0.31		
			Cum	1	17.60	4.20	5.10	4.65	0.04	3.27		
			Cum	1	11.00	5.95	6.25	6.10	0.04	2.68		
			Cum	1	15.00	6.25	6.25	6.25	0.04	3.75		
			Cum	1	15.00	6.25	5.90	6.08	0.04	3.65		
			Cum	1	3.00	5.90	5.90	5.90	0.04	0.71		
		Vinayak Nagar										
		6th B Main Road										
		North to South										
			Cum	1	9.10	5.10	4.95	5.03	0.04	1.83		
			Cum	1	5.90	4.40	3.95	4.18	0.04	0.99		
			Cum	1	4.70	3.95	4.25	4.10	0.04	0.77		
			Cum	1	10.30	4.25	4.30	4.28	0.04	1.76		
			Cum	1	15.00	4.30	3.45	3.88	0.04	2.33		
			Cum	1	15.00	3.45	4.35	3.90	0.04	2.34		
			Cum	1	15.00	4.35	4.65	4.50	0.04	2.70		
			Cum	1	4.80	4.65	5.15	4.90	0.04	0.94		
			Cum	1	8.30	4.25	3.80	4.03	0.04	1.34		
			Cum	1	1.90	4.50	3.50	4.00	0.04	0.30		
			Cum	1	1.90	3.50	3.55	3.53	0.04	0.27		
			Cum	1	5.10	5.05	5.10	5.08	0.04	1.04		
			Cum	1	2.80	4.25	4.25	4.25	0.04	0.48		
			Cum	1	5.20	3.55	4.25	3.90	0.04	0.81		
			Cum	1	3.00	4.25	4.15	4.20	0.04	0.50		
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
			Cum	1	15.00	4.80	5.80	5.30	0.04	3.18		
			Cum	1	15.00	5.80	5.30	5.55	0.04	3.33		
			Cum	1	15.00	5.30	6.15	5.73	0.04	3.44		
			Cum	1	15.00	6.15	6.48	6.32	0.04	3.79		
			Cum	1	5.80	6.48	6.49	6.49	0.04	1.50		
		11th Cross Road										
		(From South to North)										
			Cum	1	15.00	4.20	4.10	4.15	0.04	2.49		
			Cum	1	15.00	4.10	3.80	3.95	0.04	2.37		
			Cum	1	15.00	3.80	3.65	3.73	0.04	2.24		
			Cum	1	15.00	3.65	4.00	3.83	0.04	2.30		
			Cum	1	10.00	4.00	4.10	4.05	0.04	1.62		
			Cum	1	5.00	4.10	4.00	4.05	0.04	0.81		
			Cum	1	15.00	4.00	4.64	4.32	0.04	2.59		
			Cum	1	15.00	4.64	4.90	4.77	0.04	2.86		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	15.00	4.90	4.90	4.90	0.04	2.94		
			Cum	1	15.00	4.90	4.90	4.90	0.04	2.94		
			Cum	1	15.00	4.90	5.00	4.95	0.04	2.97		
			Cum	1	15.00	5.00	4.90	4.95	0.04	2.97		
			Cum	1	3.00	4.90	4.75	4.83	0.04	0.58		
		10th Cross Road										
		(From North to South)										
			Cum	1	15.00	5.35	5.30	5.33	0.04	3.20		
			Cum	1	15.00	5.30	5.10	5.20	0.04	3.12		
			Cum	1	15.00	5.10	4.40	4.75	0.04	2.85		
			Cum	1	15.00	4.40	4.50	4.45	0.04	2.67		
			Cum	1	15.00	4.50	4.60	4.55	0.04	2.73		
			Cum	1	15.00	4.60	4.48	4.54	0.04	2.72		
			Cum	1	15.00	4.48	4.84	4.66	0.04	2.80		
			Cum	1	3.60	4.84	4.85	4.85	0.04	0.70		
			Cum	1	8.80	5.35	4.80	5.08	0.04	1.79		
			Cum	1	2.60	4.50	4.60	4.55	0.04	0.47		
			Cum	1	15.00	4.60	4.49	4.55	0.04	2.73		
			Cum	1	15.00	4.49	4.67	4.58	0.04	2.75		
			Cum	1	15.00	4.67	4.55	4.61	0.04	2.77		
			Cum	1	2.60	4.55	4.90	4.73	0.04	0.49		
		10th A Cross										
		(From North to South)										
			Cum	1	15.00	6.00	5.75	5.88	0.04	3.53		
			Cum	1	15.00	5.75	5.40	5.58	0.04	3.35		
			Cum	1	15.00	5.40	5.40	5.40	0.04	3.24		
			Cum	1	15.00	5.40	5.10	5.25	0.04	3.15		
			Cum	1	15.00	5.10	5.35	5.23	0.04	3.14		
			Cum	1	15.00	5.35	5.55	5.45	0.04	3.27		
			Cum	1	15.00	5.55	6.00	5.78	0.04	3.47		
			Cum	1	15.00	6.00	6.10	6.05	0.04	3.63		
			Cum	1	14.70	6.10	6.20	6.15	0.04	3.62		
		10th A Cross										
		(From West to East)										
			Cum	1	2.80	4.80	4.50	4.65	0.04	0.52		
		2nd Main Road										
		(From West to East)										
			Cum	1	15.00	8.80	8.70	8.75	0.04	5.25		
			Cum	1	15.00	8.70	9.13	8.92	0.04	5.35		
			Cum	1	15.00	9.13	8.50	8.82	0.04	5.29		
			Cum	1	15.00	8.50	8.40	8.45	0.04	5.07		
			Cum	1	15.00	8.40	8.55	8.48	0.04	5.09		
			Cum	1	15.00	8.55	8.10	8.33	0.04	5.00		
			Cum	1	15.00	8.10	7.60	7.85	0.04	4.71		
			Cum	1	9.30	7.60	8.00	7.80	0.04	2.90		
			Cum	1	15.00	8.00	7.45	7.73	0.04	4.64		
			Cum	1	15.00	7.45	6.85	7.15	0.04	4.29		
			Cum	1	15.00	6.85	6.80	6.83	0.04	4.10		
			Cum	1	15.00	6.80	6.90	6.85	0.04	4.11		
			Cum	1	15.00	6.90	7.65	7.28	0.04	4.37		
			Cum	1	3.30	7.65	7.40	7.53	0.04	0.99		
		Cut Portion										
			Cum	1	2.60	2.10	2.10	2.10	0.04	0.22		
		2nd Main Road To M S Nagar Road										
		(From West to East)										
			Cum	1	15.00	5.10	4.36	4.73	0.04	2.84		
			Cum	1	15.00	4.36	4.40	4.38	0.04	2.63		
			Cum	1	3.70	4.40	4.60	4.50	0.04	0.67		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		(From South to North)										
			Cum	1	15.00	5.45	5.20	5.33	0.04	3.20		
			Cum	1	15.00	5.20	5.40	5.30	0.04	3.18		
			Cum	1	15.00	5.40	5.70	5.55	0.04	3.33		
			Cum	1	15.00	5.70	5.25	5.48	0.04	3.29		
			Cum	1	15.00	5.25	5.40	5.33	0.04	3.20		
			Cum	1	15.00	5.40	5.40	5.40	0.04	3.24		
			Cum	1	15.00	5.40	5.40	5.40	0.04	3.24		
			Cum	1	15.00	5.40	5.58	5.49	0.04	3.29		
			Cum	1	15.00	5.58	5.40	5.49	0.04	3.29		
			Cum	1	15.00	5.40	5.35	5.38	0.04	3.23		
			Cum	1	15.00	5.35	5.20	5.28	0.04	3.17		
			Cum	1	15.00	5.20	5.20	5.20	0.04	3.12		
			Cum	1	15.00	5.20	5.54	5.37	0.04	3.22		
			Cum	1	2.80	5.54	6.40	5.97	0.04	0.67		
		(From East to West)										
			Cum	1	15.00	3.90	3.65	3.78	0.04	2.27		
			Cum	1	15.00	3.65	3.68	3.67	0.04	2.20		
			Cum	1	15.00	3.68	3.98	3.83	0.04	2.30		
			Cum	1	4.80	3.98	4.20	4.09	0.04	0.79		
			Cum	1	2.10	4.20	7.50	5.85	0.04	0.49		
		3A Cross Road										
		(From East to West)										
			Cum	1	15.00	3.85	3.63	3.74	0.04	2.24		
			Cum	1	15.00	3.63	3.63	3.63	0.04	2.18		
			Cum	1	11.40	3.63	4.32	3.98	0.04	1.81		
			Cum	1	3.10	4.32	7.35	5.84	0.04	0.72		
		(From North to South)										
			Cum	1	15.00	4.10	3.60	3.85	0.04	2.31		
			Cum	1	3.60	3.60	3.65	3.63	0.04	0.52		
		5th Cross Road										
		(From North to South)										
			Cum	1	3.40	8.20	6.80	7.50	0.04	1.02		
			Cum	1	11.60	6.80	6.70	6.75	0.04	3.13		
			Cum	1	15.00	6.70	6.10	6.40	0.04	3.84		
			Cum	1	15.00	6.10	6.20	6.15	0.04	3.69		
			Cum	1	11.60	6.20	6.15	6.18	0.04	2.87		
		Cut Portion										
			Cum	1	12.10	2.40	2.40	2.40	0.04	1.16		
		Hegde Nagara										
		Win Field Garden										
		5th Cross Road (W1941)										
		(From South to North)										
			Cum	1	2.70	10.80	7.45	9.13	0.04	0.99		
			Cum	1	12.30	7.45	6.70	7.08	0.04	3.48		
			Cum	1	15.00	6.70	6.65	6.68	0.04	4.01		
			Cum	1	15.00	6.65	7.00	6.83	0.04	4.10		
			Cum	1	15.00	7.00	7.50	7.25	0.04	4.35		
			Cum	1	15.00	7.50	7.00	7.25	0.04	4.35		
			Cum	1	15.00	7.00	7.00	7.00	0.04	4.20		
			Cum	1	15.00	7.00	6.85	6.93	0.04	4.16		
			Cum	1	15.00	6.85	6.25	6.55	0.04	3.93		
			Cum	1	15.00	6.25	7.05	6.65	0.04	3.99		
			Cum	1	15.00	7.05	7.05	7.05	0.04	4.23		
			Cum	1	15.00	7.05	7.05	7.05	0.04	4.23		
			Cum	1	15.00	7.05	7.05	7.05	0.04	4.23		
			Cum	1	5.20	7.05	7.40	7.23	0.04	1.50		
			Cum	1	2.80	7.00	12.00	9.50	0.04	1.06		
			Cum	1	2.50	8.00	7.90	7.95	0.04	0.80		
		6th Cross Road (W1935)										
		(From South to North)										
			Cum	1	2.00	7.50	5.90	6.70	0.04	0.54		

Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	Cum	1	13.00	5.90	5.95	5.93	0.04	3.08		
	Cum	1	15.00	5.95	6.00	5.98	0.04	3.59		
	Cum	1	15.00	6.00	5.50	5.75	0.04	3.45		
	Cum	1	15.00	5.50	5.35	5.43	0.04	3.26		
	Cum	1	15.00	5.35	5.55	5.45	0.04	3.27		
	Cum	1	15.00	5.55	5.55	5.55	0.04	3.33		
	Cum	1	15.00	5.55	5.60	5.58	0.04	3.35		
	Cum	1	15.00	5.60	5.60	5.60	0.04	3.36		
	Cum	1	15.00	5.60	5.75	5.68	0.04	3.41		
	Cum	1	15.00	5.75	4.85	5.30	0.04	3.18		
	Cum	1	15.00	4.85	4.80	4.83	0.04	2.90		
	Cum	1	15.00	4.80	6.10	5.45	0.04	3.27		
	Cum	1	1.50	6.10	5.40	5.75	0.04	0.35		
9th Cross Road (From South to North)										
	Cum	1	2.80	6.90	4.90	5.90	0.04	0.66		
	Cum	1	13.10	4.90	4.40	4.65	0.04	2.44		
	Cum	1	14.10	4.00	5.45	4.73	0.04	2.66		
	Cum	1	15.00	5.45	5.60	5.53	0.04	3.32		
	Cum	1	15.00	5.50	5.70	5.60	0.04	3.36		
	Cum	1	15.00	5.70	5.00	5.35	0.04	3.21		
	Cum	1	4.90	5.00	5.10	5.05	0.04	0.99		
	Cum	1	9.70	4.60	4.60	4.60	0.04	1.78		
	Cum	1	0.40	4.60	5.95	5.28	0.04	0.08		
	Cum	1	15.00	5.95	5.75	5.85	0.04	3.51		
	Cum	1	11.70	5.75	5.60	5.68	0.04	2.66		
	Cum	1	10.20	4.60	4.85	4.73	0.04	1.93		
	Cum	1	11.00	5.70	5.80	5.75	0.04	2.53		
MSR Mansion Road (North to South)										
	Cum	1	5.80	5.75	7.15	6.45	0.04	1.50		
	Cum	1	3.90	10.70	8.40	9.55	0.04	1.49		
	Cum	1	5.30	8.40	8.25	8.33	0.04	1.76		
	Cum	1	15.00	8.25	7.40	7.83	0.04	4.70		
	Cum	1	15.00	7.40	6.85	7.13	0.04	4.28		
	Cum	1	5.00	6.85	7.10	6.98	0.04	1.40		
Nisarga Layout										
7th Cross, Zayan Travels Car Service Centre Road, North To South										
	Cum	1	15.00	5.00	4.85	4.93	0.04	2.96		
	Cum	1	15.00	4.85	4.60	4.73	0.04	2.84		
	Cum	1	15.00	4.60	5.15	4.88	0.04	2.93		
	Cum	1	15.00	5.15	5.00	5.08	0.04	3.05		
	Cum	1	15.00	5.00	5.10	5.05	0.04	3.03		
	Cum	1	15.00	5.10	5.00	5.05	0.04	3.03		
	Cum	1	11.50	5.00	4.70	4.85	0.04	2.23		
West To East										
	Cum	1	15.00	4.90	4.80	4.85	0.04	2.91		
	Cum	1	0.70	4.80	4.80	4.80	0.04	0.13		
	Cum	1	14.30	5.30	5.60	5.45	0.04	3.12		
	Cum	1	15.00	5.60	5.15	5.38	0.04	3.23		
	Cum	1	1.70	5.15	5.15	5.15	0.04	0.35		
	Cum	1	4.90	4.15	3.95	4.05	0.04	0.79		
	Cum	1	4.60	5.30	5.25	5.28	0.04	0.97		
	Cum	1	8.40	4.20	4.30	4.25	0.04	1.43		
	Cum	1	10.40	5.30	5.35	5.33	0.04	2.22		
	Cum	1	1.60	5.35	5.36	5.36	0.04	0.34		
5th Cross Road, North To South										
	Cum	1	11.10	5.70	5.90	5.80	0.04	2.58		
	Cum	1	8.90	5.10	5.35	5.23	0.04	1.86		
	Cum	1	3.80	7.00	6.95	6.98	0.04	1.06		
	Cum	1	6.20	6.05	5.95	6.00	0.04	1.49		
	Cum	1	15.00	5.95	5.50	5.73	0.04	3.44		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	15.00	5.50	6.00	5.75	0.04	3.45		
			Cum	1	6.90	6.00	6.30	6.15	0.04	1.70		
			Cum	1	8.10	4.90	5.70	5.30	0.04	1.72		
			Cum	1	0.60	5.70	5.65	5.68	0.04	0.14		
			Cum	1	1.20	2.95	3.00	2.98	0.04	0.14		
		Mithun White Pearl Apartment Road (East To West)										
			Cum	1	15.00	6.60	6.75	6.68	0.04	4.01		
			Cum	1	15.00	6.75	6.50	6.63	0.04	3.98		
			Cum	1	15.00	6.50	6.45	6.48	0.04	3.89		
			Cum	1	15.00	6.45	6.45	6.45	0.04	3.87		
			Cum	1	15.00	6.45	6.25	6.35	0.04	3.81		
			Cum	1	15.00	6.25	6.20	6.23	0.04	3.74		
			Cum	1	6.40	6.20	5.85	6.03	0.04	1.54		
		Venkateshwara Layout 3rd Cross Road South to North										
0.00	15.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
15.00	30.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
30.00	45.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
45.00	60.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
60.00	75.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
75.00	90.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
90.00	105.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
105.00	120.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
120.00	135.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
135.00	150.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
150.00	165.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
165.00	180.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
180.00	195.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
195.00	210.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
210.00	220.00		Cum	1	10.00	5.50	5.50	5.50	0.04	2.20		
		4th Cross Road North to South										
0.00	15.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
15.00	30.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
30.00	45.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
45.00	60.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
60.00	75.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
75.00	90.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
90.00	105.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
105.00	120.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
120.00	135.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
135.00	150.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
150.00	165.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
165.00	180.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
180.00	195.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
195.00	210.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
210.00	220.00		Cum	1	10.00	5.50	5.50	5.50	0.04	2.20		
		5th Cross Road North to South										
0.00	15.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
15.00	30.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
30.00	45.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
45.00	60.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
60.00	75.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
75.00	90.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
90.00	105.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
105.00	120.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
120.00	135.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
135.00	150.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
150.00	165.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
165.00	180.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
180.00	195.00		Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		

Layout (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	15.00	5.50	5.50	5.50	0.04	3.30		
			Cum	1	10.00	5.50	5.50	5.50	0.04	2.20		
200.00	210.00											
210.00	220.00											
		Deduction										
		Chembar	Cum	-1	0.64				0.04	-0.03		
					Area of Circle=(3.14X0.9²)/4=0.64							
			Cum	-4	0.70	1.00	1.00	1.00	0.04	-0.11		
			Cum	-3	0.90	0.80	0.80	0.80	0.04	-0.09		
		Katgenahalli										
		Muneshwara Provision Store										
		Kalidas Layout										
		3rd Main Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	6.70	6.65	6.68	0.04	4.01		
15.00	30.00		Cum	1	15.00	6.65	6.65	6.65	0.04	3.99		
30.00	45.00		Cum	1	15.00	6.65	6.00	6.33	0.04	3.80		
45.00	60.00		Cum	1	15.00	6.00	5.80	5.90	0.04	3.54		
60.00	66.40		Cum	1	6.40	5.80	5.60	5.70	0.04	1.46		
66.40	75.00		Cum	1	8.60	5.60	5.60	5.60	0.04	1.93		
75.00	90.00		Cum	1	15.00	5.60	5.50	5.55	0.04	3.33		
90.00	105.00		Cum	1	15.00	5.50	5.80	5.65	0.04	3.39		
105.00	113.00		Cum	1	8.00	5.80	4.30	5.05	0.04	1.62		
		Mk Provision Store Road										
		(From East to West)										
0.00	11.20		Cum	1	11.20	6.20	6.10	6.15	0.04	2.76		
11.20	19.60		Cum	1	8.40	5.60	4.94	5.27	0.04	1.77		
19.60	30.00		Cum	1	10.40	5.40	5.30	5.35	0.04	2.23		
30.00	40.20		Cum	1	10.20	5.30	5.40	5.35	0.04	2.18		
40.20	45.00		Cum	1	4.80	5.40	6.30	5.85	0.04	1.12		
45.00	47.50		Cum	1	2.50	6.30	7.00	6.65	0.04	0.67		
47.50	60.00		Cum	1	12.50	5.00	4.50	4.75	0.04	2.38		
60.00	75.00		Cum	1	15.00	4.50	5.75	5.13	0.04	3.08		
75.00	90.00		Cum	1	15.00	5.75	5.38	5.57	0.04	3.34		
90.00	105.00		Cum	1	15.00	5.38	5.10	5.24	0.04	3.14		
105.00	120.00		Cum	1	15.00	5.10	4.85	4.98	0.04	2.99		
120.00	135.00		Cum	1	15.00	4.85	4.80	4.83	0.04	2.90		
135.00	150.00		Cum	1	15.00	4.80	5.50	5.15	0.04	3.09		
150.00	155.00		Cum	1	5.00	5.50	5.88	5.69	0.04	1.14		
			Cum	1	Triangular Portion 9.5*8.2*12.55=977.65				0.04	39.11		
			Cum	1	Triangular Portion 10.5*3.3*11=381.15				0.04	15.25		
		Deduction										
0.00	1.40		Cum	-1	1.40	1.00	1.00	1.00	0.04	-0.06		
		Cross Road - 1										
		(From South to North)										
0.00	15.00		Cum	1	15.00	4.75	4.55	4.65	0.04	2.79		
15.00	30.00		Cum	1	15.00	4.55	5.10	4.83	0.04	2.90		
30.00	45.00		Cum	1	15.00	5.10	4.80	4.95	0.04	2.97		
45.00	60.00		Cum	1	15.00	4.80	4.55	4.68	0.04	2.81		
60.00	75.00		Cum	1	15.00	4.55	5.00	4.78	0.04	2.87		
75.00	88.60		Cum	1	13.60	5.00	4.50	4.75	0.04	2.58		
		Cross Road - 2										
		(From North to South)										
0.00	4.30		Cum	1	4.30	5.10	5.00	5.05	0.04	0.87		
4.30	15.00		Cum	1	10.70	5.00	5.10	5.05	0.04	2.16		
15.00	20.60		Cum	1	5.60	5.10	5.30	5.20	0.04	1.16		
20.60	30.00		Cum	1	9.40	6.65	6.20	6.43	0.04	2.42		
30.00	40.60		Cum	1	10.60	6.20	6.60	6.40	0.04	2.71		
40.60	45.00		Cum	1	4.40	6.60	5.90	6.25	0.04	1.10		
45.00	60.00		Cum	1	15.00	5.90	5.95	5.93	0.04	3.56		
60.00	75.00		Cum	1	15.00	5.95	5.85	5.90	0.04	3.54		

BMP (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	15.00	5.85	6.38	6.12	0.04	3.67		
			Cum	1	15.00	6.38	5.50	5.94	0.04	3.56		
			Cum	1	15.00	5.50	5.69	5.60	0.04	3.36		
			Cum	1	3.00	5.69	5.00	5.35	0.04	0.64		
90.00	105.00											
105.00	120.00											
120.00	123.00											
		Kattigenahalli										
		Durgamba Layout										
		Amulya Family Restaurant Road (N-S)										
			Cum	1	15.00	6.90	6.40	6.65	0.04	3.99		
0.00	15.00		Cum	1	15.00	6.40	6.05	6.23	0.04	3.74		
15.00	30.00		Cum	1	15.00	5.60	5.30	5.45	0.04	3.27		
30.00	45.00		Cum	1	15.00	5.30	4.95	5.13	0.04	3.08		
45.00	60.00		Cum	1	15.00	4.95	5.05	5.00	0.04	3.00		
60.00	75.00		Cum	1	6.00	5.05	5.05	5.05	0.04	1.21		
75.00	81.00		Cum	1	9.00	5.70	5.90	5.80	0.04	2.09		
81.00	90.00		Cum	1	15.00	5.90	5.30	5.60	0.04	3.36		
90.00	105.00		Cum	1	13.80	5.30	4.60	4.95	0.04	2.73		
105.00	118.80		Cum	1	9.10	5.80	5.85	5.83	0.04	2.12		
118.80	127.90		Cum	1	7.10	4.95	4.85	4.90	0.04	1.39		
127.90	135.00		Cum	1	2.10	4.85	5.05	4.95	0.04	0.42		
135.00	137.10		Cum	1	12.90	4.35	4.95	4.65	0.04	2.40		
137.10	150.00		Cum	1	15.00	4.95	4.60	4.78	0.04	2.87		
150.00	165.00		Cum	1	15.00	4.60	5.25	4.93	0.04	2.96		
165.00	180.00		Cum	1	2.50	5.25	5.15	5.20	0.04	0.52		
180.00	182.50		Cum	1	12.50	5.85	6.60	6.23	0.04	3.11		
182.50	195.00		Cum	1	15.00	6.60	6.15	6.38	0.04	3.83		
195.00	210.00		Cum	1	8.00	6.15	6.00	6.08	0.04	1.94		
210.00	218.00											
		Kaustaba House Road #33 (W-E)										
			Cum	1	6.30	7.45	7.55	7.50	0.04	1.89		
0.00	6.30		Cum	1	8.70	6.80	6.48	6.64	0.04	2.31		
6.30	15.00		Cum	1	15.00	6.48	6.00	6.24	0.04	3.74		
15.00	30.00		Cum	1	15.00	6.00	5.70	5.85	0.04	3.51		
30.00	45.00		Cum	1	12.90	5.70	6.05	5.88	0.04	3.03		
45.00	57.90		Cum	1	2.10	6.95	7.70	7.33	0.04	0.62		
57.90	60.00		Cum	1	3.60	7.70	7.65	7.68	0.04	1.11		
60.00	63.60											
		Sukruthi House Road #26 (S-N)										
			Cum	1	8.30	5.60	5.90	5.75	0.04	1.91		
0.00	8.30		Cum	1	6.70	5.35	4.90	5.13	0.04	1.37		
8.30	15.00		Cum	1	15.00	4.90	5.80	5.35	0.04	3.21		
15.00	30.00		Cum	1	15.00	5.80	5.35	5.58	0.04	3.35		
30.00	45.00		Cum	1	15.00	5.35	5.30	5.33	0.04	3.20		
45.00	60.00		Cum	1	0.50	5.30	5.30	5.30	0.04	0.11		
60.00	60.50		Cum	1	14.50	5.85	6.20	6.03	0.04	3.49		
60.50	75.00		Cum	1	15.00	6.20	5.40	5.80	0.04	3.48		
75.00	90.00		Cum	1	8.70	5.40	5.20	5.30	0.04	1.84		
90.00	98.70		Cum	1	6.30	4.40	4.95	4.68	0.04	1.18		
98.70	105.00		Cum	1	3.20	4.95	4.95	4.95	0.04	0.63		
105.00	108.20		Cum	1	4.00	5.50	5.20	5.35	0.04	0.86		
108.20	112.20		Cum	1	7.80	4.40	4.60	4.50	0.04	1.40		
112.20	120.00		Cum	1	5.80	4.60	4.50	4.55	0.04	1.06		
120.00	125.80		Cum	1	9.90	4.00	4.45	4.23	0.04	1.67		
125.80	135.70		Cum	1	8.20	5.60	5.95	5.78	0.04	1.89		
135.70	143.90		Cum	1	6.10	6.65	5.75	6.20	0.04	1.51		
143.90	150.00		Cum	1	14.30	5.75	5.85	5.80	0.04	3.32		
150.00	164.30											
		SP Singh House Road (E-W)										
0.00	15.00		Cum	1	15.00	6.35	5.65	6.00	0.04	3.60		
15.00	19.10		Cum	1	4.10	5.65	6.00	5.83	0.04	0.96		
19.10	30.00		Cum	1	10.90	5.20	5.65	5.43	0.04	2.37		
30.00	34.20		Cum	1	4.20	5.65	6.10	5.88	0.04	0.99		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Form mrd Main To Muneshwara provsion										
0.00	1.70		Cum	1	1.70	5.05	5.05	5.05	0.04	0.34		
1.70	15.00		Cum	1	13.30	7.30	7.40	7.35	0.04	3.91		
15.00	30.00		Cum	1	15.00	7.40	7.10	7.25	0.04	4.35		
30.00	45.00		Cum	1	15.00	7.10	6.75	6.93	0.04	4.16		
45.00	60.00		Cum	1	15.00	6.75	7.55	7.15	0.04	4.29		
60.00	75.00		Cum	1	15.00	7.55	6.45	7.00	0.04	4.20		
75.00	77.80		Cum	1	2.80	6.45	5.70	6.08	0.04	0.68		
77.80	90.00		Cum	1	12.20	6.80	7.15	6.98	0.04	3.40		
90.00	95.90		Cum	1	5.90	7.15	6.95	7.05	0.04	1.66		
95.90	105.00		Cum	1	9.10	6.25	6.30	6.28	0.04	2.28		
105.00	117.90		Cum	1	12.90	6.30	5.90	6.10	0.04	3.15		
117.90	120.00		Cum	1	2.10	6.75	6.80	6.78	0.04	0.57		
120.00	124.80		Cum	1	4.80	6.80	5.80	6.30	0.04	1.21		
		Deduction										
		Chamber	Cum	-1	0.70	1.00	1.00	1.00	0.04	-0.03		
		Manhole	Cum	-1	0.64				0.04	-0.03		
					Area of Circle = (3.142*0.9^2)/4= 0.64							
		Manhole	Cum	-1	1.13				0.04	-0.05		
					Area of Circle = (3.142*1.2^2)/4= 1.13							
		Green Garden Main Road (West to East)										
0.00	15.00		Cum	1	15.00	6.00	6.18	6.09	0.04	3.65		
15.00	30.00		Cum	1	15.00	6.18	6.18	6.18	0.04	3.71		
30.00	42.70		Cum	1	12.70	6.18	5.75	5.97	0.04	3.03		
42.70	45.00		Cum	1	2.30	5.00	4.90	4.95	0.04	0.46		
45.00	53.70		Cum	1	8.70	4.90	4.95	4.93	0.04	1.71		
53.70	60.00		Cum	1	6.30	6.80	5.85	6.33	0.04	1.59		
60.00	75.00		Cum	1	15.00	5.85	6.00	5.93	0.04	3.56		
75.00	90.00		Cum	1	15.00	6.00	5.95	5.98	0.04	3.59		
90.00	105.00		Cum	1	15.00	5.95	6.10	6.03	0.04	3.62		
105.00	120.00		Cum	1	15.00	6.10	5.35	5.73	0.04	3.44		
120.00	126.90		Cum	1	6.90	5.35	5.50	5.43	0.04	1.50		
126.90	130.00		Cum	1	3.10	6.00	6.00	6.00	0.04	0.74		
130.00	145.00		Cum	1	15.00	6.00	6.05	6.03	0.04	3.62		
145.00	154.30		Cum	1	9.30	6.05	6.10	6.08	0.04	2.26		
154.30	160.00		Cum	1	5.70	5.10	5.00	5.05	0.04	1.15		
160.00	171.40		Cum	1	11.40	5.00	4.85	4.93	0.04	2.25		
		Cross Road-4 (South to North)										
0.00	1.60		Cum	1	1.60	4.70	4.60	4.65	0.04	0.30		
1.60	15.00		Cum	1	13.40	6.15	5.50	5.83	0.04	3.12		
15.00	23.50		Cum	1	8.50	5.50	5.60	5.55	0.04	1.89		
23.50	30.00		Cum	1	6.50	5.15	5.45	5.30	0.04	1.38		
30.00	33.70		Cum	1	3.70	5.45	5.70	5.58	0.04	0.83		
		Sri Ganga House Road East to West										
0.00	3.80		Cum	1	3.80	5.70	5.70	5.70	0.04	0.87		
3.80	13.20		Cum	1	9.40	5.40	5.40	5.40	0.04	2.03		
13.20	15.00		Cum	1	1.80	5.75	5.70	5.73	0.04	0.41		
15.00	27.40		Cum	1	12.40	5.70	5.45	5.58	0.04	2.77		
27.40	30.00		Cum	1	2.60	5.25	4.80	5.03	0.04	0.52		
30.00	45.00		Cum	1	15.00	4.80	5.30	5.05	0.04	3.03		
45.00	60.00		Cum	1	15.00	5.30	5.55	5.43	0.04	3.26		
60.00	69.30		Cum	1	9.30	5.55	6.40	5.98	0.04	2.22		
		Cross Road-3 (North to South)										
0.00	1.70		Cum	1	1.70	4.70	4.70	4.70	0.04	0.32		
1.70	15.00		Cum	1	13.30	6.80	5.50	6.15	0.04	3.27		
15.00	30.00		Cum	1	15.00	5.50	5.40	5.45	0.04	3.27		
30.00	45.00		Cum	1	15.00	5.40	5.45	5.43	0.04	3.26		

BMP (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	1.10	5.45	5.45	5.45	0.04	0.24		
			Cum	1	2.80	6.15	6.40	6.28	0.04	0.70		
45.00	46.10											
46.10	48.90											
		Cross Road 2										
		(South to North)										
			Cum	1	11.80	5.75	5.60	5.68	0.04	2.68		
0.00	11.80		Cum	1	3.20	4.90	4.70	4.80	0.04	0.61		
11.80	15.00		Cum	1	6.10	4.70	4.65	4.68	0.04	1.14		
15.00	21.10		Cum	1	8.90	5.20	5.25	5.23	0.04	1.86		
21.10	30.00		Cum	1	15.00	5.25	5.35	5.30	0.04	3.18		
30.00	45.00		Cum	1	15.00	5.35	5.40	5.38	0.04	3.23		
45.00	60.00		Cum	1	15.00	5.40	5.40	5.40	0.04	3.24		
60.00	75.00		Cum	1	15.00	5.40	5.65	5.53	0.04	3.32		
75.00	90.00		Cum	1	10.30	5.65	5.85	5.75	0.04	2.37		
90.00	100.30		Cum	1	2.10	5.85	6.00	5.93	0.04	0.50		
100.30	102.40											
		Cross Road 1										
		(North to South)										
			Cum	1	2.90	6.50	6.40	6.45	0.04	0.75		
0.00	2.90		Cum	1	12.10	6.40	5.90	6.15	0.04	2.98		
2.90	15.00		Cum	1	15.00	5.90	5.75	5.83	0.04	3.50		
15.00	30.00		Cum	1	15.00	5.75	5.70	5.73	0.04	3.44		
30.00	45.00		Cum	1	15.00	5.70	5.50	5.60	0.04	3.36		
45.00	60.00		Cum	1	15.00	5.50	5.40	5.45	0.04	3.27		
60.00	75.00		Cum	1	15.00	5.40	5.55	5.48	0.04	3.29		
75.00	90.00		Cum	1	12.30	5.55	5.80	5.68	0.04	2.79		
90.00	102.30											
		Pyramid apartment main road										
		(East to West)										
			Cum	1	1.10	8.16	8.15	8.16	0.04	0.36		
0.00	1.10		Cum	1	1.30	8.15	6.80	7.48	0.04	0.39		
1.10	2.40		Cum	1	2.30	6.80	6.60	6.70	0.04	0.62		
2.40	4.70		Cum	1	7.70	7.65	7.85	7.75	0.04	2.39		
4.70	12.40		Cum	1	2.60	7.85	7.70	7.78	0.04	0.81		
12.40	15.00		Cum	1	15.00	7.70	8.35	8.03	0.04	4.82		
15.00	30.00		Cum	1	2.00	8.35	8.35	8.35	0.04	0.67		
30.00	32.00		Cum	1	13.00	8.35	8.50	8.43	0.04	4.38		
32.00	45.00		Cum	1	15.00	8.50	8.65	8.58	0.04	5.15		
45.00	60.00		Cum	1	15.00	8.65	8.70	8.68	0.04	5.21		
60.00	75.00		Cum	1	6.10	8.70	8.75	8.73	0.04	2.13		
75.00	81.10		Cum	1	8.90	8.75	8.20	8.48	0.04	3.02		
81.10	90.00		Cum	1	15.00	8.20	8.45	8.33	0.04	5.00		
90.00	105.00		Cum	1	15.00	8.45	8.38	8.42	0.04	5.05		
105.00	120.00		Cum	1	8.00	8.38	8.40	8.39	0.04	2.68		
120.00	128.00											
		Cross Road 3 Near Pyramid apartment										
		(North to South)										
0.00	2.90		Cum	1	2.90	6.40	6.35	6.38	0.04	0.74		
2.90	15.00		Cum	1	12.10	6.35	5.75	6.05	0.04	2.93		
15.00	30.00		Cum	1	15.00	5.75	5.70	5.73	0.04	3.44		
30.00	44.00		Cum	1	14.00	5.70	5.10	5.40	0.04	3.02		
		Cross Road 2 Near Pyramid apartment										
		(North to South)										
0.00	3.60		Cum	1	3.60	6.40	6.40	6.40	0.04	0.92		
3.60	15.00		Cum	1	11.40	5.00	5.10	5.05	0.04	2.30		
15.00	30.00		Cum	1	15.00	5.10	4.85	4.98	0.04	2.99		
30.00	32.80		Cum	1	2.80	4.85	4.85	4.85	0.04	0.54		
32.80	42.30		Cum	1	9.50	3.80	4.00	3.90	0.04	1.48		
42.30	45.10		Cum	1	2.80	5.10	5.10	5.10	0.04	0.57		
45.10	48.30		Cum	1	3.20	5.10	5.00	5.05	0.04	0.65		
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
0.00	4.50		Cum	1	4.50	6.40	5.50	5.95	0.04	1.07		
4.50	15.00		Cum	1	10.50	5.50	5.25	5.38	0.04	2.26		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	30.00		Cum	1	15.00	5.25	5.25	5.25	0.04	3.15		
30.00	45.00		Cum	1	15.00	5.25	5.40	5.33	0.04	3.20		
45.00	51.70		Cum	1	6.70	5.00	4.70	4.85	0.04	1.30		
51.70	52.20		Cum	1	0.50	4.70	5.20	4.95	0.04	0.10		
52.20	60.00		Cum	1	7.80	5.20	5.45	5.33	0.04	1.66		
60.00	75.00		Cum	1	15.00	5.45	5.45	5.45	0.04	3.27		
75.00	90.00		Cum	1	15.00	5.45	4.85	5.15	0.04	3.09		
90.00	105.00		Cum	1	15.00	4.85	5.65	5.25	0.04	3.15		
105.00	120.00		Cum	1	15.00	5.65	5.60	5.63	0.04	3.38		
120.00	127.20		Cum	1	7.20	5.60	5.55	5.58	0.04	1.61		
		Car 24 Beside Road										
		From Agrahara Main Road to Lake										
		East to West										
0.00	15.00		Cum	1	15.00	4.80	4.60	4.70	0.04	2.82		
15.00	27.00		Cum	1	12.00	4.60	4.65	4.63	0.04	2.22		
27.00	30.00		Cum	1	3.00	5.40	5.70	5.55	0.04	0.67		
30.00	45.00		Cum	1	15.00	5.70	5.70	5.70	0.04	3.42		
45.00	60.00		Cum	1	15.00	5.70	6.30	6.00	0.04	3.60		
60.00	75.00		Cum	1	15.00	6.30	6.30	6.30	0.04	3.78		
75.00	90.00		Cum	1	15.00	6.30	6.50	6.40	0.04	3.84		
90.00	105.00		Cum	1	15.00	6.50	6.65	6.58	0.04	3.95		
105.00	120.00		Cum	1	15.00	6.65	6.40	6.53	0.04	3.92		
120.00	135.00		Cum	1	15.00	6.40	6.20	6.30	0.04	3.78		
135.00	150.00		Cum	1	15.00	6.20	6.10	6.15	0.04	3.69		
150.00	165.00		Cum	1	15.00	6.10	6.30	6.20	0.04	3.72		
165.00	180.00		Cum	1	15.00	6.30	6.10	6.20	0.04	3.72		
180.00	195.00		Cum	1	15.00	6.10	6.25	6.18	0.04	3.71		
195.00	210.00		Cum	1	15.00	6.25	6.50	6.38	0.04	3.83		
210.00	225.00		Cum	1	15.00	6.50	6.40	6.45	0.04	3.87		
225.00	240.00		Cum	1	15.00	6.40	6.50	6.45	0.04	3.87		
240.00	255.00		Cum	1	15.00	6.50	6.65	6.58	0.04	3.95		
255.00	270.00		Cum	1	15.00	6.65	6.70	6.68	0.04	4.01		
270.00	285.00		Cum	1	15.00	6.70	6.45	6.58	0.04	3.95		
285.00	300.00		Cum	1	15.00	6.45	6.20	6.33	0.04	3.80		
300.00	315.00		Cum	1	15.00	6.20	6.10	6.15	0.04	3.69		
315.00	330.00		Cum	1	15.00	6.10	6.10	6.10	0.04	3.66		
330.00	345.00		Cum	1	15.00	6.10	6.00	6.05	0.04	3.63		
345.00	360.00		Cum	1	15.00	6.00	6.60	6.30	0.04	3.78		
360.00	375.00		Cum	1	15.00	6.60	6.00	6.30	0.04	3.78		
375.00	390.00		Cum	1	15.00	6.00	6.10	6.05	0.04	3.63		
390.00	405.00		Cum	1	15.00	6.10	6.30	6.20	0.04	3.72		
405.00	410.00		Cum	1	5.00	6.30	6.40	6.35	0.04	1.27		
410.00	419.00		Cum	1	9.00	4.70	4.50	4.60	0.04	1.66		
419.00	420.00		Cum	1	1.00	6.30	6.30	6.30	0.04	0.25		
420.00	435.00		Cum	1	15.00	6.30	6.30	6.30	0.04	3.78		
435.00	450.00		Cum	1	15.00	6.30	6.80	6.55	0.04	3.93		
450.00	465.00		Cum	1	15.00	6.80	7.10	6.95	0.04	4.17		
465.00	480.00		Cum	1	15.00	7.10	5.80	6.45	0.04	3.87		
480.00	495.00		Cum	1	15.00	5.80	5.20	5.50	0.04	3.30		
495.00	510.00		Cum	1	15.00	5.20	3.95	4.58	0.04	2.75		
510.00	512.00		Cum	1	2.00	3.95	3.80	3.88	0.04	0.31		
512.00	525.00		Cum	1	13.00	4.70	5.45	5.08	0.04	2.64		
525.00	540.00		Cum	1	15.00	5.45	6.10	5.78	0.04	3.47		
540.00	546.00		Cum	1	6.00	6.10	5.50	5.80	0.04	1.39		
		Cross Road-1										
		South to North										
0.00	6.00		Cum	1	6.00	12.00	5.90	8.95	0.04	2.15		
6.00	12.00		Cum	1	6.00	5.90	5.00	5.45	0.04	1.31		
12.00	15.00		Cum	1	3.00	6.00	6.00	6.00	0.04	0.72		
15.00	19.00		Cum	1	4.00	6.00	5.70	5.85	0.04	0.94		
		Cross Road-2										
		South to north										
0.00	15.00		Cum	1	15.00	6.50	6.00	6.25	0.04	3.75		
15.00	30.00		Cum	1	15.00	6.00	6.00	6.00	0.04	3.60		
30.00	45.00		Cum	1	15.00	6.00	6.00	6.00	0.04	3.60		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	1	15.00	6.00	6.30	6.15	0.04	3.69		
			Cum	1	7.70	6.30	6.60	6.45	0.04	1.99		
			Cum	1	2.00	6.60	7.30	6.95	0.04	0.56		
60.00	67.70											
67.70	69.70											
		MCECHS layout										
		22nd Cross Road										
		North to South										
			Cum	1	15.00	5.05	4.95	5.00	0.04	3.00		
0.00	15.00		Cum	1	15.00	4.95	4.30	4.63	0.04	2.78		
15.00	30.00		Cum	1	15.00	4.30	3.90	4.10	0.04	2.46		
30.00	45.00		Cum	1	15.00	3.90	4.95	4.43	0.04	2.66		
45.00	60.00		Cum	1	15.00	4.95	4.90	4.93	0.04	2.96		
60.00	75.00		Cum	1	15.00	4.90	3.90	4.40	0.04	2.64		
75.00	90.00		Cum	1	15.00	3.90	4.20	4.05	0.04	2.43		
90.00	105.00		Cum	1	15.00	3.90	4.30	4.10	0.04	2.46		
105.00	120.00		Cum	1	15.00	4.30	4.10	4.20	0.04	2.52		
120.00	135.00		Cum	1	6.10	4.10	4.70	4.40	0.04	1.07		
135.00	141.10											
		Vidhana Soudha Layout										
		(From North to South)										
			Cum	1	15.00	6.10	5.45	5.78	0.04	3.47		
0.00	15.00		Cum	1	14.30	5.45	8.30	6.88	0.04	3.93		
15.00	29.30											
		(From East to West)										
0.00	15.00		Cum	1	15.00	9.40	8.90	9.15	0.04	5.49		
15.00	30.00		Cum	1	15.00	8.90	8.60	8.75	0.04	5.25		
30.00	45.00		Cum	1	15.00	8.60	8.90	8.75	0.04	5.25		
45.00	60.00		Cum	1	15.00	8.90	8.20	8.55	0.04	5.13		
60.00	75.00		Cum	1	15.00	8.20	8.25	8.23	0.04	4.94		
75.00	90.00		Cum	1	15.00	8.25	8.50	8.38	0.04	5.03		
90.00	105.00		Cum	1	15.00	8.50	8.30	8.40	0.04	5.04		
105.00	117.80		Cum	1	12.80	8.30	8.25	8.28	0.04	4.24		
117.80	125.10		Cum	1	7.30	11.35	11.25	11.30	0.04	3.30		
125.10	135.00		Cum	1	9.90	8.20	8.05	8.13	0.04	3.22		
135.00	150.00		Cum	1	15.00	8.05	8.05	8.05	0.04	4.83		
150.00	150.90		Cum	1	0.90	10.95	10.95	10.95	0.04	0.39		
150.90	165.00		Cum	1	14.10	8.30	8.35	8.33	0.04	4.70		
165.00	180.00		Cum	1	15.00	8.35	8.42	8.39	0.04	5.03		
180.00	184.90		Cum	1	4.90	8.42	8.55	8.49	0.04	1.66		
184.90	193.50		Cum	1	8.60	11.20	11.30	11.25	0.04	3.87		
193.50	195.00		Cum	1	1.50	8.30	8.30	8.30	0.04	0.50		
195.00	210.00		Cum	1	15.00	8.30	8.15	8.23	0.04	4.94		
210.00	225.00		Cum	1	15.00	8.15	8.30	8.23	0.04	4.94		
225.00	240.00		Cum	1	15.00	8.30	9.00	8.65	0.04	5.19		
240.00	255.00		Cum	1	15.00	9.00	8.85	8.93	0.04	5.36		
255.00	258.00		Cum	1	3.00	8.85	8.25	8.55	0.04	1.03		
258.00	265.10		Cum	1	7.10	9.70	9.80	9.75	0.04	2.77		
265.10	270.00		Cum	1	4.90	8.40	8.35	8.38	0.04	1.64		
270.00	285.00		Cum	1	15.00	8.35	8.25	8.30	0.04	4.98		
285.00	291.00		Cum	1	6.00	8.25	8.20	8.23	0.04	1.97		
291.00	299.80		Cum	1	8.80	9.55	9.40	9.48	0.04	3.34		
299.80	300.00		Cum	1	0.20	8.15	8.14	8.15	0.04	0.07		
300.00	301.00		Cum	1	1.00	8.14	8.15	8.15	0.04	0.33		
301.00	307.30		Cum	1	6.30	9.81	9.80	9.81	0.04	2.47		
307.30	315.00		Cum	1	7.70	8.10	8.15	8.13	0.04	2.50		
315.00	323.00		Cum	1	8.00	8.15	8.25	8.20	0.04	2.62		
323.00	332.00		Cum	1	9.00	9.60	9.60	9.60	0.04	3.46		
332.00	343.00		Cum	1	11.00	9.40	9.60	9.50	0.04	4.18		
343.00	345.00		Cum	1	2.00	8.10	8.20	8.15	0.04	0.65		
345.00	358.90		Cum	1	13.90	8.20	8.15	8.18	0.04	4.55		
358.90	368.10		Cum	1	9.20	9.70	9.71	9.71	0.04	3.57		
368.10	375.00		Cum	1	6.90	8.15	8.15	8.15	0.04	2.25		
375.00	382.60		Cum	1	7.60	8.15	8.30	8.23	0.04	2.50		
382.60	391.90		Cum	1	9.30	9.90	9.50	9.70	0.04	3.61		
391.90	393.30		Cum	1	1.40	7.90	8.00	7.95	0.04	0.45		
393.30	400.00		Cum	1	6.70	9.20	9.20	9.20	0.04	2.47		
400.00	405.00		Cum	1	5.00	7.90	7.40	7.65	0.04	1.53		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	420.00		Cum	1	15.00	7.40	7.60	7.50	0.04	4.50		
420.00	435.00		Cum	1	15.00	7.60	7.40	7.50	0.04	4.50		
435.00	444.20		Cum	1	9.20	9.00	9.10	9.05	0.04	3.33		
444.20	446.30		Cum	1	2.10	7.30	7.45	7.38	0.04	0.62		
446.30	456.40		Cum	1	10.10	9.15	9.10	9.13	0.04	3.69		
456.40	465.00		Cum	1	8.60	7.45	7.35	7.40	0.04	2.55		
465.00	480.00		Cum	1	15.00	7.35	7.25	7.30	0.04	4.38		
480.00	495.00		Cum	1	15.00	7.25	7.65	7.45	0.04	4.47		
495.00	510.00		Cum	1	15.00	7.65	8.50	8.08	0.04	4.85		
510.00	525.20		Cum	1	15.20	10.00	10.60	10.30	0.04	6.26		
525.20	540.00		Cum	1	14.80	8.50	7.60	8.05	0.04	4.77		
540.00	555.00		Cum	1	15.00	7.60	7.50	7.55	0.04	4.53		
555.00	560.90		Cum	1	5.90	7.50	7.50	7.50	0.04	1.77		
560.90	562.70		Cum	1	1.80	4.80	4.80	4.80	0.04	0.35		
		Deduction										
		Electric Pole	Cum	-1	1.50	1.00	1.00	1.00	0.04	-0.06		
			Cum	-4	0.64				0.04	-0.10		
					Area=3.142*0.9^2/4=0.64							
			Cum	-4	1.00	1.00	1.00	1.00	0.04	-0.16		
			Cum	-1	0.79				0.04	-0.03		
					Area=3.142*1^2/4=0.79							
		Total Executed Quantity								**1708.69**	**8534.82**	**14583336.00**
		Tender Quantity								**1925.14**		

Item no. 20 Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. and directions of the Engineer in charge.

		Defence Colony										
		6th Main Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	40.10		Sqm	2	10.10	0.10	0.10	0.10		2.02		
40.10	43.70		Sqm	2	3.60	0.10	0.10	0.10		0.72		
43.70	45.00		Sqm	2	1.30	0.10	0.10	0.10		0.26		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	110.80		Sqm	2	5.80	0.10	0.10	0.10		1.16		
		8th Main Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	131.00		Sqm	2	11.00	0.10	0.10	0.10		2.20		
		Cross Road 2										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	31.50		Sqm	2	1.50	0.10	0.10	0.10		0.30		
		Cross Road 1										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	29.50		Sqm	2	14.50	0.10	0.10	0.10		2.90		
		Nithish Central Park Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	21.40		Sqm	2	6.40	0.10	0.10	0.10		1.28		
21.40	29.60		Sqm	2	8.20	0.10	0.10	0.10		1.64		
29.60	30.00		Sqm	2	0.40	0.10	0.10	0.10		0.08		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	5.00	0.10	0.10	0.10		1.00		
			Sqm	2	3.70	0.10	0.10	0.10		0.74		
			Sqm	2	3.90	0.10	0.10	0.10		0.78		
			Sqm	2	5.60	0.10	0.10	0.10		1.12		
			Sqm	2	3.00	0.10	0.10	0.10		0.60		
45.00	60.00											
60.00	75.00											
75.00	80.00											
80.00	83.70											
83.70	87.60											
87.60	93.20											
93.20	96.20											
		Anand Nagar										
		1st Cross Road										
		Royal ACE Road										
		(From North to South)										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	7.80	0.10	0.10	0.10		1.56		
15.00	22.80		Sqm	2	9.20	0.10	0.10	0.10		1.84		
22.80	32.00		Sqm	2	13.00	0.10	0.10	0.10		2.60		
32.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	5.10	0.10	0.10	0.10		1.02		
90.00	95.10											
		7th Main Road										
		(From North to South)										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	2.40	0.10	0.10	0.10		0.48		
15.00	17.40		Sqm	2	9.30	0.10	0.10	0.10		1.86		
17.40	26.70		Sqm	2	15.00	0.10	0.10	0.10		3.00		
26.70	41.70		Sqm	2	3.40	0.10	0.10	0.10		0.68		
41.70	45.10		Sqm	2	14.90	0.10	0.10	0.10		2.98		
45.10	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	8.70	0.10	0.10	0.10		1.74		
75.00	83.70		Sqm	2	15.00	0.10	0.10	0.10		3.00		
83.70	98.70		Sqm	2	1.70	0.10	0.10	0.10		0.34		
98.70	100.40		Sqm	2	3.70	0.10	0.10	0.10		0.74		
100.40	104.10											
		2nd Cross										
		(From North to South)										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	9.30	0.10	0.10	0.10		1.86		
60.00	69.30		Sqm	2	8.20	0.10	0.10	0.10		1.64		
69.30	77.50		Sqm	2	12.50	0.10	0.10	0.10		2.50		
77.50	90.00		Sqm	2	6.40	0.10	0.10	0.10		1.28		
90.00	96.40											
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	25.40		Sqm	2	10.40	0.10	0.10	0.10		2.08		
		8th Main Road										
		North to South										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	19.40		Sqm	2	4.40	0.10	0.10	0.10		0.88		
19.40	30.00		Sqm	2	10.60	0.10	0.10	0.10		2.12		
30.00	37.20		Sqm	2	7.20	0.10	0.10	0.10		1.44		
37.20	45.00		Sqm	2	7.80	0.10	0.10	0.10		1.56		
45.00	46.40		Sqm	2	1.40	0.10	0.10	0.10		0.28		
46.40	64.00		Sqm	2	17.60	0.10	0.10	0.10		3.52		
64.00	75.00		Sqm	2	11.00	0.10	0.10	0.10		2.20		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	108.00		Sqm	2	3.00	0.10	0.10	0.10		0.60		
		Vinayak Nagar										
		6th B Main Road										
		North to South										
0.00	9.10		Sqm	2	9.10	0.10	0.10	0.10		1.82		
9.10	15.00		Sqm	2	5.90	0.10	0.10	0.10		1.18		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	2	4.70	0.10	0.10	0.10		0.94		
15.00	19.70		Sqm	2	10.30	0.10	0.10	0.10		2.06		
19.70	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	4.80	0.10	0.10	0.10		0.96		
75.00	79.80		Sqm	2	8.30	0.10	0.10	0.10		1.66		
79.80	88.10		Sqm	2	1.90	0.10	0.10	0.10		0.38		
88.10	90.00		Sqm	2	1.90	0.10	0.10	0.10		0.38		
90.00	91.90		Sqm	2	5.10	0.10	0.10	0.10		1.02		
91.90	97.00		Sqm	2	2.80	0.10	0.10	0.10		0.56		
97.00	99.80		Sqm	2	5.20	0.10	0.10	0.10		1.04		
99.80	105.00		Sqm	2	3.00	0.10	0.10	0.10		0.60		
105.00	108.00											
		M S Nagar										
		11th A Cross/2nd Main Road										
		(From South to North)										
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
0.00	15.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
15.00	30.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
30.00	45.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
45.00	60.00		Sqm	0.5	5.80	0.10	0.10	0.10		0.29		
60.00	65.80											
		11th Cross Road										
		(From South to North)										
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
0.00	15.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
15.00	30.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
30.00	45.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
45.00	60.00		Sqm	0.5	10.00	0.10	0.10	0.10		0.50		
60.00	70.00		Sqm	0.5	5.00	0.10	0.10	0.10		0.25		
70.00	75.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
75.00	90.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
90.00	105.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
105.00	120.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
120.00	135.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
135.00	150.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
150.00	165.00		Sqm	0.5	3.00	0.10	0.10	0.10		0.15		
165.00	168.00											
		10th Cross Road										
		(From North to South)										
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
0.00	15.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
15.00	30.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
30.00	45.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
45.00	60.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
60.00	75.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
75.00	90.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
90.00	105.00		Sqm	0.5	3.60	0.10	0.10	0.10		0.18		
105.00	108.60		Sqm	0.5	8.80	0.10	0.10	0.10		0.44		
108.60	117.40		Sqm	0.5	2.60	0.10	0.10	0.10		0.13		
117.40	120.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
120.00	135.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
135.00	150.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
150.00	165.00		Sqm	0.5	2.60	0.10	0.10	0.10		0.13		
165.00	167.60											
		10th A Cross										
		(From North to South)										
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
0.00	15.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
15.00	30.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
30.00	45.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
45.00	60.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
60.00	75.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
75.00	90.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
90.00	105.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
105.00	120.00		Sqm	0.5	14.70	0.10	0.10	0.10		0.73		
120.00	134.70											

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		2nd Main Road										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	9.30	0.10	0.10	0.10		1.86		
105.00	114.30		Sqm	2	15.00	0.10	0.10	0.10		3.00		
114.30	129.30		Sqm	2	15.00	0.10	0.10	0.10		3.00		
129.30	144.30		Sqm	2	15.00	0.10	0.10	0.10		3.00		
144.30	159.30		Sqm	2	15.00	0.10	0.10	0.10		3.00		
159.30	174.30		Sqm	2	15.00	0.10	0.10	0.10		3.00		
174.30	189.30		Sqm	2	3.30	0.10	0.10	0.10		0.66		
189.30	192.60											
		2nd Main Road To M S Nagar Road										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	33.70		Sqm	2	3.70	0.10	0.10	0.10		0.74		
		(From South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	197.80		Sqm	2	2.80	0.10	0.10	0.10		0.56		
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	49.80		Sqm	2	4.80	0.10	0.10	0.10		0.96		
49.80	51.90		Sqm	2	2.10	0.10	0.10	0.10		0.42		
		3A Cross Road										
		(From East to West)										
0.00	15.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
15.00	30.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
30.00	41.40		Sqm	0.5	11.40	0.10	0.10	0.10		0.57		
41.40	44.50		Sqm	0.5	3.10	0.10	0.10	0.10		0.16		
		5th Cross Road										
		(From North to South)										
0.00	3.40		Sqm	0.5	3.40	0.10	0.10	0.10		0.17		
3.40	15.00		Sqm	0.5	11.60	0.10	0.10	0.10		0.58		
15.00	30.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
30.00	45.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
45.00	56.60		Sqm	0.5	11.60	0.10	0.10	0.10		0.58		

BBMP (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Hegde Nagara										
		Win Field Garden										
		5th Cross Road (W1941)										
		(From South to North)										
			Sqm	2	2.70	0.10	0.10	0.10		0.54		
0.00	2.70		Sqm	2	12.30	0.10	0.10	0.10		2.46		
2.70	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	5.20	0.10	0.10	0.10		1.04		
180.00	185.20		Sqm	2	2.80	0.10	0.10	0.10		0.56		
185.20	188.00		Sqm	2	2.50	0.10	0.10	0.10		0.50		
188.00	190.50											
		6th Cross Road (W1935)										
		(From South to North)										
			Sqm	2	2.00	0.10	0.10	0.10		0.40		
0.00	2.00		Sqm	2	13.00	0.10	0.10	0.10		2.60		
2.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	181.50		Sqm	2	1.50	0.10	0.10	0.10		0.30		
		9th Cross Road										
		(From South to North)										
			Sqm	2	2.80	0.10	0.10	0.10		0.56		
0.00	2.80		Sqm	2	13.10	0.10	0.10	0.10		2.62		
2.80	15.90		Sqm	2	14.10	0.10	0.10	0.10		2.82		
15.90	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	4.90	0.10	0.10	0.10		0.98		
75.00	79.90		Sqm	2	9.70	0.10	0.10	0.10		1.94		
79.90	89.60		Sqm	2	0.40	0.10	0.10	0.10		0.08		
89.60	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	11.70	0.10	0.10	0.10		2.34		
105.00	116.70		Sqm	2	10.20	0.10	0.10	0.10		2.04		
116.70	126.90		Sqm	2	11.00	0.10	0.10	0.10		2.20		
126.90	137.90											
		MSR Mansion Road										
		(North to South)										
			Sqm	2	5.80	0.10	0.10	0.10		1.16		
0.00	5.80		Sqm	2	3.90	0.10	0.10	0.10		0.78		
5.80	9.70		Sqm	2	5.30	0.10	0.10	0.10		1.06		
9.70	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	5.00	0.10	0.10	0.10		1.00		
45.00	50.00											
		Nisarga Layout										
		7th Cross, Zayan Travels Car Service Centre Road,										
		North To South										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

BMP (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	11.50	0.10	0.10	0.10		2.30		
75.00	90.00											
90.00	101.50											
		West To East										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	0.70	0.10	0.10	0.10		0.14		
15.00	15.70		Sqm	2	14.30	0.10	0.10	0.10		2.86		
15.70	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	1.70	0.10	0.10	0.10		0.34		
45.00	46.70		Sqm	2	4.90	0.10	0.10	0.10		0.98		
46.70	51.60		Sqm	2	4.60	0.10	0.10	0.10		0.92		
51.60	56.20		Sqm	2	8.40	0.10	0.10	0.10		1.68		
56.20	64.60		Sqm	2	10.40	0.10	0.10	0.10		2.08		
64.60	75.00		Sqm	2	1.60	0.10	0.10	0.10		0.32		
75.00	76.60											
		5th Cross Road,										
		North To South										
			Sqm	2	11.10	0.10	0.10	0.10		2.22		
0.00	11.10		Sqm	2	8.90	0.10	0.10	0.10		1.78		
11.10	20.00		Sqm	2	3.80	0.10	0.10	0.10		0.76		
20.00	23.80		Sqm	2	6.20	0.10	0.10	0.10		1.24		
23.80	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	6.90	0.10	0.10	0.10		1.38		
60.00	66.90		Sqm	2	8.10	0.10	0.10	0.10		1.62		
66.90	75.00		Sqm	2	0.60	0.10	0.10	0.10		0.12		
75.00	75.60		Sqm	2	1.20	0.10	0.10	0.10		0.24		
75.60	76.80											
		Mithun White Pearl Apartment Road										
		(East To West)										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	6.40	0.10	0.10	0.10		1.28		
90.00	96.40											
		Venkateshwara Layout										
		3rd Cross Road										
		South to North										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	10.00	0.10	0.10	0.10		2.00		
210.00	220.00											
		4th Cross Road										
		North to South										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

BBMP (Ward No 04)

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	10.00	0.10	0.10	0.10		2.00		
		5th Cross Road										
		North to South										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	10.00	0.10	0.10	0.10		2.00		
		Katgenahalli										
		Muneshwara Provision Store										
		Beside Road										
		Kalidas Layout										
		3rd Main Road										
		(From North to South)										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	6.40	0.10	0.10	0.10		1.28		
			Sqm	2	8.60	0.10	0.10	0.10		1.72		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	8.00	0.10	0.10	0.10		1.60		
		Mk Provision Store Road										
		(From East to West)										
			Sqm	2	11.20	0.10	0.10	0.10		2.24		
			Sqm	2	8.40	0.10	0.10	0.10		1.68		
			Sqm	2	10.40	0.10	0.10	0.10		2.08		
			Sqm	2	10.20	0.10	0.10	0.10		2.04		
			Sqm	2	4.80	0.10	0.10	0.10		0.96		
			Sqm	2	2.50	0.10	0.10	0.10		0.50		
			Sqm	2	12.50	0.10	0.10	0.10		2.50		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
			Sqm	2	5.00	0.10	0.10	0.10		1.00		
		Cross Road - 1										
		(From South to North)										
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
			Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
			Sqm	0.5	13.60	0.10	0.10	0.10		0.68		

From	To
0.00	120.00
105.00	135.00
120.00	150.00
135.00	165.00
150.00	180.00
165.00	195.00
180.00	210.00
195.00	220.00
210.00	
0.00	15.00
15.00	30.00
30.00	45.00
45.00	60.00
60.00	75.00
75.00	90.00
90.00	105.00
105.00	120.00
120.00	135.00
135.00	150.00
150.00	165.00
165.00	180.00
180.00	195.00
195.00	210.00
210.00	220.00
0.00	15.00
15.00	30.00
30.00	45.00
45.00	60.00
60.00	66.40
66.40	75.00
75.00	90.00
90.00	105.00
105.00	113.00
0.00	11.20
11.20	19.60
19.60	30.00
30.00	40.20
40.20	45.00
45.00	47.50
47.50	60.00
60.00	75.00
75.00	90.00
90.00	105.00
105.00	120.00
120.00	135.00
135.00	150.00
150.00	155.00
0.00	15.00
15.00	30.00
30.00	45.00
45.00	60.00
60.00	75.00
75.00	88.60

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road - 2										
		(From North to South)										
			Sqm	0.5	4.30	0.10	0.10	0.10		0.22		
0.00	4.30		Sqm	0.5	10.70	0.10	0.10	0.10		0.54		
4.30	15.00		Sqm	0.5	5.60	0.10	0.10	0.10		0.28		
15.00	20.60		Sqm	0.5	9.40	0.10	0.10	0.10		0.47		
20.60	30.00		Sqm	0.5	10.60	0.10	0.10	0.10		0.53		
30.00	40.60		Sqm	0.5	4.40	0.10	0.10	0.10		0.22		
40.60	45.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
45.00	60.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
60.00	75.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
75.00	90.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
90.00	105.00		Sqm	0.5	15.00	0.10	0.10	0.10		0.75		
105.00	120.00		Sqm	0.5	3.00	0.10	0.10	0.10		0.15		
120.00	123.00											
		Kattigenahalli										
		Durgamba Layout										
		Amulya Family Restaurant Road (N-S)										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
75.00	81.00		Sqm	2	9.00	0.10	0.10	0.10		1.80		
81.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	13.80	0.10	0.10	0.10		2.76		
105.00	118.80		Sqm	2	9.10	0.10	0.10	0.10		1.82		
118.80	127.90		Sqm	2	7.10	0.10	0.10	0.10		1.42		
127.90	135.00		Sqm	2	2.10	0.10	0.10	0.10		0.42		
135.00	137.10		Sqm	2	12.90	0.10	0.10	0.10		2.58		
137.10	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	2.50	0.10	0.10	0.10		0.50		
180.00	182.50		Sqm	2	12.50	0.10	0.10	0.10		2.50		
182.50	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	8.00	0.10	0.10	0.10		1.60		
210.00	218.00											
		Kaustaba House Road #33 (W-E)										
0.00	6.30		Sqm	2	6.30	0.10	0.10	0.10		1.26		
6.30	15.00		Sqm	2	8.70	0.10	0.10	0.10		1.74		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	57.90		Sqm	2	12.90	0.10	0.10	0.10		2.58		
57.90	60.00		Sqm	2	2.10	0.10	0.10	0.10		0.42		
60.00	63.60		Sqm	2	3.60	0.10	0.10	0.10		0.72		
		Sukruthi House Road #26 (S-N)										
0.00	8.30		Sqm	2	8.30	0.10	0.10	0.10		1.66		
8.30	15.00		Sqm	2	6.70	0.10	0.10	0.10		1.34		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	60.50		Sqm	2	0.50	0.10	0.10	0.10		0.10		
60.50	75.00		Sqm	2	14.50	0.10	0.10	0.10		2.90		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	98.70		Sqm	2	8.70	0.10	0.10	0.10		1.74		
98.70	105.00		Sqm	2	6.30	0.10	0.10	0.10		1.26		
105.00	108.20		Sqm	2	3.20	0.10	0.10	0.10		0.64		
108.20	112.20		Sqm	2	4.00	0.10	0.10	0.10		0.80		
112.20	120.00		Sqm	2	7.80	0.10	0.10	0.10		1.56		
120.00	125.80		Sqm	2	5.80	0.10	0.10	0.10		1.16		
125.80	135.70		Sqm	2	9.90	0.10	0.10	0.10		1.98		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Sqm	2	8.20	0.10	0.10	0.10		1.64		
143.70	143.90		Sqm	2	6.10	0.10	0.10	0.10		1.22		
143.90	150.00		Sqm	2	14.30	0.10	0.10	0.10		2.86		
150.00	164.30											
		SP Singh House Road (E-W)										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	4.10	0.10	0.10	0.10		0.82		
15.00	19.10		Sqm	2	10.90	0.10	0.10	0.10		2.18		
19.10	30.00		Sqm	2	4.20	0.10	0.10	0.10		0.84		
30.00	34.20											
		Form mrd Main To Muneshwara provsion										
			Sqm	2	1.70	0.10	0.10	0.10		0.34		
0.00	1.70		Sqm	2	13.30	0.10	0.10	0.10		2.66		
1.70	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	2.80	0.10	0.10	0.10		0.56		
75.00	77.80		Sqm	2	12.20	0.10	0.10	0.10		2.44		
77.80	90.00		Sqm	2	5.90	0.10	0.10	0.10		1.18		
90.00	95.90		Sqm	2	9.10	0.10	0.10	0.10		1.82		
95.90	105.00		Sqm	2	12.90	0.10	0.10	0.10		2.58		
105.00	117.90		Sqm	2	2.10	0.10	0.10	0.10		0.42		
117.90	120.00		Sqm	2	4.80	0.10	0.10	0.10		0.96		
120.00	124.80											
		Green Garden Main Road										
		(West to East)										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	12.70	0.10	0.10	0.10		2.54		
30.00	42.70		Sqm	2	2.30	0.10	0.10	0.10		0.46		
42.70	45.00		Sqm	2	8.70	0.10	0.10	0.10		1.74		
45.00	53.70		Sqm	2	6.30	0.10	0.10	0.10		1.26		
53.70	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	6.90	0.10	0.10	0.10		1.38		
120.00	126.90		Sqm	2	3.10	0.10	0.10	0.10		0.62		
126.90	130.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
130.00	145.00		Sqm	2	9.30	0.10	0.10	0.10		1.86		
145.00	154.30		Sqm	2	5.70	0.10	0.10	0.10		1.14		
154.30	160.00		Sqm	2	11.40	0.10	0.10	0.10		2.28		
160.00	171.40											
		Cross Road-4										
		(South to North)										
0.00	1.60		Sqm	2	1.60	0.10	0.10	0.10		0.32		
1.60	15.00		Sqm	2	13.40	0.10	0.10	0.10		2.68		
15.00	23.50		Sqm	2	8.50	0.10	0.10	0.10		1.70		
23.50	30.00		Sqm	2	6.50	0.10	0.10	0.10		1.30		
30.00	33.70		Sqm	2	3.70	0.10	0.10	0.10		0.74		
		Sri Ganga House Road										
		East to West										
0.00	3.80		Sqm	2	3.80	0.10	0.10	0.10		0.76		
3.80	13.20		Sqm	2	9.40	0.10	0.10	0.10		1.88		
13.20	15.00		Sqm	2	1.80	0.10	0.10	0.10		0.36		
15.00	27.40		Sqm	2	12.40	0.10	0.10	0.10		2.48		
27.40	30.00		Sqm	2	2.60	0.10	0.10	0.10		0.52		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	69.30		Sqm	2	9.30	0.10	0.10	0.10		1.86		
		Cross Road-3										
		(North to South)										
0.00	1.70		Sqm	2	1.70	0.10	0.10	0.10		0.34		
1.70	15.00		Sqm	2	13.30	0.10	0.10	0.10		2.66		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	46.10		Sqm	2	1.10	0.10	0.10	0.10		0.22		
46.10	48.90		Sqm	2	2.80	0.10	0.10	0.10		0.56		
		Cross Road 2 (South to North)										
0.00	11.80		Sqm	2	11.80	0.10	0.10	0.10		2.36		
11.80	15.00		Sqm	2	3.20	0.10	0.10	0.10		0.64		
15.00	21.10		Sqm	2	6.10	0.10	0.10	0.10		1.22		
21.10	30.00		Sqm	2	8.90	0.10	0.10	0.10		1.78		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	100.30		Sqm	2	10.30	0.10	0.10	0.10		2.06		
100.30	102.40		Sqm	2	2.10	0.10	0.10	0.10		0.42		
		Cross Road 1 (North to South)										
0.00	2.90		Sqm	2	2.90	0.10	0.10	0.10		0.58		
2.90	15.00		Sqm	2	12.10	0.10	0.10	0.10		2.42		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	102.30		Sqm	2	12.30	0.10	0.10	0.10		2.46		
		Pyramid apartment main road (East to West)										
0.00	1.10		Sqm	2	1.10	0.10	0.10	0.10		0.22		
1.10	2.40		Sqm	2	1.30	0.10	0.10	0.10		0.26		
2.40	4.70		Sqm	2	2.30	0.10	0.10	0.10		0.46		
4.70	12.40		Sqm	2	7.70	0.10	0.10	0.10		1.54		
12.40	15.00		Sqm	2	2.60	0.10	0.10	0.10		0.52		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	32.00		Sqm	2	2.00	0.10	0.10	0.10		0.40		
32.00	45.00		Sqm	2	13.00	0.10	0.10	0.10		2.60		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	81.10		Sqm	2	6.10	0.10	0.10	0.10		1.22		
81.10	90.00		Sqm	2	8.90	0.10	0.10	0.10		1.78		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	128.00		Sqm	2	8.00	0.10	0.10	0.10		1.60		
		Cross Road 3 Near Pyramid apartment (North to South)										
0.00	2.90		Sqm	2	2.90	0.10	0.10	0.10		0.58		
2.90	15.00		Sqm	2	12.10	0.10	0.10	0.10		2.42		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	44.00		Sqm	2	14.00	0.10	0.10	0.10		2.80		
		Cross Road 2 Near Pyramid apartment (North to South)										
0.00	3.60		Sqm	2	3.60	0.10	0.10	0.10		0.72		
3.60	15.00		Sqm	2	11.40	0.10	0.10	0.10		2.28		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	32.80		Sqm	2	2.80	0.10	0.10	0.10		0.56		
32.80	42.30		Sqm	2	9.50	0.10	0.10	0.10		1.90		
42.30	45.10		Sqm	2	2.80	0.10	0.10	0.10		0.56		
45.10	48.30		Sqm	2	3.20	0.10	0.10	0.10		0.64		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road 1 Near Pyramid apartment										
		(North to South)										
0.00	4.50		Sqm	2	4.50	0.10	0.10	0.10		0.90		
4.50	15.00		Sqm	2	10.50	0.10	0.10	0.10		2.10		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	51.70		Sqm	2	6.70	0.10	0.10	0.10		1.34		
51.70	52.20		Sqm	2	0.50	0.10	0.10	0.10		0.10		
52.20	60.00		Sqm	2	7.80	0.10	0.10	0.10		1.56		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	127.20		Sqm	2	7.20	0.10	0.10	0.10		1.44		
		Car 24 Beside Road From Agrahara Main Road to Lake										
		East to West										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	27.00		Sqm	2	12.00	0.10	0.10	0.10		2.40		
27.00	30.00		Sqm	2	3.00	0.10	0.10	0.10		0.60		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	255.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
255.00	270.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
270.00	285.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
285.00	300.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
300.00	315.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
315.00	330.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
330.00	345.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
345.00	360.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
360.00	375.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
375.00	390.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
390.00	405.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
405.00	410.00		Sqm	2	5.00	0.10	0.10	0.10		1.00		
410.00	419.00		Sqm	2	9.00	0.10	0.10	0.10		1.80		
419.00	420.00		Sqm	2	1.00	0.10	0.10	0.10		0.20		
420.00	435.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
435.00	450.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
450.00	465.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
465.00	480.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
480.00	495.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
495.00	510.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
510.00	512.00		Sqm	2	2.00	0.10	0.10	0.10		0.40		
512.00	525.00		Sqm	2	13.00	0.10	0.10	0.10		2.60		
525.00	540.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
540.00	546.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
		Cross Road-1										
		South to North										
0.00	6.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
6.00	12.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
12.00	15.00		Sqm	2	3.00	0.10	0.10	0.10		0.60		
15.00	19.00		Sqm	2	4.00	0.10	0.10	0.10		0.80		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Cross Road-2										
		South to north										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	7.70	0.10	0.10	0.10		1.54		
60.00	67.70		Sqm	2	2.00	0.10	0.10	0.10		0.40		
67.70	69.70											
		MCECHS layout										
		22nd Cross Road										
		North to South										
			Sqm	2	15.00	0.10	0.10	0.10		3.00		
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	6.10	0.10	0.10	0.10		1.22		
135.00	141.10											
		Vidhana Soudha Layout										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	29.30		Sqm	2	14.30	0.10	0.10	0.10		2.86		
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	117.80		Sqm	2	12.80	0.10	0.10	0.10		2.56		
117.80	125.10		Sqm	2	7.30	0.10	0.10	0.10		1.46		
125.10	135.00		Sqm	2	9.90	0.10	0.10	0.10		1.98		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	150.90		Sqm	2	0.90	0.10	0.10	0.10		0.18		
150.90	165.00		Sqm	2	14.10	0.10	0.10	0.10		2.82		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	184.90		Sqm	2	4.90	0.10	0.10	0.10		0.98		
184.90	193.50		Sqm	2	8.60	0.10	0.10	0.10		1.72		
193.50	195.00		Sqm	2	1.50	0.10	0.10	0.10		0.30		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	255.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
255.00	258.00		Sqm	2	3.00	0.10	0.10	0.10		0.60		
258.00	265.10		Sqm	2	7.10	0.10	0.10	0.10		1.42		
265.10	270.00		Sqm	2	4.90	0.10	0.10	0.10		0.98		
270.00	285.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
285.00	291.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
291.00	299.80		Sqm	2	8.80	0.10	0.10	0.10		1.76		
299.80	300.00		Sqm	2	0.20	0.10	0.10	0.10		0.04		
300.00	301.00		Sqm	2	1.00	0.10	0.10	0.10		0.20		
301.00	307.30		Sqm	2	6.30	0.10	0.10	0.10		1.26		
307.30	315.00		Sqm	2	7.70	0.10	0.10	0.10		1.54		
315.00	323.00		Sqm	2	8.00	0.10	0.10	0.10		1.60		
323.00	332.00		Sqm	2	9.00	0.10	0.10	0.10		1.80		
332.00	343.00		Sqm	2	11.00	0.10	0.10	0.10		2.20		
343.00	345.00		Sqm	2	2.00	0.10	0.10	0.10		0.40		
345.00	358.90		Sqm	2	13.90	0.10	0.10	0.10		2.78		
358.90	368.10		Sqm	2	9.20	0.10	0.10	0.10		1.84		
368.10	375.00		Sqm	2	6.90	0.10	0.10	0.10		1.38		
375.00	382.60		Sqm	2	7.60	0.10	0.10	0.10		1.52		
382.60	391.90		Sqm	2	9.30	0.10	0.10	0.10		1.86		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
393.30	400.00		Sqm	2	1.40	0.10	0.10	0.10		0.28		
400.00	405.00		Sqm	2	6.70	0.10	0.10	0.10		1.34		
405.00	420.00		Sqm	2	5.00	0.10	0.10	0.10		1.00		
420.00	435.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
435.00	444.20		Sqm	2	15.00	0.10	0.10	0.10		3.00		
444.20	446.30		Sqm	2	9.20	0.10	0.10	0.10		1.84		
446.30	456.40		Sqm	2	2.10	0.10	0.10	0.10		0.42		
456.40	465.00		Sqm	2	10.10	0.10	0.10	0.10		2.02		
465.00	480.00		Sqm	2	8.60	0.10	0.10	0.10		1.72		
480.00	495.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
495.00	510.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
510.00	525.20		Sqm	2	15.00	0.10	0.10	0.10		3.00		
525.20	540.00		Sqm	2	15.20	0.10	0.10	0.10		3.04		
540.00	555.00		Sqm	2	14.80	0.10	0.10	0.10		2.96		
555.00	560.90		Sqm	2	15.00	0.10	0.10	0.10		3.00		
560.90	562.70		Sqm	2	5.90	0.10	0.10	0.10		1.18		
			Sqm	2	1.80	0.10	0.10	0.10		0.36		
		Total Executed Quantity								**1262.32**	**459.29**	**579771.00**
		Tender Quantity								**1446.08**		
	E1	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 (For Grading -V Material) (PWD SR 21-22 Vol III Pg no 19 Item No 4.1 A (v))										
		Measurements taken on										
		Car 24 Beside Road From Agrahara Main Road to Lake East to West										
0.00	15.00		Cum	1	15.00	4.80	4.60	4.70	0.15	10.58		
15.00	27.00		Cum	1	12.00	4.60	4.65	4.63	0.15	8.33		
27.00	30.00		Cum	1	3.00	5.40	5.70	5.55	0.15	2.50		
30.00	45.00		Cum	1	15.00	5.70	5.70	5.70	0.15	12.83		
45.00	60.00		Cum	1	15.00	5.70	6.30	6.00	0.15	13.50		
60.00	75.00		Cum	1	15.00	6.30	6.30	6.30	0.15	14.18		
75.00	90.00		Cum	1	15.00	6.30	6.50	6.40	0.15	14.40		
90.00	105.00		Cum	1	15.00	6.50	6.65	6.58	0.15	14.79		
105.00	120.00		Cum	1	15.00	6.65	6.40	6.53	0.15	14.68		
120.00	135.00		Cum	1	15.00	6.40	6.20	6.30	0.15	14.18		
135.00	150.00		Cum	1	15.00	6.20	6.10	6.15	0.15	13.84		
150.00	165.00		Cum	1	15.00	6.10	6.30	6.20	0.15	13.95		
165.00	180.00		Cum	1	15.00	6.30	6.10	6.20	0.15	13.95		
180.00	195.00		Cum	1	15.00	6.10	6.25	6.18	0.15	13.89		
195.00	210.00		Cum	1	15.00	6.25	6.50	6.38	0.15	14.34		
210.00	225.00		Cum	1	15.00	6.50	6.40	6.45	0.15	14.51		
225.00	240.00		Cum	1	15.00	6.40	6.50	6.45	0.15	14.51		
240.00	255.00		Cum	1	15.00	6.50	6.65	6.58	0.15	14.79		
255.00	270.00		Cum	1	15.00	6.65	6.70	6.68	0.15	15.02		
270.00	285.00		Cum	1	15.00	6.70	6.45	6.58	0.15	14.79		
285.00	300.00		Cum	1	15.00	6.45	6.20	6.33	0.15	14.23		
300.00	315.00		Cum	1	15.00	6.20	6.10	6.15	0.15	13.84		
315.00	330.00		Cum	1	15.00	6.10	6.10	6.10	0.15	13.73		
330.00	345.00		Cum	1	15.00	6.10	6.00	6.05	0.15	13.61		
345.00	360.00		Cum	1	15.00	6.00	6.60	6.30	0.15	14.18		
360.00	375.00		Cum	1	15.00	6.60	6.00	6.30	0.15	14.18		
375.00	390.00		Cum	1	15.00	6.00	6.10	6.05	0.15	13.61		
390.00	405.00		Cum	1	15.00	6.10	6.30	6.20	0.15	13.95		
405.00	410.00		Cum	1	5.00	6.30	6.40	6.35	0.15	4.76		
410.00	419.00		Cum	1	9.00	4.70	4.50	4.60	0.15	6.21		
419.00	420.00		Cum	1	1.00	6.30	6.30	6.30	0.15	0.95		
420.00	435.00		Cum	1	15.00	6.30	6.30	6.30	0.15	14.18		
435.00	450.00		Cum	1	15.00	6.30	6.80	6.55	0.15	14.74		
450.00	465.00		Cum	1	15.00	6.80	7.10	6.95	0.15	15.64		
465.00	480.00		Cum	1	15.00	7.10	5.80	6.45	0.15	14.51		
480.00	495.00		Cum	1	15.00	5.80	5.20	5.50	0.15	12.38		
495.00	510.00		Cum	1	15.00	5.20	3.95	4.58	0.15	10.29		
510.00	512.00		Cum	1	2.00	3.95	3.80	3.88	0.15	1.16		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
[illegible]2.00	525.00		Cum	1	13.00	4.70	5.45	5.08	0.15	9.90		
525.00	540.00		Cum	1	15.00	5.45	6.10	5.78	0.15	12.99		
540.00	546.00		Cum	1	6.00	6.10	5.50	5.80	0.15	5.22		
		Total Executed Quantity								497.79	2607.52	1298006.00
											Sub Total	50315990.00
											GST @18%	9056879.00
											TOTAL AMOUNT	59372869.00

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

Technical Sanction
Accorded For Rs. 59372,869.00
Head of A/C. P 3867
CER NO : 82 Dt: 14/03/23

TA